

#### STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION



# BAR SPLICER ASSEMBLY ALTERNATIVES

WELDED SECTIONS

\*\* Heavy Hex Nuts conforming to ASTM A 563, Grade C. D or DH may be used.




### FOR INTEGRAL OR SEMI-INTEGRAL ABUTMENTS

Bar Splicer for #5 bar							
Min.	Capacity	= 23	.0 kip	5 -	tensi	on	
Min.	Pull-out	Stren	gth =	9.2	kips	-	tension
No.	Required	= 80	(NB)	; 80	(SB)		

THOUVENOT, WADE & MOERCHEN, INC.




DESIGNED	_	ALN
CHECKED		BWP
DRAWN	_	JMI, DEH
CHECKED	**	ALN
BSD-1		9-01-03



### INSTALLATION AND SETTING METHODS

"A": Set bar splicer assembly by means of a template bolt. "B" : Set bar splicer assembly by nailing to wood forms or cementing to steel forms. (E): Indicates epoxy coating.



# FOR PILE BENT ABUTMENTS

	Ваг	r Splicer for #5 bar
Min.	Capacity	= 23.0 kips - tension
Min.	Pull-out	Strength = 9.2 kips - tension
No.	Required	=

SHEETS SHEET NO. 18 FAP 24 SHEETS 52 38 147BR ST. CLAIR 805

Contract No. 76393

### **NOTES**

Bar splicer assemblies shall be of an approved type and shall develop in tension at least 125 percent of the yield strength of the lapped reinforcement bars.

Splicer rods shall be of minimum 60 ksi yield strength, threaded or coiled full length. All reinforcement bars shall be lapped and tied to the splicer rods or dowel bars. Bar splicer assemblies shall be epoxy coated according to the requirements for reinforcement bars.

Other systems of similar design may be submitted to the Engineer for approval. Approval shall be based on certified test results from an approved testing laboratory that the proposed bar splicer assembly satisfies the following requirements:

- Minimum Capacity = 1.25 x fy x A<sub>t</sub>
- (Tension III Kips)
  Minimum \*Pull-out Strength = 1.25 x  $fs_{allow}$  x  $A_1$


Where fy = Yield strength of lapped reinforcement bars in ksi.

fs<sub>allow</sub>= Allowable tensile stress in lapped reinforcement bars in ksi (Service Load)

A<sub>t</sub> = Tensile stress area of lapped reinforcement bars. \* = 28 day concrete

	BAR SPLIC	ER ASSEMBLI	ES		
Bar Size to be Spliced	_	Strength Requirements			
	Splicer Rod or Dowel Bar Length	Min. Capacity kips - tension	Min. Pull-Out Strength kips - tension		
#4	1'-8''	14.7	5.9		
#5	2'-0"	23.0	9,2		
#6	2'-7"	33.1	13.3		
#7	3'-5''	45.1	18.0		
#8	4'-6"	58.9	23.6		
#9	5′-9″	75.0	30.0		
#10	7'-3''	95.0	38.0		
#11	9'-0''	117.4	46.8		

Bar splicer assemblies shall be according to Section 508 of the Standard Specifications, except as noted. The furnishing and installation of bar splicer assemblies will be measured and paid for at the contract unit price each for "BAR SPLICERS."



#### STANDARD

Bar Size	No. Assemblies Required	Location

ILLINOIS ROUTE 161 OVER TRIBUTARY TO SCHOENBERGER CREEK F.A.P. ROUTE 805 - SECTION 147BR ST. CLAIR COUNTY STATION 101+03.82 STRUCTURE NO. 082-0102 (N.B.) STRUCTURE NO. 082-0103 (S.B.)

BAR SPLICER ASSEMBLY DETAILS