

FAI ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
255	(82-41-5)-1R	ST. CLAIR	8	2
STA.		TO STA.		
CONTRACT NO.: 76571				

HIGHWAY STANDARDS

- 000001-04
- 701101-01
- 701106-01
- 701400-02
- 701406-04
- 701411-03
- 702001-06

GENERAL NOTES

1. THE STANDARDS AND REVISIONS LISTED APPLY TO THIS PROJECT.
2. ILLINOIS STATE LAW REQUIRES A 48-HOUR NOTICE TO BE GIVEN TO UTILITIES BEFORE DIGGING. FIELD MARKING OF FACILITIES MAY BE OBTAINED BY CONTACTING J.U.L.I.E. OR FOR NON-MEMBERS, THE UTILITY COMPANY DIRECTLY. AGENCIES KNOWN TO HAVE FACILITIES WITHIN THE PROJECT AREA ARE AS FOLLOWS:
 - * AMERENIP
 - * AMERENUE
 - * CITY OF CENTREVILLE
 - * COMMONFIELDS OF CAHOKIA PUBLIC WATER DISTRICT
 - * ILLINOIS AMERICAN WATER CO.
 - * LEVEL 3 COMMUNICATIONS, LLC
 - * SBC

(MEMBERS OF J.U.L.I.E. (800) 892-0123 ARE INDICATED BY *. NON J.U.L.I.E. MEMBERS MUST BE NOTIFIED INDIVIDUALLY.)
3. IF SECTION OR SUB-SECTION MONUMENTS ARE ENCOUNTERED, THE ENGINEER SHALL BE NOTIFIED BEFORE SUCH MONUMENTS ARE REMOVED. THE CONTRACTOR SHALL PROTECT AND CAREFULLY PRESERVE ALL PROPERTY MARKS AND MONUMENTS UNTILL THE OWNER, AN AUTHORIZED SURVEYOR, OR AGENT HAS WITNESSED OR OTHERWISE REFERENCED THEIR LOCATION.
4. AN ESTIMATED 0.5 ACRE OF SEEDING CLASS 2 IS INCLUDED ON THE PLANS TO SEED ALL DISTURBED AREAS AS DIRECTED BY THE RESIDENT ENGINEER. THE QUANTITY WAS INCLUDE SHOULD THE CONTRACTOR NEED MACHINERY BEHIND THE WALL. ANY RUTS OR OTHER DAMAGE TO THE EXISTING FORE SLOPE INCURRED BY THE CONTRACTORS OPERATIONS SHALL BE REPAIRED BY THE CONTRACTOR, AT THE CONTRACTOR'S EXPENSE.
5. "ROAD CONSTRUCTION AHEAD" SIGNS SHALL BE PLACED IN ADVANCE OF WORK IS BEING CONDUCTED AS DIRECTED BY THE RESIDENT ENGINEER. ALL CONSTRUCTION SIGNS SHALL BE FLUORESCENT 48"x48" ORANGE. THESE ITEMS SHALL BE INCLUDED IN THE COST OF THE TRAFFIC CONTROL AND PROTECTION.
6. THE CONTRACTOR SHALL VERIFY ALL DIMENSIONS AND CONDITIONS IN THE FIELD, INCLUDING EXISTING STEEL POST, PRIOR TO CONSTRUCTION AND ORDERING OF MATERIALS.
7. THE EXISTING GUARDRAIL SHALL REMAIN IN PLACE. ANY DAMAGE TO THE GUARDRAIL INCURRED BY THE CONTRACTOR'S OPERATIONS SHALL BE REPAIRED BY THE CONTRACTOR, AT THE CONTRACTOR'S EXPENSE AND AS DIRECTED BY THE ENGINEER.
8. TWO LANES OF TRAFFIC ON THE MAINLINE SHALL REMAIN OPEN AT ALL TIMES.
9. TRAFFIC CONTROL AND PROTECTION, STANDARD 701411 SHALL BE CONFIGURED TO REPLACE SOUND WALL PANELS ON RAMP E. NO ADDITIONAL COMPENSATION SHALL BE INCLUDED.
10. THE PANELS SHALL BE INSTALLED SO THAT THE TOP EDGE OF THE PANELS ARE IN A LEVEL HORIZONTAL POSITION EVEN WITH THE TOP EDGE OF EXISTING POST.
11. A QUANTITY OF AGGREGATE SHOULDERS TYPE B IS PROVIDED SO THAT THE PANELS ARE PLACED ON THE AGGREGATE BASE. THERE IS AN EXISTING AGGREGATE IN PLACE. THE QUANTITY IS INCLUDED TO LEVEL ANY AREAS DETERMINED BY THE ENGINEER. ANY EXCAVATION REQUIRED SHALL BE INCLUDED IN THE PAY ITEM "ABSORPTIVE NOISE ABATEMENT WALL PANELS".

COMMITMENTS

NONE

PLAN	SURVEYED	DATE
NOTE BOOK	BY	
NO.		
	ADJUSTED	
	ALIGNED	
	CHECKED	
	BY	
	DATE	

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
HIGHWAY STANDARDS, GENERAL NOTES AND COMMITMENTS
 FAI ROUTE 255
 SECTION (83-41-5)1R
 ST. CLAIR COUNTY
 DRAWN BY:

PLOT DATE: *DATE-TIME*

DATE
 DATE-TIME
 DATE-TIME
 REF
 REF