

FAP ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO
304	GRS-2	JERSEY	12	7

STA. \_\_\_\_\_ TO STA. \_\_\_\_\_  
 CONTRACT NUMBER: 76942

### PAVEMENT SCHEDULE

LOCATION	LANE	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVEL BINDER (MACHINE METHOD), SUPERPAVE, N70	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N70	AGGREGATE SHOULDERS, TYPE B	BITUMINOUS SHOULDERS, SUPERPAVE	INCIDENTAL BITUMINOUS SURFACING
		TON	TON	TON	TON	TON	TON	TON	TON
IL 100/IL 16									
STA TO STA									
742+66 TO 745+00	BOTH	0.42	2.0	38	5	57	10.8		
745+00 TO 747+50	BOTH	0.45	2.2	40	5	61	11.6		
747+50 TO 750+00	BOTH	0.45	2.2	40	5	61	11.6		
750+00 TO 752+50	BOTH	0.45	2.2	40	5	61	11.6		
752+50 TO 754+29	BOTH	0.32	1.6	29	4	43	8.3		
754+29 TO 754+97	LT	0.06	0.3	6	1	8	3.1		
754+29 TO 754+97	RT	0.06	0.3	5		8		0.8	
754+97 TO 756+54	BOTH	0.26	1.3	23		35		3.9	
757+42 TO 758+97	BOTH	0.26	1.2	23		35		3.9	
758+97 TO 759+64	RT	0.06	0.3	5		8		0.8	
758+97 TO 759+64	LT	0.06	0.3	5	1	8	3.1		
759+64 TO 762+50	BOTH	0.52	2.5	46	6	69	13.2		
762+50 TO 765+00	BOTH	0.45	2.2	40	5	61	11.6		
765+00 TO 767+50	BOTH	0.45	2.2	40	5	61	11.6		
767+50 TO 770+00	BOTH	0.45	2.2	40	5	61	11.6		
770+00 TO 772+50	BOTH	0.45	2.2	40	5	61	11.6		
772+50 TO 775+00	BOTH	0.45	2.2	40	5	61	11.6		
775+00 TO 777+50	BOTH	0.45	2.2	40	5	61	11.6		
777+50 TO 779+57	BOTH	0.37	1.8	33	5	50	9.6		
779+57 TO 780+13	LT	0.05	0.2	5	1	7	2.6		
779+57 TO 780+13	RT	0.05	0.2	4		6		0.7	
780+13 TO 781+82	BOTH	0.28	1.4	25		38		4.2	
783+45 TO 785+13	BOTH	0.28	1.3	25		38		4.2	
785+13 TO 786+47	RT	0.11	0.5	10		15		1.7	
785+13 TO 786+47	LT	0.12	0.6	11	3	16	6.2		
786+47 TO 787+50	BOTH	0.19	0.9	17	2	25	4.8		
787+50 TO 790+00	BOTH	0.45	2.2	40	5	61	11.6		
792+50 TO 795+00	BOTH	0.45	2.2	40	5	61	11.6		
795+00 TO 796+00	BOTH	0.18	0.9	16	2	24	4.6		
ELDRED RD									
STA TO STA									
577+57 TO 578+00	BOTH	0.10	0.5	9		13	5.9		
578+00 TO 579+00	BOTH	0.23	1.1	21		31	4.6		
579+00 TO 579+57	BOTH	0.22	1.0	19		29	2.6		
BUSBY LANE									
STA									
745+60									5.3
SHAW HOLLOW ROAD									
STA									
755+60									6.4
BUTT JOINT AREAS									
IL 16/IL 100									
STA TO STA									
742+16 TO 742+66	BOTH	0.04	0.2			15	2.3		
756+04 TO 756+54	BOTH	0.04	0.2			15	2.3		
757+42 TO 757+92	BOTH	0.04	0.2			15	2.3		
781+32 TO 781+82	BOTH	0.04	0.2			15	2.3		
783+45 TO 783+95	BOTH	0.04	0.2			15	2.3		
796+00 TO 796+50	BOTH	0.04	0.2			15	2.3		
ELDRED RD									
STA TO STA									
577+07 TO 577+57	BOTH	0.05	0.2			19	2.3		
TOTALS									
		9.4	45	820	91	1320	331	20	12

\*AGGREGATE WEDGE QUANTITY IS BASED 3' WIDE WEDGE 3" THICK AT PAVEMENT PLUS 50% FOR LOW AREAS

### PAVEMENT MARKING

LOCATION	STATION TO STATION	PAINT PAVEMENT MARKING				RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	RAISED REFLECTIVE PAVEMENT MARKER	PRISMATIC CURB REFLECTORS	PAINT CURB	PAINT MEDIAN
		4"		8"						
		SOLID WHITE EDGE LINE	SOLID YELLOW - AROUND MEDIAN	YELLOW SKIP-DASH	YELLOW DIAGONALS					
		FOOT	FOOT	FOOT	FOOT	EACH	EACH	EACH	FOOT	SQ FT
IL 16										
742+16 TO 756+54		2776		350		18	18			
757+42 TO 781+82		4880		610		30	30			
783+45 TO 796+50		2510		320		16	16			
ELDRED RD										
579+44 TO 577+57			464		72			18	96	53
SUB-TOTALS		10166	464	1280	72	64	64	18	96	53
TOTALS			11910		72	64	64	18	96	53

### CONCRETE SCHEDULE

LOCATION	C&G REMOVAL	MEDIAN SURFACE REMOVAL	MEDIAN REMOVAL PARTIAL DEPTH	C&G TYPE B, 9.06*	CONC MEDIAN (RAMPED NOSES)	MEDIAN SURFACE	CONC. BASE COURSE 10"	REINFORCEMENT BARS
	FT	SQ FT	SQ FT	FT	SQ FT	SQ FT	SQ YD	LB
ELDRED RD.	126	776	173	51	79	310	51	500
TOTAL	126	776	173	51	79	310	51	500

\*GUTTER FLAG VARIES 0.5' TO 1.5' FROM STA 578+55 TO STA 578+73

ILLINOIS DEPARTMENT OF TRANSPORTATION

### SCHEDULES OF QUANTITIES

FAP ROUTE 304 (IL 16/IL 100)  
 SECTION 6RS-2  
 JERSEY COUNTY

REVISIONS	
NAME	DATE

DRAWN BY:

PLOT DATE = 3/29/2006  
 FILE NAME = c:\projects\aed81625\plan\plan68505.dgn  
 PLOT SCALE = 0.80000 / IN.  
 REFERENCE = REF#