

SUMMARY OF QUANTITIES, CONTINUED

SPCLTY	IDOT CODE	ITEM	UNIT	TOTAL QUANTITY	ROADWAY I000-2A	SIGNAL Y031-1F	SIDEWALK SFTY-1B
	67100100	MOBILIZATION	L SUM	1	1		
	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
	70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
	70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
	70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	3	3		
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10311	10311		
	70300200	TEMPORARY PAVEMENT MARKING	FOOT	41244	41244		
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3437	3437		
**	72000100	SIGN PANEL - TYPE 1	SQ FT	300	200	100	
**	72900100	METAL POST - TYPE A	FOOT	632	632		
**	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	858	858		
**	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	33625	33625		
**	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2654	2654		
**	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1296	1296		
**	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	326	326		
**	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	561	561		
**	78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8		
**	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
**	78300100	PAVEMENT MARKING REMOVAL	SQ FT	3437	3437		
**	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	208	208		
**	81000300	CONDUIT IN TRENCH, 1" DIA., GALVANIZED STEEL	FOOT	15	15		
**	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	5631		5631	
**	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	287		287	
**	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	48		48	
**	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	30		30	
**	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	581		581	
**	81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	71		71	
**	81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	231		231	
**	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	520		520	
**	81400100	HANDHOLE	EACH	18		18	
**	81400200	HEAVY DUTY HANDHOLE	EACH	11		11	
**	81400300	DOUBLE HANDHOLE	EACH	3		3	
**	81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6002		6002	
**	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	20	20		
**	84200700	LIGHTING FOUNDATION REMOVAL	EACH	2	2		
**	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2		2	
**	85000200	MAINTAINANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		2	
**	85700200	FULL - ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2		2	
**	85700300	FULL - ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1		1	
**	86000100	MASTER CONTROLLER	EACH	1		1	
**	86400100	TRANSCIEVER - FIBER OPTIC	EACH	3		3	
**	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	813		813	
**	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	2541		2541	
**	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	4526		4526	
**	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	2468		2468	
**	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4619		4619	
**	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6, 2C	FOOT	463		463	
**	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 10 FT.	EACH	1		1	
**	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 14 FT.	EACH	5		5	
**	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	4		4	
**	87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	2		2	


Deleted
6-12-06

Revised
6-12-06

F.A.U. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2774	99-00073-00-WR	COOK	116	5
STA.	TO STA.		FED. ROAD DIST. NO. 1	
	ILLINOIS		FED. AID PROJECT CMM-7003 (750)	
CONTRACT NO. 83727				

I:\GARFF\001146\DWSS\20146-SMKY-CTT.dwg
 P:\0146\001146.dwg
 5/18/06 10:49:37 am
 6/2/06 By: E. Woodman, Inc.
 State of Illinois - Professional Design Firm
 License No. - 184-001121 - Expires 4-30-06

CONSULTANTS	REV. NO.	DATE	DESCRIPTION
	1	4-28-06	PER IDOT AND COOK COUNTY COMMENTS
	2	5-8-06	PER IDOT COMMENTS
* - REFER TO EQUIPMENT MANUFACTURER'S SHOP DRAWINGS			



Baxler & Woodman
 Crystal Lake, Illinois 815.459.1260
 Burlington, Wisconsin 262.768.7934
 Mokena, Illinois 708.478.2090
 DeKalb, Illinois 815.797.3111
 Grayland, Illinois 815.223.5098
 Rockford, Illinois 815.480.1551
 Plainfield, Illinois 815.509.7425

CITY OF OAK FOREST, ILLINOIS
OAK PARK AVENUE PROJECT

SUMMARY OF QUANTITIES

DESIGNED BY	SCALE
NJP	NONE
DRAWN BY	PROJECT NO.
LUK	020146
CHECKED BY	SHEET NO.
NJP	5 OF 116
DATE	1-20-05