

# SUMMARY OF QUANTITIES, CONTINUED

SPCLTY	IDOT CODE	ITEM	UNIT	TOTAL QUANTITY	ROADWAY 1000-2A	SIGNAL Y031-1F	SIDEWALK SFTY-1B
**	87700170	STEEL MAST ARM ASSEMBLY AND POLE, 26 FT.	EACH	2		2	
**	87700180	STEEL MAST ARM ASSEMBLY AND POLE, 28 FT.	EACH	4		4	
**	87700190	STEEL MAST ARM ASSEMBLY AND POLE, 30 FT.	EACH	1		1	
**	87700280	STEEL MAST ARM ASSEMBLY AND POLE, 48 FT.	EACH	1		1	
**	87800100	CONCRETE FOUNDATION, TYPE A	FOOT	40		40	
**	87800200	CONCRETE FOUNDATION, TYPE D	FOOT	12		12	
**	87800400	CONCRETE FOUNDATION, TYPE E 30" DIAMETER	FOOT	150		150	
**	87800415	CONCRETE FOUNDATION, TYPE E 36" DIAMETER	FOOT	15		15	
**	87900200	DRILL EXISTING HANDHOLE	EACH	3		3	
**	88000170	SIGNAL HEAD, 1-FACE, 3-SECTION, MAST ARM MOUNTED	EACH	2		2	
**	88000290	SIGNAL HEAD, 1-FACE, 5-SECTION, MAST ARM MOUNTED	EACH	4		4	
**	88200110	TRAFFIC SIGNAL BACKPLATE, LOUVERED	EACH	27		27	
**	88500100	INDUCTIVE LOOP DETECTOR	EACH	22		22	
**	88600100	DETECTOR LOOP, TYPE 1	FOOT	2053		2053	
**	88700200	LIGHT DETECTOR	EACH	7		7	
**	88700300	LIGHT DETECTOR AMPLIFIER	EACH	3		3	
**	88800100	PEDESTRIAN PUSH BUTTON	EACH	7		7	
**	89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	2		2	
**	89502200	MODIFY EXISTING CONTROLLER	EACH	1		1	
**	89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	4576		4576	
**	89502350	REMOVE AND REINSTALL ELECTRIC CABLE FROM CONDUIT	FOOT	3023		3023	
**	89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	2		2	
**	89502380	REMOVE EXISTING HANDHOLE	EACH	11		11	
**	89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9		9	
**	A2004620	TREE, GLEDITSIA TRIACANTHOS INERMIS (THORNLESS COMMON HONEYLOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	1	1		
**	A2008020	TREE, TILIA CORDATA (LITTLE LEAF LINDEN) 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	2	2		
**	K0036120	MULCH PLACEMENT 4"	SQ YD	65	65		
**	XX001877	SUMP PUMP LINE CONNECTION	EACH	3	3		
**	XX002202	VEHICLE CONTROL BOLLARDS	EACH	3	3		
**	XX002881	TRAFFIC SIGNAL SYSTEM OPTIMIZATION	L SUM	1	1		
**	XX003183	POST MOUNTED FLASHING BEACON INSTALLATION	EACH	1	1		
**	XX003817	GRATING FOR CONCRETE FLARED END SECTION 12"	EACH	1	1		
**	XX005011	BOX CULVERT EXTENSION WITH HEADWALL	L SUM	1	1		
**	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	1	1		
**	XX006372	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE 4"	FOOT	30	30		
**	XX006373	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE 8"	FOOT	45	45		
**	X0321905	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE 12"	FOOT	67	67		
**	X0321906	STORM SEWERS, TYPE 1, WATER MAIN QUALITY PIPE 15"	FOOT	164	164		
**	X0321020	PORTLAND CEMENT CONCRETE SURFACE REMOVAL (COLD MILLING) VARIABLE DEPTH	SQ YD	3503	3503		
**	X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	100	100		
**	X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	4297		4297	
**	X0323868	DRAINAGE RESTRICTOR	EACH	1	1		
**	X0545000	BOX CULVERT REMOVAL	FOOT	71	71		
**	X2800100	TEMPORARY DITCH CHECKS, ROLLED EXCELSIOR	EACH	12	12		
**	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	14	14		
**	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	15	15		
**	X4023000	TEMPORARY ACCESS (ROAD)	EACH	10	10		
**	X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	5718	5718		
**	X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	386	386		
**	X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	3305	3305		
**	X4066770	LEVELING BINDER (MACHINE METHOD), SUPERPAVE, N70	TON	1097	1097		

Revised  
6-12-06



Revised  
6-12-06  
Deleted  
6-12-06

F.A.U. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2774	99-00073-00-WR	COOK	116	5A
STA.	TO STA.		FED. ROAD DIST. NO. 1	
	ILLINOIS		FED. AID PROJECT CMM-7003 (750)	
CONTRACT NO. 83727				

I:\DATA\020146\DWG\020146-SUM-QTY.dwg  
 Plotted: 5-08-06 By: [unclear]  
 Date: 5-08-06 By: [unclear]  
 State of Illinois - Professional Design Firm  
 License No. - 184-001121 - Expires 4-30-05

CONSULTANTS	REV. NO.	DATE	DESCRIPTION
	1	4-28-06	PER IDOT AND COOK COUNTY COMMENTS
	2	5-8-06	PER IDOT COMMENTS

\* - REFER TO EQUIPMENT MANUFACTURER'S SHOP DRAWINGS

**Baxter & Woodman**  
 Consulting Engineers  
 Crystal Lake, Illinois 815.459.1260  
 Burlington, Wisconsin 262.763.7454  
 Mokena, Illinois 708.478.2090  
 DeKalb, Illinois 815.787.3111  
 Graylake, Illinois 815.223.5088  
 Rockford, Illinois 815.489.1551  
 Plainfield, Illinois 815.609.7455

**CITY OF OAK FOREST, ILLINOIS**  
**OAK PARK AVENUE PROJECT**

**SUMMARY OF QUANTITIES**

DESIGNED BY	SCALE
NJP	NONE
DRAWN BY	PROJECT NO.
LUK	020146
CHECKED BY	SHEET NO.
NJP	5A OF 116
DATE	
1-20-05	