

# SUMMARY OF QUANTITIES

SPCLTY/IDOT CODE	ITEM	UNIT	TOTAL QUANTITY	ROADWAY I000-2A	SIGNAL Y031-1F	SIDEWALK SFTY-1B
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	90	90		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	193	193		
20101000	TEMPORARY FENCE	FOOT	910	910		
20101100	TREE TRUNK PROTECTION	EACH	6	6		
20101200	TREE ROOT PRUNING	EACH	30	30		
20101300	TREE PRUNING (1 TO 10 INCH DIAMETER)	EACH	10	10		
20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	20	20		
20200100	EARTH EXCAVATION	CU YD	4509	4509		
20201200	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL	CU YD	8826	8826		
20700420	POROUS GRANULAR EMBANKMENT, SUBGRADE	CU YD	250	250		
20800250	TRENCH BACKFILL, SPECIAL	CU YD	1785	1785		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION	SQ YD	300	300		
** 21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	26942	26942		
21300010	EXPLORATION TRENCH, SPECIAL	FOOT	10	10		
21301052	EXPLORATION TRENCH 52" DEPTH	FOOT	623	623		
** 25000210	SEEDING, CLASS 2A	ACRE	3.30	3.30		
** 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	433	433		
** 25000500	PHOSPOROUS FERTILIZER NUTRIENT	POUND	433	433		
** 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	433	433		
25100630	EROSION CONTROL BLANKET	SQ YD	15972	15972		
25200110	SODDING, SALT TOLERANT	SQ YD	10970	10970		
25200200	SUPPLEMENTAL WATERING	UNIT	329	329		
28000400	PERIMETER EROSION BARRIER	FOOT	5260	5260		
28000500	INLET AND PIPE PROTECTION	EACH	54	54		
28000510	INLET FILTERS	EACH	53	53		
28100107	STONE RIP RAP, CLASS A4	SQ YD	105	105		
28200200	FILTER FABRIC	SQ YD	120	120		
35400300	PORTLAND CEMENT CONCRETE BASE COURSE WIDENING 8"	SQ YD	455	455		
40500100	BITUMINOUS MATERIALS (PRIME COAT)	GAL	7975	7975		
40600300	AGGREGATE (PRIME COAT)	TON	160	160		
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	20	20		
40600895	CONSTRUCTING TEST STRIP	EACH	3	3		
40602000	BITUMINOUS REPLACEMENT OVER PATCHES, SUPERPAVE	TON	69	69		
40800040	INCIDENTAL BITUMINOUS SURFACING	TON	272	272		
42300710	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 6", SPECIAL	SQ YD	12	12		
42300800	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT 8", SPECIAL	SQ YD	228	228		
42400430	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH, SPECIAL	SQ FT	19012			19012
42400440	PORTLAND CEMENT CONCRETE SIDEWALK 6 INCH, SPECIAL	SQ FT	1110			1110
42400800	DETECTABLE WARNINGS	SQ FT	256			256
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	22061	22061		
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	299	299		
44000300	CURB REMOVAL	FOOT	232	232		
44000500	COMBINATION CONCRETE CURB AND GUTTER REMOVAL	FOOT	3014	3014		
44000600	SIDEWALK REMOVAL	SQ FT	353			353
44200934	CLASS B PATCHES, TYPE II, 8 INCH	SQ YD	183	183		
44200942	CLASS B PATCHES, TYPE III, 8 INCH	SQ YD	174	174		
44200944	CLASS B PATCHES, TYPE IV, 8 INCH	SQ YD	741	741		
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	112	112		
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	328	328		
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	374	374		
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	19302	19302		
48202400	BITUMINOUS SHOULDERS, SUPERPAVE - 6"	SQ YD	1536	1536		
50104400	CONCRETE HEADWALL REMOVAL	EACH	13	13		
50105220	PIPE CULVERT REMOVAL	FOOT	1614	1614		
542C0217	PIPE CULVERTS, CLASS C, TYPE 1 12"	FOOT	176	176		

F.A.U. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2774	99-00073-00-WR	COOK	116	4
STA.	TO STA.	FED. ROAD DIST. NO. 1		
		ILLINOIS	FED. AID PROJECT CMM-700.3 (750)	
CONTRACT NO. 83727				

I:\CADD\020146\DWG\020146-SMRY-QTY.dwg  
 Plotted: 5-08-06 @ 7:36pm by: 354rjp  
 Copyright © 2004, by Baxter & Woodman, Inc.  
 State of Illinois - Professional Design Firm  
 License No. 184-001171 - Expires 4-30-05

CONSULTANTS	REV. NO.	DATE	DESCRIPTION
	1	4-28-06	PER IDOT AND COOK COUNTY COMMENTS
	2	5-8-06	PER IDOT COMMENTS
* - REFER TO EQUIPMENT MANUFACTURER'S SHOP DRAWINGS			



**Baxter & Woodman**  
 Consulting Engineers  
 Crystal Lake, Illinois 815.459.1200  
 Burlington, Wisconsin 262.768.7834  
 Mukwonago, Illinois 708.478.5090  
 DeKalb, Illinois 815.787.2111  
 Crystal Lake, Illinois 847.233.5098  
 Rockford, Illinois 815.409.1651  
 Plainfield, Illinois 815.609.7425

**CITY OF OAK FOREST, ILLINOIS**  
**OAK PARK AVENUE PROJECT**

**SUMMARY OF QUANTITIES**

DESIGNED BY	SCALE
NJP	NONE
DRAWN BY	PROJECT NO.
LIK	020146
CHECKED BY	SHEET NO.
NJP	4 OF 116
DATE	1-20-05