

# SUMMARY OF QUANTITIES, CONTINUED

SPCLTY	IDOT CODE	ITEM	UNIT	TOTAL QUANTITY	ROADWAY I000-2A	SIGNAL Y031-1F	SIDEWALK SFT-Y-1B
	67100100	MOBILIZATION	L SUM	1	1		
	70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1	1		
	70100500	TRAFFIC CONTROL AND PROTECTION, STANDARD 701326	L SUM	1	1		
	70100700	TRAFFIC CONTROL AND PROTECTION, STANDARD 701406	L SUM	1	1		
	70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	1		
	70102622	TRAFFIC CONTROL AND PROTECTION, STANDARD 701502	L SUM	1	1		
	70102550	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	EACH	3	3		
	70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1		
	70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1		
	70300100	SHORT-TERM PAVEMENT MARKING	FOOT	10311	10311		
	70300200	TEMPORARY PAVEMENT MARKING	FOOT	41244	41244		
	70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	3437	3437		
**	72000100	SIGN PANEL - TYPE 1	SQ FT	300	200	100	
**	72900100	METAL POST - TYPE A	FOOT	632	632		
**	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	858	858		
**	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	33625	33625		
**	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	2654	2654		
**	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1296	1296		
**	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	326	326		
**	78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	561	561		
**	78200410	GUARDRAIL MARKERS, TYPE A	EACH	8	8		
**	78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	4	4		
	78300100	PAVEMENT MARKING REMOVAL	SQ FT	3437	3437		
**	78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	208	208		
**	81000300	CONDUIT IN TRENCH, 1" DIA., GALVANIZED STEEL	FOOT	15	15		
**	81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	5631		5631	
**	81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	287		287	
**	81000800	CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL	FOOT	48		48	
**	81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	30		30	
**	81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	581		581	
**	81018600	CONDUIT PUSHED, 2 1/2" DIA., GALVANIZED STEEL	FOOT	71		71	
**	81018700	CONDUIT PUSHED, 3" DIA., GALVANIZED STEEL	FOOT	231		231	
**	81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	520		520	
**	81400100	HANDHOLE	EACH	18		18	
**	81400200	HEAVY DUTY HANDHOLE	EACH	11		11	
**	81400300	DOUBLE HANDHOLE	EACH	3		3	
**	81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	6002		6002	
**	83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	20	20		
**	84200700	LIGHTING FOUNDATION REMOVAL	EACH	2	2		
**	84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2		2	
**	85000200	MAINTAINANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2		2	
**	85700200	FULL - ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	2		2	
**	85700300	FULL - ACTUATED CONTROLLER AND TYPE V CABINET	EACH	1		1	
**	86000100	MASTER CONTROLLER	EACH	1		1	
**	86400100	TRANSCEIVER - FIBER OPTIC	EACH	3		3	
**	87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 2C	FOOT	813		813	
**	87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 3C	FOOT	2681		2681	
**	87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 5C	FOOT	4540		4540	
**	87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL, NO. 14 7C	FOOT	2522		2522	
**	87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4677		4677	
**	87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6, 2C	FOOT	621		621	
**	87502440	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 10 FT.	EACH	1		1	
**	87502480	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 14 FT.	EACH	5		5	
**	87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL, 16 FT.	EACH	4		4	
**	87700160	STEEL MAST ARM ASSEMBLY AND POLE, 24 FT.	EACH	2		2	

F.A.U. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2774	99-00073-00-WR	COOK	116	5
STA.	TO STA.		FED AID PROJECT	
FED. ROAD DIST. NO. 1	ILLINOIS		CMM-700.3 (750)	
CONTRACT NO. 83727				

I:\CIVIL\020146\DWG\020146-SUM-QTY.dwg  
 Plotted: 5-08-06 @ 7:46pm by 354-jip  
 Copyright © 2004, by Baxter & Woodman, Inc.  
 State of Illinois - Professional Design Firm  
 License No. - 184-001121 - Expires 4-30-08

CONSULTANTS	REV. NO.	DATE	DESCRIPTION
	1	4-28-06	PER IDOT AND COOK COUNTY COMMENTS
	2	5-8-06	PER IDOT COMMENTS
* - REFER TO EQUIPMENT MANUFACTURER'S SHOP DRAWINGS			


**BAXTER & WOODMAN**  
 Consulting Engineers  
 Crystal Lake, Illinois 815.458.1260  
 Burlington, Wisconsin 262.763.7834  
 Mokena, Illinois 708.478.2090  
 DeKalb, Illinois 815.787.3111  
 Graylake, Illinois 815.253.2089  
 Rockford, Illinois 815.449.1551  
 Plainfield, Illinois 815.609.7425

**CITY OF OAK FOREST, ILLINOIS**  
**OAK PARK AVENUE PROJECT**

DESIGNED BY	SCALE
NJP	NONE
DRAWN BY	PROJECT NO.
UKB	020146
CHECKED BY	SHEET NO.
NJP	5 OF 116
DATE	
1-20-05	