

F.A.U. ROUTE NO.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2774	99-00073-00-WR	COOK	116	7A
STA.	TO STA.		FED AID PROJECT	
FED. ROAD DIST. NO. 1	ILLINOIS		CMM-7003 (750)	

CONTRACT NO. 83727

# PAVEMENT SCHEDULE, CONTINUED

STATION	LENGTH FT	PROPOSED PAVEMENT WIDTH	EXISTING PAVEMENT WIDTH	AVERAGE PROPOSED WIDTH FT	AVERAGE EXISTING WIDTH FT	AVERAGE WIDENING WIDTH FT	BIT BINDER AREA SY	AGGREGATE SUBGRADE AREA SY	LEVELING BINDER AREA SY	BIT SURFACE AREA SY	BIT BINDER TONS	BIT LEVELING BINDER TONS	BIT SURFACE TONS
OAK PARK AVENUE													
56+00	100	36.0	21.9	36	21.50	14.50	161.11	241.11	238.89	400.00	94.73	13.38	33.60
57+00	100	36.0	21.1	36	21.15	14.85	165.00	245.00	235.00	400.00	97.02	13.16	33.60
58+00	89.1	36.0	21.2	36	21.20	14.80	146.52	217.80	209.88	356.40	86.15	11.75	29.94
58+89		36.0	21.2				178.97	310.33	942.42	1121.39	105.23	52.78	94.20
60+39	60.9	36.0	21.6	36	21.30	14.70	99.47	148.19	144.13	243.60	58.49	8.07	20.46
61+00	100	36.0	21.0	36	21.00	15.00	166.67	246.67	233.33	400.00	98.00	13.07	33.60
62+00	100	36.0	21.0	36	20.50	15.50	172.22	252.22	227.78	400.00	101.27	12.76	33.60
63+00	100	36.0	20.0	36	20.35	15.65	173.89	253.89	226.11	400.00	102.25	12.66	33.60
64+00	100	36.0	20.7	36	20.70	15.30	170.00	250.00	230.00	400.00	99.96	12.88	33.60
65+00	100	36.0	20.7	36	20.95	15.05	167.22	247.22	232.78	400.00	98.33	13.04	33.60
66+00	100	36.0	21.2	36	21.55	14.45	160.56	240.56	239.44	400.00	94.41	13.41	33.60
67+00	100	36.0	21.9	36	22.80	13.20	146.67	226.67	253.33	400.00	86.24	14.19	33.60
68+00	67.3	36.0	23.7	36	25.20	10.80	80.76	134.60	188.44	269.20	47.49	10.55	22.61
68+67		36.0	26.7										
68+67	132.7		29.5	36	32.75	3.25	47.92	154.08	482.88	530.80			
70+00	100	36.0	36.0	36	36.00	0.00	0.00	80.00	400.00	400.00	0.00	22.40	33.60
71+00	66.3	36.0	36.0	36	36.00	0.00	0.00	53.04	265.20	265.20	0.00	14.85	22.28
71+66		36.0	36.0				50.79	144.71	791.97	842.76	29.86	44.35	70.79
73+00	92.2	46.4	41.7	41.2	38.85	2.35	10.47	53.75	411.60	422.07	6.16	23.05	35.45
73+92	107.8	36.0	36.0	36	36.00	0.00	0.00	0.00	431.20	431.20	0.0	0.0	36.22
75+00	100	36.0	36.0	36	36.00	0.00	0.00	0.00	400.00	400.00	0.0	0.0	33.60
76+00	100	36.0	36.0	33.7	33.70	0.00	0.00	0.00	374.44	374.44	0.0	0.0	31.45
77+00	100	31.4	31.4	29.3	29.30	0.00	0.00	0.00	325.56	0.00	0.0	0.0	0.00
78+00	100	27.2	27.2	25.95	25.95	0.00	0.00	0.00	288.33	288.33	0.0	0.0	24.22
79+00	100	24.7	24.7	24.35	24.35	0.00	0.00	0.00	270.56	270.56	0.0	0.0	22.73
80+00	100	24.0	24.0	24	24.00	0.00	0.00	0.00	266.67	266.67	0.0	0.0	22.40
81+00	100	24.0	24.0	24	24.00	0.00	0.00	0.00	266.67	266.67	0.0	0.0	22.40
82+00	100	24.0	24.0	24	24.00	0.00	0.00	0.00	266.67	266.67	0.0	0.0	22.40
83+00	100	24.0	24.0	24	24.00	0.00	0.00	0.00	266.67	266.67	0.0	0.0	22.40
84+00	100	24.0	24.0	24	24.00	0.00	0.00	0.00	266.67	266.67	0.0	0.0	22.40
85+00	100	24.0	24.0	24	24.00	0.00	0.00	0.00	266.67	266.67	0.0	0.0	22.40
86+00	100	24.0	24.0	24	24.00	0.00	0.00	0.00	266.67	266.67	0.0	0.0	22.40
87+00	100	24.0	24.0	24	24.00	0.00	0.00	0.00	266.67	266.67	0.0	0.0	22.40
88+00	100	24.0	24.0	24	24.00	0.00	0.00	0.00	266.67	266.67	0.0	0.0	22.40
89+00	100	24.0	24.0	24	24.00	0.00	0.00	0.00	266.67	266.67	0.0	0.0	22.40
90+00	100	24.0	24.0	24	24.00	0.00	0.00	0.00	266.67	266.67	0.0	0.0	22.40
91+00	104	24.0	24.0	24	24.00	0.00	0.00	0.00	277.33	277.33	0.0	0.0	23.30

I:\OAKFT\020146\DWG\20146-SCHD-MAT.dwg  
 Plotted: 5-08-06 @ 8:32am By: 354njp  
 Copyright © 2004, by Baxter & Woodman, Inc.  
 State of Illinois - Professional Design Firm  
 License No. - 184-001121 - Expires 4-30-05

CONSULTANTS	REV. NO.	DATE	DESCRIPTION
	1	4-28-06	PER IDOT AND COOK COUNTY COMMENTS
	2	5-8-06	PER IDOT COMMENTS

\* - REFER TO EQUIPMENT MANUFACTURER'S SHOP DRAWINGS

**Baxter & Woodman**  
 Consulting Engineers  
 Crystal Lake, Illinois 815.459.1800  
 Burlington, Wisconsin 262.763.7934  
 Mokena, Illinois 708.478.2090  
 DeKalb, Illinois 815.767.2111  
 Grayslake, Illinois 815.223.5088  
 Rockford, Illinois 815.499.1551  
 Plainfield, Illinois 815.609.7425

**CITY OF OAK FOREST, ILLINOIS**  
**OAK PARK AVENUE PROJECT**

**SCHEDULE OF MATERIALS**

DESIGNED BY	NJP	SCALE	NONE
DRAWN BY	LKB	PROJECT NO.	020146
CHECKED BY	NJP	SHEET NO.	7A OF 116
DATE	1-20-05		