


# PAVEMENT SCHEDULE, CONTINUED

STATION	LENGTH FT	PROPOSED PAVEMENT WIDTH	EXISTING PAVEMENT WIDTH	AVERAGE PROPOSED WIDTH FT	AVERAGE EXISTING WIDTH FT	AVERAGE WIDENING WIDTH FT	BIT BINDER AREA SY	AGGREGATE SUBGRADE AREA SY	LEVELING BINDER AREA SY	BIT SURFACE AREA SY	BIT BINDER TONS	BIT LEVELING BINDER TONS	BIT SURFACE TONS
OAK PARK AVENUE													
92+04		24.0	24.0										
92+04		30.0	30.0										
93+00	96	34.0	34.0	32	32.00	0.00	0.00	0.00	341.33	341.33	0.0	0.0	28.67
94+00	100	34.0	34.0	34	34.00	0.00	0.00	0.00	377.78	377.78	0.0	0.0	31.73
95+00	100	34.0	34.0	34.9	34.90	0.00	0.00	0.00	387.78	387.78	0.0	0.0	32.57
96+00	100	35.8	35.8	38.8	38.80	0.00	0.00	0.00	431.11	431.11	0.0	0.0	36.21
97+10	110	41.8	41.8	44.1	44.10	0.00	0.00	0.00	539.00	539.00	0.0	0.0	45.28
97+10		46.4	46.4										
97+10		34.4	34.4										
98+00	90	34.4	34.4	35.2	35.20	0.00	0.00	0.00	352.00	352.00	0.0	0.0	29.57
98+00	100	36.0	36.0	36	36.00	0.00	0.00	0.00	400.00	400.00	0.0	0.0	33.60
99+00		36.0	36.0										
99+00		36.0	18.0										
100+00	100	36.0	16.0	34	17.00	17.00	188.89	266.67	188.89	377.78	111.07	10.58	31.73
101+58		36.0	36.0				985.87	985.87	193.33	1179.20	579.69	10.83	99.05
101+58	42	41.4	10.6	38.2	10.80	27.40	230.33	230.33	50.65	178.27	135.43	2.84	14.97
102+00		35.0	11.0										
102+00		35.0	24.8										
102+00	100	35.0	24.8	32.45	24.85	7.60	50.48	153.33	276.11	360.56	29.68	15.46	30.29
103+00	120	29.9	24.9	27.45	24.95	2.50	19.63	116.00	332.67	366.00	11.54	18.63	30.74
104+20		25.0	25.0										
				OAK PARK AVENUE SUBTOTAL			8808.64	13520.08	26885.65	35313.89	5151.42	997.78	2921.78
151ST STREET													
120+50		57.1	40.2										
120+50	44.8	42.1	31.6	49.6	35.9	13.7	68.20	68.20	0.00	246.90	40.10	0.00	20.74
120+95	105.2	42.1	31.6	42.05	31.1	10.95	127.99	127.99	0.00	491.52	75.26	0.00	41.29
122+00		42.0	30.6										
122+00	100	42.0	30.6	42	30.4	11.6	128.89	128.99	0.00	466.67	75.79	0.00	39.20
123+00		42.0	30.2										
123+00	100	42.0	30.2	40.65	30.1	10.55	117.22	117.22	0.00	451.67	68.93	0.00	37.94
124+00		39.3	30.0										
124+00	100	39.3	30.0	37.65	30	7.65	85.00	85.00	0.00	418.33	49.98	0.00	35.14
125+00		36.0	30.0										
125+00	86	36.0	30.0	36	30	6	57.33	57.33	0.00	344.00	33.71	0.00	28.90
125+86		36.0	30.0										
				151ST STREET SUBTOTAL			584.63	584.73	0.00	2419.08	343.76	0.00	203.20
JUSTAMERE ROAD													
201+00		36.0	26.6										
201+00	100	36.0	26.6	36	26	10	111.11	184.44	288.89	400.00	65.33	16.18	33.60
202+00		36.0	25.4										
202+00	143.9	36.0	25.4	36	25.3	10.7	171.08	276.61	404.52	575.60	100.60	22.65	48.35
203+44		36.0	25.2										
203+44	58.7	36.0	25.2	37.2	28	9.2	60.00	103.05	182.62	242.63	35.28	10.23	20.38
204+03		38.4	30.8										
204+03		38.4	30.8				36.80	98.47	887.46	924.26	21.64	49.70	77.64
205+85		36.0											
				JUSTAMERE ROAD SUBTOTAL			379.00	662.57	1763.49	2142.49	222.85	98.76	179.97
				PROJECT TOTAL			9772.5	14767.4	28649.1	39875.5	5718.0	1096.5	3305.0

I:\CADD\020146\DWG\20146-05-SCHD-MAI.dwg  
 Plotter: 5-18-05 @ 8:33am By: 35enjp  
 Copyright ©2004, By Baxter & Woodman, Inc.  
 State of Illinois - Professional Design Firm  
 License No. - 184-001121 - Expires 4-30-05

CONSULTANTS	REV. NO.	DATE	DESCRIPTION
	1	4-28-06	PER IDOT AND COOK COUNTY COMMENTS
	2	5-8-06	PER IDOT COMMENTS
* - REFER TO EQUIPMENT MANUFACTURER'S SHOP DRAWINGS			


**Baxter & Woodman**  
 Consulting Engineers  
 Crystal Lake, Illinois 815.489.1260  
 Burlington, Wisconsin 262.763.7834  
 Mokena, Illinois 708.478.2090  
 DeKalb, Illinois 815.787.3111  
 Graylake, Illinois 815.223.2088  
 Rockford, Illinois 815.489.1051  
 Plainfield, Illinois 815.609.7425

**CITY OF OAK FOREST, ILLINOIS**  
**OAK PARK AVENUE PROJECT**

**SCHEDULE OF MATERIALS**

DESIGNED BY	SCALE
NJP	NONE
DRAWN BY	PROJECT NO.
UKB	020146
CHECKED BY	SHEET NO.
NJP	7B OF 116
DATE	
1-20-05	