

MANHOLES

OAK PARK AVENUE

ST-MH 1 MANHOLE, TY A, TY 1 F&G, CL 4' DIA. STA. 25+50, 12.4' LT. RIM = 732.35 INV. = 727.49 12" N & W INV. = 728.51 12" E

ST-MH 14 MANHOLE, TY A, TY 1 F&G, CL 4' DIA. STA. 49+50 13' LT. RIM = 712.87 INV. = 706.40 12" N INV. = 709.32 12" W INV. = 709.07 12" E

CATCH BASINS

OAK PARK AVENUE

ST-CB 1 CATCH BASIN, TY C, TY 24 F&G 2' DIA. STA. 19+82 39.2' LT. EP = 731.25 INV. = 726.00

ST-CB 19 CATCH BASIN, TY C, TY 24 F&G 2' DIA. STA. 39+00 18' LT. EP = 726.00 INV. = 722.62 12" E

INLETS

OAK PARK AVENUE

ST-IN 1 INLET, TY A, TY 1 F&G, OL STA. 25+50 32.7' LT. RIM = 729.94 INV. = 727.70 12" E

ST-IN 19 INLET, TY A, TY 8 F&G STA. 64+88 27' LT. RIM = 695.00 INV. = 693.50 12" E

FLARED END SECTION

OAK PARK AVENUE

ST-FES 1 RCEP 24"x30" STA. 32+03 29' RT. INV. 721.97 NW

STORM SEWER PIPES

OAK PARK AVENUE

ST-P 1 15 L.F. OF 12" STSW, CL A, TY 2 @ 1.40% T.B.F. = 2.6 C.Y.

F.A.U. SHEETS COUNTY TOTAL SHEETS SHEET NO.

Table with columns: F.A.U. ROUTE NO., SECTION, COUNTY, TOTAL SHEETS, SHEET NO. Includes project details for Cook County, IL, and sheet number 10 of 116.


CONTRACT NO. 030146 (DNRS) 701146 - SCHEMATIC - 4/30/05

DESIGNED BY: NJP DRAWN BY: LKB CHECKED BY: NJP DATE: 1-20-05

SCALE: NONE PROJECT NO.: 020146 SHEET NO.: 10 OF 116

1" = 50' 0" 1" = 20' 0" 1" = 10' 0"

Table with columns: CONSULTANTS, REV, DATE, DESCRIPTION. Includes entry for 4-28-06 PER IDOT AND COOK COUNTY COMMENTS.



Baxter & Woodman Consulting Engineers, Crystal Lake, Illinois, 815.459.1260

CITY OF OAK FOREST, ILLINOIS OAK PARK AVENUE PROJECT

OAK PARK AVENUE, JUSTAMERE ROAD AND 151st STREET DRAINAGE STRUCTURE SCHEDULE