

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
0369	97-00025-00-BR	WILL	156	7
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

CONTRACT NO: 83757

CODE NUMBER	ITEM	UNIT	TOTAL	BITUMINOUS CONCRETE 1000-2A	PORTLAND CEMENT CONCRETE J000-2A	STEEL GIRDER BRIDGE OVER WATERWAY X071-2A	PAVEMENT MARKING SFTY-1D	HIGHWAY LIGHTING Y030-1E	TRAFFIC SIGNALS Y031-1F
* 81400200	HEAVY-DUTY HANDHOLE	EACH	3						3
* 81400300	DOUBLE HANDHOLE	EACH	3						3
* 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	2,496					1,775	721
* 81701385	ELECTRIC CABLE IN CONDUIT, 600V (EPR-TYPE USE) 3-1/C 350MCM	FOOT	145					145	
* 81800600	AERIAL CABLE, 2-1/C NO. 2, ALUMINUM, WITH MESSENGER WIRE	FOOT	45					45	
* 81800620	AERIAL CABLE, 2-1/C NO. 4, ALUMINUM, WITH MESSENGER WIRE	FOOT	785					785	
* 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	7					7	
* 82102310	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 310 WATT	EACH	5					5	
* 83008500	LIGHT POLE, ALUMINUM, 40 FT. M.H., 12 FT. MAST ARM	EACH	8					8	
* 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	80					80	
* 83800205	BREAKAWAY DEVICE, TRANSFORMER BASE, 15 INCH BOLT CIRCLE	EACH	2					2	
* 84100110	REMOVAL OF TEMPORARY LIGHTING UNITS	EACH	1					1	
* 84200500	REMOVAL OF EXISTING LIGHTING UNIT, SALVAGE	EACH	1					1	
* 84200700	LIGHTING FOUNDATION REMOVAL	EACH	2					2	
* 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1						1
* 85700206	FALL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1						1
* 86400100	TRANSCEIVER - FIBER OPTIC	EACH	1						1
* 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1,520						1,520
* 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2,462						2,462
* 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	1,296						1,296
* 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1,746						1,746
* 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	2,532						2,532
* 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2 C	FOOT	124						124
* 87502500	TRAFFIC SIGNAL POST, GALVANIZED STEEL 16 FT.	EACH	3						3
* 87502520	TRAFFIC SIGNAL POST, GALVANIZED STEEL 18 FT.	EACH	1						1
* 87702870	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 28 FT.	EACH	1						1
* 87702890	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 32 FT.	EACH	1						1
* 87702920	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 38 FT.	EACH	1						1
* 87702940	STEEL COMBINATION MAST ARM ASSEMBLY AND POLE 42 FT.	EACH	1						1
* 87800100	CONCRETE FOUNDATION, TYPE A	FOOT	16						16
* 87800200	CONCRETE FOUNDATION, TYPE D	FOOT	4						4
* 87800400	CONCRETE FOUNDATION, TYPE E 30-INCH DIAMETER	FOOT	15						15
* 87800415	CONCRETE FOUNDATION, TYPE E 36-INCH DIAMETER	FOOT	45						45
* 88200100	TRAFFIC SIGNAL BACKPLATE	EACH	8						8
* 88500100	INDUCTIVE LOOP DETECTOR	EACH	10						10
* 88600100	DETECTOR LOOP, TYPE I	FOOT	1,166						1,166
* 88700200	LIGHT DETECTOR	EACH	2						2

*SPECIALTY ITEM

REVISIONS	
NAME	DATE

VILLAGE OF NEW LENOX
F.A.U. (0369) CEDAR ROAD OVER HICKORY CREEK
WILL. COUNTY

SUMMARY OF QUANTITIES V

SCALE: NTS
DATE: 07/01/05

DRAWN BY: PFR
CHECKED BY: KPS

TENG

TENG & ASSOCIATES, INC.
ENGINEERS/ARCHITECTS/PLANNERS
205 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312-662-2000

ATTORNEY GENERAL'S OFFICE, CIVIL RIGHTS DIVISION, 100 N. LAUREL AVENUE, CHICAGO, IL 60602-4500