

CODE NUMBER	ITEM	UNIT	TOTAL	BITUMINOUS CONCRETE 1000-2A	PORTLAND CEMENT CONCRETE J000-2A	STEEL GIRDER BRIDGE OVER WATERWAY X071-2A	PAVEMENT MARKING SFTY-10	HIGHWAY LIGHTING Y030-1E	TRAFFIC SIGNALS Y031-1F
* 88700300	LIGHT DETECTOR AMPLIFIER	EACH	1						1
* 88800100	PEDESTRIAN PUSH-BUTTON	EACH	8						8
* 89000100	TEMPORARY TRAFFIC SIGNAL INSTALLATION	EACH	1						1
* 89100400	ILLUMINATED SIGN, LED	EACH	2						2
* 89502300	REMOVE ELECTRIC CABLE FROM CONDUIT	FOOT	4,778						4,778
* 89502375	REMOVE EXISTING TRAFFIC SIGNAL EQUIPMENT	EACH	1						1
* 89502380	REMOVE EXISTING HANDHOLE	EACH	13						13
* 89502385	REMOVE EXISTING CONCRETE FOUNDATION	EACH	9						9
* A2000620	TREE, ACER PLATANOIDES (NORWAY MAPLE), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5					
* A2003520	TREE, FRAXINUS AMERICANA AUTUMN PURPLE (AUTUMN PURPLE WHITE ASH), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5					
* A2004020	TREE, FRAXINUS PENNSYLVANICA MARSHALL'S SEEDLESS (MARSHALL'S SEEDLESS GREEN ASH), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5					
* A2004220	TREE, FRAXINUS PENNSYLVANICA SUMMIT (SUMMIT GREEN ASH), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5					
* A2004720	TREE, GLEDITSIA TRIACANTHOS INERMIS SHADEMASTER (SHADEMASTER THORNLESS COMMON HONEYLOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	4	4					
* A2004820	TREE, GLEDITSIA TRIACANTHOS INERMIS SKYLINE (SKYLINE THORNLESS COMMON HONEYLOCUST), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5					
* A2007920	TREE, TILIA AMERICANA REDMOND (REDMOND AMERICAN LINDEN), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5					
* A2008120	TREE, TILIA CORDATA GREENSPIRE (GREENSPIRE LITTLE LEAF LINDEN), 2-1/2" CALIPER, BALLED AND BURLAPPED	EACH	5	5					
42400800	DETECTABLE WARNINGS	SOFT	350		350				
* X0322695	MAST ARM, STEEL, STREET LIGHTING, 12 FT.	EACH	4					4	
* X0322925	ELECTRIC CABLE IN CONDUIT, TRACER, NO. 14 1C	FOOT	2,827						2,827
X0323082	DRAINAGE SCUPPERS, DS-33	EACH	4			4			
X0323260	SEDIMENT BASIN	EACH	6	6					
* X0323792	LIGHTING CONTROLLER, SINGLE DOOR, CONSOLE TYPE	EACH	3					3	
X0323988	TEMPORARY SOIL RETENTION SYSTEM	SQ FT	1,670			1,670			
X0324044	EROSION CONTROL, TEMPORARY PIPE SLOPE DRAIN	EACH	12	12					
X0324120	STEEL CASING PIPE 48"	FOOT	75	75					
X0330200	SANITARY MANHOLES TO BE ADJUSTED	EACH	2	2					
* X0968500	WIRE AERIAL 1/C NO. 6	FOOT	785					785	
X3550300	BITUMINOUS BASE COURSE SUPERPAVE 6"	SQ YD	1,443	1,443					
X3550500	BITUMINOUS BASE COURSE SUPERPAVE 8"	SQ YD	5,290	5,290					
X4066414	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N50	TON	162	162					
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	887	592					295
X4066616	BITUMINOUS CONCRETE BINDER COURSE, SUPERPAVE, IL-19.0, N70	TON	667	667					
X6022110	MANHOLES, TYPE A, 10'-DIAMETER, TYPE 1 FRAME, CLOSED LID	EACH	2	2					
* X7011005	TRAFFIC CONTROL AND PROTECTION FOR TEMPORARY DETOUR	L SUM	1	1					
* X8040400	ELECTRIC UTILITY SERVICE CONNECTION	EACH	3					3	
* X8050015	SERVICE INSTALLATION - POLE MOUNTED	EACH	1						1
* X8160112	UNIT DUCT, WITH 2-1/C NO. 6 AND 1/C NO. 8 GROUND, 600V (EPR-TYPE RHW), 1-1/4" DIA. POLYETHYLENE	FOOT	2,010					2,010	

*SPECIALTY ITEM

REVISIONS	
NAME	DATE

VILLAGE OF NEW LENOX
F.A.U. (0369) CEDAR ROAD OVER HICKORY CREEK
WILL COUNTY

SUMMARY OF QUANTITIES VI

SCALE: NTS
DATE: 07/01/05

DRAWN BY: PFR
CHECKED BY: KPS

TENG

TENG & ASSOCIATES INC.
ENGINEERS/ARCHITECTS/PLANNERS
300 N. MICHIGAN AVE. CHICAGO, IL 60601
TELEPHONE: 312-467-6000