

F.A.U. SECTION COUNTY TOTAL SHEETS SHEET NO.	0369 97-00025-00-BR WILL 156 13
STA. TO STA.	FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT
CONTRACT NO: 83757	

SCHEDULE OF WORK ZONE PAVEMENT MARKING REMOVAL								TOTAL	3621	
STAGE	FROM STATION	OFFSET	SIDE	TO STATION	OFFSET	SIDE	LENGTH (FT)	WIDTH (IN)	TYPE	SQ FT
STAGE I TO	10+64.58	56.74	LT	10+43.23	24.46	RT	83.96	6	SOLID	42.0
	10+69.37	51.36	LT	10+49.70	23.45	RT	77.35	6	SOLID	38.7
STAGE II TO	10+32.95	65.97	LT	10+39.61	32.88	LT	33.75	4	SOLID	11.3
	10+39.61	32.88	LT	10+69.22	16.67	LT	33.76	4	SOLID	11.3
	10+69.22	16.67	LT	11+21.92	13.22	LT	52.81	4	SOLID	17.6
	11+21.92	13.22	LT	11+64.83	7.36	LT	43.31	4	SOLID	14.4
	10+76.82	22.04	LT	10+75.00	5.76	RT	27.86	24	SOLID	55.7
	10+75.65	4.22	LT	11+21.13	11.24	RT	45.58	6	SOLID	22.8
	11+21.13	4.22	LT	11+67.21	11.80	RT	47.89	6	DOTTED	6.0
	10+75.00	5.76	RT	11+67.21	11.80	RT	92.41	4	DBL YEL	61.6
	10+97.56	8.50	RT	10+96.69	20.50	RT	12.03	24	SOLID	24.1
	11+22.00	16.00	RT	"RXR"						61.2
	11+47.00	11.30	RT	11+47.00	24.00	RT	12.70	24	SOLID	25.4
STAGE II TO	3+67.71	3.45	RT	5+97.02	1.92	LT	219.38	4	DBL YEL	146.3
	6+64.93	5.25	LT	9+25.00	5.25	LT	260.07	4	DBL YEL	173.4
STAGE III TO	300+35.06	28.05	LT	300+50.00	46.00	RT	75.54	6	SOLID	37.8
	300+41.19	26.91	LT	300+55.12	40.02	RT	68.36	6	SOLID	34.2
STAGE III TO	300+59.65	15.00	LT	300+04.85	15.32	LT	54.80	4	DBL YEL	36.5
	10+12.96	9.53	RT	10+31.97	4.25	LT	23.48	4	SOLID	7.8
STAGE IV TO	10+31.97	4.25	LT	11+23.28	4.25	LT	91.31	4	SOLID	30.4
	11+23.28	4.25	LT	11+67.28	6.58	LT	44.06	4	SOLID	14.7
	10+75.00	14.25	LT	10+75.00	2.25	LT	12.00	24	SOLID	24.0
	11+00.00	7.50	LT	"RXR"						61.2
	11+26.00	14.25	LT	11+26.00	2.25	LT	12.00	24	SOLID	24.0
	10+75.00	46.66	LT	10+75.00	14.25	LT	32.41	24	SOLID	64.8
	10+75.00	46.66	LT	11+23.28	14.25	LT	58.15	4	SOLID	19.4
	11+23.28	14.25	LT	11+67.28	18.25	LT	44.18	4	SOLID	14.7
	10+75.00	24.25	LT	11+23.28	24.25	LT	48.28	6	SOLID	24.1
	11+23.28	24.25	LT	11+67.28	18.25	LT	44.41	6	SOLID	22.2
	11+99.00	6.58	LT	13+90.02	6.25	LT	191.02	4	SOLID	63.7
	13+90.02	6.25	LT	15+24.78	10.00	RT	135.74	4	SOLID	45.2
	11+99.00	18.25	LT	13+90.02	18.25	RT	194.48	4	SOLID	64.8
	13+90.02	18.25	RT	15+24.78	2.00	LT	136.27	4	DBL YEL	90.8
	12+60.00	30.15	LT	12+60.00	18.35	LT	11.80	12	SOLID	11.8
	12+86.00	25.00	LT	"RXR"						61.2
	13+11.00	30.15	LT	13+11.00	18.35	LT	11.80	12	SOLID	11.8
STAGE IV TO	3+76.58	1.31	RT	5+96.22	5.05	LT	219.73	4	DBL YEL	146.5
FINAL	6+68.95	8.65	LT	7+81.95	9.96	LT	113.01	4	DBL YEL	75.3
	7+81.95	9.96	LT	8+71.40	12.25	LT	89.48	4	DBL YEL	59.7
	8+71.40	12.25	LT	9+25.00	12.25	LT	53.60	4	DBL YEL	35.7
	7+81.95	9.96	LT	8+26.68	6.11	LT	44.90	4	DBL YEL	29.9
	8+26.68	6.11	LT	8+71.40	12.25	LT	45.14	4	DBL YEL	30.1
	CENTER SLASHES									21.0
	8+26.68	6.11	LT	8+71.40	2.25	LT	44.89	6	DOTTED	5.6
	8+71.40	2.25	LT	9+25.00	2.25	LT	53.60	6	SOLID	26.8
	8+80.00	8.50	LT	"ONLY"						20.8
	9+05.00	8.50	LT	ARROW						15.6
	9+25.00	12.25	LT	9+25.00	18.25	RT	30.50	24	SOLID	61.0
	9+51.60	27.76	LT	9+29.85	20.74	RT	53.15	6	SOLID	26.6
	9+59.60	30.92	LT	9+34.82	24.32	RT	60.54	6	SOLID	30.3
	10+64.58	56.74	LT	10+39.50	38.63	RT	98.61	6	SOLID	49.3
	10+69.37	51.36	LT	10+46.11	37.09	RT	91.46	6	SOLID	45.7
	10+75.00	46.66	LT	10+75.00	0.25	LT	46.41	24	SOLID	92.8
	10+75.00	23.25	LT	11+67.28	23.25	LT	92.28	6	SOLID	46.1
	10+75.00	11.25	LT	11+15.00	11.25	LT	40.00	6	SOLID	20.0
	11+15.00	11.25	LT	11+67.28	11.25	LT	52.28	6	DOTTED	6.5
	11+15.00	0.25	LT	11+67.28	11.25	LT	53.42	4	SOLID	17.8
	10+73.94	5.00	RT	10+83.19	14.25	RT	13.08	4	SOLID	4.4
	10+83.19	14.25	RT	11+67.28	14.25	RT	84.09	4	SOLID	28.0
	10+40.50	38.35	RT	10+59.02	33.32	RT	19.19	4	SOLID	6.4
	10+59.02	33.32	RT	10+64.84	43.16	RT	11.43	4	SOLID	3.8
	11+01.70	36.25	RT	11+01.70	26.25	RT	10.00	4	SOLID	3.3
	11+01.70	26.25	RT	11+23.49	26.25	RT	21.79	4	SOLID	7.3
	11+23.49	26.25	RT	11+23.49	36.25	RT	10.00	4	SOLID	3.3
	11+48.29	36.25	RT	11+48.29	26.25	RT	10.00	4	SOLID	3.3
	11+48.29	26.25	RT	11+67.28	26.25	RT	18.99	4	SOLID	6.3
	11+28.00	28.75	LT	ARROW						15.6
	11+50.00	28.75	LT	"ONLY"						20.8
	10+90.00	5.75	LT	ARROW						15.6
	11+10.00	5.75	LT	"ONLY"						20.8
	10+84.00	14.25	RT	10+84.00	26.25	RT	12.00	24	SOLID	24.0
	11+10.00	20.25	RT	"RXR"						61.2
	11+34.00	14.25	RT	11+34.00	26.25	RT	12.00	24	SOLID	24.0
	11+99.00	23.25	LT	13+21.00	23.25	LT	122.00	6	SOLID	61.0
	13+21.00	23.25	LT	14+55.00	26.25	LT	134.03	6	DOTTED	16.8
	11+99.00	11.25	LT	13+86.38	14.72	LT	187.41	4	SOLID	62.5
	13+86.38	14.72	LT	14+94.68	7.73	LT	108.53	4	SOLID	36.2
	11+99.00	14.25	RT	14+35.00	9.07	RT	236.06	4	SOLID	78.7
	14+35.00	9.07	RT	14+94.55	7.51	RT	59.57	4	SOLID	19.9
	14+94.55	7.51	RT	14+94.68	7.73	LT	15.24	4	SOLID	6.1
	11+99.00	26.25	RT	14+35.69	20.95	RT	237.75	4	SOLID	79.2
	12+95.00	28.75	RT	ARROW						15.6
	13+17.00	28.75	RT	"ONLY"						20.8
	14+44.00	12.29	LT	14+44.00	23.29	LT	11.00	24	SOLID	22.0
	14+70.00	14.67	LT	"RXR"						61.2
	14+93.00	7.83	LT	14+93.00	18.83	LT	11.00	24	SOLID	22.0
	15+00.00	4.91	LT	15+24.78	2.00	LT	24.95	4	DBL YEL	15.6
	15+24.78	2.00	LT	17+28.00	2.00	LT	203.22	4	DBL YEL	135.5
	17+28.00	2.00	LT	17+89.95	0.00	LT	61.98	4	DBL YEL	41.3
	18+08.61	53.98	RT	18+32.22	48.65	RT	24.20	6	SOLID	12.1
	18+10.71	59.58	RT	18+32.17	54.74	RT	22.00	6	SOLID	11.0
	18+23.12	61.74	RT	18+32.54	58.72	RT	9.89	24	SOLID	19.8
	18+50.24	1.90	RT	19+94.74	1.62	RT	144.50	4	DBL YEL	96.3
	19+94.74	1.62	RT	21+27.23	0.00	RT	132.50	4	DBL YEL	88.3
	21+30.96	26.56	RT	21+56.88	26.66	RT	25.92	6	SOLID	13.0
	21+33.80	32.57	RT	21+54.62	32.65	RT	20.82	6	SOLID	10.4
	21+44.50	36.61	RT	21+54.00	36.65	RT	9.50	24	SOLID	19.0
	21+61.13	0.41	LT	22+64.24	1.67	LT	103.12	4	DBL YEL	68.7

SCHEDULE OF PAVEMENT MARKING REMOVAL										TOTAL	2752
FROM STATION	OFFSET	SIDE	TO STATION	OFFSET	SIDE	LENGTH (FT)	WIDTH (IN)	TYPE	SQ FT		
3+50.00	7.70	RT	6+00.00	3.60	LT	250.26	4	SKIP DASH	20.9		
6+45.00	5.50	LT	9+25.00	8.40	LT	280.02	4	DBL YEL	186.7		
6+45.00	5.50	LT	7+75.00	1.00	LT	130.08	4	DBL YEL	86.7		
7+75.00	1.00	LT	8+25.00	13.90	LT	51.64	4	DBL YEL	34.4		
CENTER SLASHES						30.00	12		30.0		
7+75.00	1.00	LT	8+25.00	1.00	LT	50.00	6	DOTTED	6.3		
8+25.00	1.00	LT	9+25.00	3.00	LT	100.02	6		50.0		
8+40.00	7.00	LT	"ONLY"						20.8		
9+25.00	8.40	LT	9+25.00	17.70	RT	26.10	24		52.2		
9+65.00	33.00	LT	9+30.00	23.30	RT	66.29	6		33.1		
9+75.00	36.00	LT	9+40.00	22.20	RT	67.91	6		34.0		
10+45.00	38.00	LT	10+28.00	28.00	RT	68.15	6		34.1		
10+50.00	36.00	LT	10+33.00	28.00	RT	66.22	6		33.1		