

SUMMARY OF QUANTITIES

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
303 03-00520-00-WR	WINNEBAGO	254	3
STA. TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	URBAN 80% FED 20% CITY		Y030-1E HWY. LIGHTING	Y031-1F SIGNALS	Y080 TRAINING
				I000 BIT. CONCRETE	J000 P. C. CONCRETE			
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	143		143			
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	216		216			
20100500	TREE REMOVAL, ACRES	ACRES	0.48		0.48			
20200100	EARTH EXCAVATION	C. Y.	42,759		42,759			
20800150	TRENCH BACKFILL	C. Y.	1,924.62		1,924.62			
21101625	TOPSOIL FURNISH AND PLACE, 6"	S. Y.	40,324		40,324			
25100115	MULCH, METHOD 2	ACRE	25.00		25.00			
25200100	SODDING	S. Y.	40,324		40,324			
25200200	SUPPLEMENTAL WATERING	UNIT	2,016		2,016			
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2,250		2,250			
28000300	TEMPORARY DITCH CHECKS	EACH	48		48			
28000400	PERIMETER EROSION BARRIER	FT.	7,179		7,179			
28000500	INLET AND PIPE PROTECTION	EACH	135		135			
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A	TON	68,978.2		68,978.2			
31200100	STABILIZED SUB-BASE 4"	S. Y.	86,428.6		86,428.6			
35101400	AGGREGATE BASE COURSE, TYPE B	TON	5,475		5,475			
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	20		20			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	23.5	7.1	16.4			
40600300	AGGREGATE (PRIME COAT)	TON	0.4		0.4			
42000401	PORTLAND CEMENT CONCRETE PAVEMENT 9" (JOINTED)	S. Y.	85,262.1		85,262.1			
42001300	PROTECTIVE COAT	S. Y.	101,210		101,210			

Deleted
6-9-06

*SPECIALTY ITEMS