

SUMMARY OF QUANTITIES

SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
03-00520-00-WR	WINNEBAGO	254	4
STA. TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT	

CODE NUMBER	PAY ITEMS	UNIT	TOTAL QUANTITY	URBAN 80% FED 20% CITY		Y030-1E HWY. LIGHTING	Y031-1F SIGNALS	Y080 TRAINING
				I000 BIT. CONCRETE	J000 P.C. CONCRETE			
42300300	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 7 INCH	S. Y.	723.2		723.2			
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	S. F.	2,578		2,578			
Added 6-9-06 42400800	DETECTABLE WARNINGS	S. F.	889		889			
44000009	BITUMINOUS SURFACE REMOVAL 3"	S. Y.	29,208	29,208				
44000100	PAVEMENT REMOVAL	S. Y.	77,703		77,703			
44000200	DRIVEWAY PAVEMENT REMOVAL	S. Y.	154		154			
44000500	COMBINATION CURB AND GUTTER REMOVAL	FT.	27,188		27,188			
44000600	SIDEWALK REMOVAL	S. F.	1,818		1,818			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FT.	491		491			
44002020	CONCRETE MEDIAN SURFACE REMOVAL	S. F.	58,324		58,324			
44004250	PAVED SHOULDER REMOVAL	S. Y.	9,537		9,537			
44200962	CLASS B PATCHES, TYPE III, 9 INCH	S. Y.	175	175				
44200964	CLASS B PATCHES, TYPE IV, 9 INCH	S. Y.	113	113				
44213200	SAW CUTS	FT.	2,050	870	1,180			
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FT.	724	724				
48100100	AGGREGATE SHOULDERS, TYPE A	TON	5.3		5.3			
48202400	BITUMINOUS SHOULDERS SUPERPAVE 6"	S. Y.	253.9		253.9			
50104400	CONCRETE HEADWALL REMOVAL	EACH	1		1			
50105220	PIPE CULVERT REMOVAL	FT.	261		261			
542A0235	PIPE CULVERTS, CLASS A, TYPE 1 30"	FT.	23		23			
54207165	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE-ELLIPTICAL, EQUIVALENT ROUND-SIZE 30"	FT.	18		18			

* SPECIALTY ITEMS