

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
343 & 1362	01-00025-04-RS	LIVINGSTON	12	12
PROJECT NO. SR-343(108)				

**SCHEDULE OF RESURFACING QUANTITIES**

Unit weight Constant = 112.0 lbs./s.y./inch

LOCATION (QUANTITY)	LENGTH	AREA (SQ YD)	BIT SURF REMOVAL VAR DEPTH (SQ YD)	SHORT- TERM PAVT MARKING (FOOT)	WORK ZONE PAVT MK REM (SQ FT)	EARTH EXCAVATION (CU YD)	AGG BSE CSE TYPE A (TON)	BITUMINOUS BSE CSE WIDENING (TON)	BIT MATLS PR CT RC-70 (GALLON)	BIT MATLS PR CT MC-30 (GALLON)	AGG PR CT (TON)	BINDER CSE SUPER, IL-19.0 N50 (TON)	BIT CONC SC, SUPER "C" N50 (TON)	INCIDENTAL BIT SURF (TON)	PAINT PVT MARKING LINE, 4" (FOOT)	AGG SHLDS TYPE B (TON)
<b>MAINLINE</b>																
530+15 to 531+15 Truck Intersection	100	550	85	(2 Apps.) 20	(1 App.) 3	250	125	125	28	98	1	(crown corr. = 22.4) 25	46	-	-	-
531+15 to 680+68	14,953	36,552	-	2,990	498	-	-	-	1,828	-	73	6,141	3,070	-	-	3,028
680+68 to 682+68 (TAPER)	200	489	147	40	7	-	-	-	24	-	-	21	41	-	-	20
682+68 to 685+21 (053-3003)	253	618	-	-	-	-	-	-	-	-	-	-	-	-	-	-
685+21 to 687+21 (TAPER)	200	489	147	40	7	-	-	-	24	-	-	21	41	-	-	20
687+21 to 816+21	12,900	31,533	-	2,580	430	-	-	-	1,577	-	63	5,298	2,649	-	-	2,612
816+21 to 817+71 (TAPER)	150	367	220	30	5	-	-	-	18	-	-	13	31	-	-	15
817+71 to 818+00 (053-3004)	29	71	-	-	-	-	-	-	4	-	-	-	6	-	-	-
818+00 to 819+50 (TAPER)	150	367	220	30	5	-	-	-	18	-	-	13	31	-	-	15
819+50 to 980+28	16,078	39,301	-	3,216	536	-	-	-	1,965	-	79	6,603	3,301	-	-	3,255
980+28 to 982+28 (TAPER)	200	489	147	40	7	-	-	-	24	-	-	21	41	-	-	20
0+11 to 1+11 Truck Intersection	100	550	-	20	3	250	90	115	28	98	1	77	46	-	-	-
1+11 to 24+40	2,329	5,693	-	466	78	-	-	-	285	-	11	956	478	-	-	472
24+40 to 26+40 (TAPER)	200	489	147	40	7	-	-	-	24	-	-	21	41	-	-	-
26+40 to 26+60 RR Crossing	20	49	-	-	-	-	-	-	-	-	-	-	-	-	-	-
26+60 to 28+60 (TAPER)	200	489	147	40	7	-	-	-	24	-	-	21	41	-	-	-
26+60 to 33+30 Thru charlotte	670	1,638	-	134	22	-	-	-	82	-	3	275	138	-	-	-
33+30 to 35+30 (TAPER)	200	489	147	40	7	-	-	-	24	-	-	21	41	-	-	20
TOTAL JOB LENGTH OR MAINLINE QUANTITY	48,932	120,223	1,407	9,726	1,622	500	215	240	5,977	196	231	19,523	10,042	0	0	9,477
<b>MISCELLANEOUS</b>																
P.E.'s, C.E.'s, and M.B.T.O.'s	-	-	98.0	-	-	-	-	-	15	714	-	208	88	311.0	-	-
SIDEROAD INTERSECTIONS (14)	-	-	-	-	-	-	-	-	126.0	-	-	98	56	210.0	-	-
<b>TOTALS OF MAINLINE &amp; MISC.</b>	<b>48,932</b>	<b>120,223</b>	<b>1,505</b>	<b>9,726</b>	<b>1,622</b>	<b>500</b>	<b>215</b>	<b>240</b>	<b>6,118</b>	<b>910</b>	<b>231</b>	<b>19,829</b>	<b>10,186</b>	<b>521</b>	<b>18,877</b>	<b>9,477</b>

SEE SHEET 2 FOR SCHEDULE

Z:\COWORK\ROAD Projects\00025RS4-ChatsRd-North\Planning\Plans\Est\Cost-Resurf\Sched-ChatsworthRd.xls\SchedResurfQty