

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	11W-3,RS-8,*	TAZEWELL	442	10
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 11BR-1, 11BR-2				

SUMMARY OF QUANTITIES			URBAN TOTAL QUANTITIES	ACF		HSIP		← ACF →		CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT		ROADWAY 20% STATE 80% FED I000-2A	ROADWAY SAFETY 10% STATE 90% FED I000-1A	STRUCTURE 090-0172 20% STATE 80% FED X071-2A	STRUCTURE 090-0174 20% STATE 80% FED X020-2A	IMPACT ATTENUATORS 20% STATE 80% FED SFTY-3N	WATER MAIN 100% VILLAGE Y060						
20100110	TREE REMOVAL (6 TO 15 UNITS DIAMETER)	UNIT	278.9	278.9											
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)	UNIT	364.1	254.5	109.6										
20100500	TREE REMOVAL, ACRES	ACRE	0.4	0.4											
20101000	TEMPORARY FENCE	FOOT	140	140											
20101100	TREE TRUNK PROTECTION	EACH	16	11	5										
X 20101200	TREE ROOT PRUNING	EACH	14		14										
X 20101350	TREE PRUNING (OVER 10 INCH DIAMETER)	EACH	13		13										
20200100	EARTH EXCAVATION	CU YD	16998	12114	4884										
20200300	EARTH EXCAVATION FOR EROSION CONTROL	CU YD	116	67	49										
20300100	CHANNEL EXCAVATION	CU YD	2529			1667	862								
20400800	FURNISHED EXCAVATION	CU YD	4160	4160											
40200040			56												
20700400	POROUS GRANULAR EMBANKMENT, SPECIAL	CU YD	403			242	161								
20800150	TRENCH BACKFILL	CU YD	1808	8	1800										
X 20800250	TRENCH BACKFILL, SPECIAL	CU YD	256							256					
X 20900210	POROUS GRANULAR BACKFILL, SPECIAL	CU YD	834							834					
21101615	TOP SOIL FURNISH AND PLACE, 4"	SQ YD	52441	41156	11285										
X 25000210	SEEDING, CLASS 2A	ACRE	11.3	9.0	2.3										
X 25000400	NITROGEN FERTILIZER NUTRIENT	POUND	1028	813	215										
X 25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	1028	813	215										
X 25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	1028	813	215										
X 25000750	MOWING	ACRE	16	16											
25100115	MULCH, METHOD 2	ACRE	9.4	7.7	1.7										
25100630	EROSION CONTROL BLANKET	SQ YD	9285	6387	2898										
X 25200100	SODDING	SQ YD	1002		1002										
28000250	TEMPORARY EROSION CONTROL SEEDING	POUND	2256	1806	450										
28000300	TEMPORARY DITCH CHECKS	EACH	37	25	12										
28000400	PERIMETER EROSION BARRIER	FOOT	9129	4827	4302										
28000500	INLET AND PIPE PROTECTION	EACH	47	9	38										
28000510	INLET FILTERS	EACH	17		17										

(X) SPECIALTY ITEM