

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	11W-3,RS-8,*	TAZEWELL	442	45
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
• 11BR-1, 11BR-2				

BITUMINOUS SURFACE REMOVAL - BUTT JOINT	
LOCATION	SQ YD
IL 29	
STA. 245+96.75 - 246+06.75	105
STA. 334+11.5 - 334+21.5	82
PARK DRIVE	
STA. 28+81 - 28+96	43
N. RIVER DRIVE	
STA. 8+47.5 - 8+62.5	37
N. FOREST DRIVE	
STA. 50+83.32 - 50+98.32	33
S. RIVER DRIVE	40
S. FOREST DRIVE	
STA. 61+21.72 - 61+36.72	36
ELM ST.	
STA. 71+19 - 71+34	48
ENTRANCE IL 29 STA. 254+69 LT	128
TOTAL	552

DRIVEWAY PAVEMENT REMOVAL	
LOCATION	SQ YD
STA. 259+97 RT	6.49
STA. 260+56 RT	2.96
STA. 260+82 RT	6.46
STA. 261+69 RT	7.40
STA. 262+64 LT	14.61
STA. 264+18 LT	19.26
STA. 264+25 RT	5.77
STA. 264+66 LT	24.80
STA. 264+80 LT	30.41
STA. 264+83 RT	4.87
STA. 265+24 LT	29.74
STA. 265+79 LT	6.41
STA. 266+34 LT	13.74
STA. 267+57 LT	7.07
STA. 267+74 LT	10.30
STA. 268+14 RT	7.46
STA. 269+86 LT	9.28
STA. 270+35 RT	8.75
STA. 270+49 LT	6.53
STA. 270+95 RT	7.60
STA. 272+17 LT	5.53
STA. 303+18 LT	198
STA. 305+31 LT	195
WATER MAIN	
STA. 303+18 LT	47.91
TOTAL	676

COMBINATION CURB AND GUTTER REMOVAL	
LOCATION	FOOT
STA. 280+09 - 282+95	180
STA. 307+16 - 314+22	1422
STA. 314+50 - 315+75	264
STA. 317+86 - 321+31	695
STA. 329+60 - 334+11.4	452
WEST LANE	
STA. 80+71 - 81+07.3 LT	36
STA. 80+75 - 81+07.3 RT	32
TOTAL	3081

PAVEMENT REMOVAL		
LOCATION	THICKNESS	SQ YD
N. RIVER DRIVE	8"	48
HIGHWAY BLVD 1	4"	2761
HIGHWAY BLVD 2	4"	2534
N. FOREST DR.	8"	33
S. RIVER DR.	8"	35
S. FOREST DR.	8"	47
IL 29		
STA. 273+22 - 275+54 RT	6"	544
STA. 274+68.76 - 275+63.32	13"	555
STA. 275+91.79 - 277+56.23	13"	843
STA. 279+68 - 281+01 RT	6"	508
STA. 280+81 LT	8"	8
STA. 300+14.15 - 301+32.42	13"	680
STA. 302+78.52 - 303+61.65	13"	429
WEST LANE	8"	426
ELM ST. TEMPORARY ACCESS	8"	199
TOTAL		9650

MEDIAN REMOVAL (PARTIAL DEPTH)	
LOCATION	SQ FT
STA. 257+30 - 258+42	326
STA. 259+08 - 261+26	623
STA. 261+91 - 272+88	3185
STA. 273+53 - 274+16	184
STA. 282+95 - 300+14.15	5160
STA. 303+61.65 - 303+78	48
STA. 304+45 - 305+09	184
STA. 305+53 - 305+89	102
STA. 306+54 - 307+16	179
STA. 321+31 - 329+60	2307
TOTAL	12298

BITUMINOUS SURFACE REMOVAL - BUTT JOINT (SPECIAL)	
LOCATION	SQ YD
STA. 251+25 - 251+66	286
STA. 333+66.5 - 334+11.5	353
TOTAL	639

BITUMINOUS SHOULDER REMOVAL	
LOCATION	SQ YD
STA. 246+06.75 - 249+92.31 LT	320
STA. 308+04.65 - 313+62.86 LT	646.11
STA. 330+40 - 334+11.46 RT	62
TOTAL	1028

CLASS C PATCHING SCHEDULE			
LOCATION	TYPE II, 13"	TYPE III, 13"	TYPE IV, 13"
	SQ YD (No.)	SQ YD (No.)	SQ YD (No.)
SB LANES			
STA. 246+06.75 - LITTLE LICK CREEK	128 (16)	40 (2)	27 (1)
LITTLE LICK CREEK - LICK CREEK	104 (13)		
LICK CREEK - STA. 334+41	64 (8)		93 (3)
NB LANES			
STA. 246+06.75 - LITTLE LICK CREEK	296 (37)		40 (1)
LITTLE LICK CREEK - LICK CREEK	232 (29)		27 (1)
LICK CREEK - STA. 334+41	160 (20)		
SUB-TOTAL	984	40	187
15% WINTER BREAK-UP	148	6	28
TOTAL SQ YD	1132	46	215

CLASS D PATCHING SCHEDULE		
LOCATION	TYPE I, 8"	TYPE III, 8"
	SQ YD (No.)	SQ YD (No.)
STAGE II		
IL 29 STA. 274+35 RT		24 (1)
S. RIVER DRIVE STA. 69+48		22 (1)
ELM ST. STA. 70+66		35 (2)
STAGE IV		
N. FOREST DRIVE STA. 50+44		19 (1)
S. RIVER DRIVE STA. 60+96	8 (2)	
S. FOREST DRIVE STA. 60+46.5		20 (1)
TOTAL SQ YD	8	120

CONSTRUCTING TEST STRIP	
LOCATION	EACH
X4066536 - POLY. BCSC, SP, MIX E, N 70	1
X4066656 - POLY. BCBC, SP, IL-19.0, N70	1
TOTAL	2

NOTE: QUANTITIES PROPOSED FOR FEDERAL SAFETY FUNDS ARE FROM STA 251+80 TO STA 282+00.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		SCHEDULES OF QUANTITIES