CONTRACT NO. 88804

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	11W-3,RS-8,*	TAZEWELL	442	46
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* 11BR-1, 11BR-2

MEDIAN REMOVAL

LOCATION	SQ FT
STA. 274+97 - 275+13.85(BK) / 274+91.42(AH) - 275+48	210
STA. 276+06 - 276+64	162
STA. 277+31 - 277+58	93
STA. 278+24 - 278+45	111
STA. 279+09 - 282+00	1953
STA. 282+00 - 282+09	32
STA. 300+14.15 - 300+87	208
STA. 301+30 - 301+36	15
STA. 302+76 - 302+84	19
STA. 303+27 - 303+61.65	103
STA. 329+60 - 334+00	3408
TOTAL	6314

PAVEMENT REMOVAL (SPECIAL)

LOCATION	SQ YD
STA 275+05 (BK) - STA 275+30 (AH)	105.4
STA 276+23 - STA 276+73	111.11
STA 300+85 - STA 301+30.06	100.13
STA 322+84.61 - STA 331+01.69	286.36
TOTAL	603.0

TEMPORARY PAVEMENT

LOCATION	SQ YD
STAGE 2	
LITTLE LICK CREEK	
STA. 274+68.8 - STA. 275+13.85 (BK) LT	21
STA. 274+91.42 (AH) - STA. 275+33.5 LT	20
STA. 275+89.7 - STA. 276+82 LT	58
LICK CREEK	
STA. 300+13.9 LT - STA. 301+36 LT	48
STA. 302+76 LT - STA. 303+61.6 LT	34
TOTAL	181

TEMPORARY PAVEMENT REMOVAL

LOCATION	SQ YD
STAGE 2	
LITTLE LICK CREEK	
STA. 274+68.8 - STA. 275+13.85 (BK) LT	21
STA. 274+91.42 (AH) - STA. 275+33.5 LT	20
STA. 275+89.7 - STA. 276+82 LT	58
LICK CREEK	
STA. 300+13.9 LT - STA. 301+36 LT	48
STA. 302+76 LT - STA. 303+61.6 LT	34
TOTAL	181

REMOVAL OF EXISTING STRUCTURES

LOCATION	EACH
STA 275+77.36, EX STR 090-0048	1
STA 302+06, EX STR 090-0049	1
TOTAL	2

STRUCTURE EXCAVATION

LOCATION	CU YD
STA 275+77.36, STR 090-0174	331
STA 301+87.90, STR 090-0172	136
TOTAL	467

FLOOR DRAINS

LOCATION	EACH
STA 275+77.36, STR 090-0174	18
STA 301+87.90, STR 090-0172	8
TOTAL	26

CONCRETE STRUCTURES

LOCATION	CU YD
STA 275+77.36, STR 090-0174	225.8
STA 301+87.90, STR 090-0172	256.6
TOTAL	482.4

CONCRETE SUPERSTRUCTURE

LOCATION	CU YD
STA 275+77.36, STR 090-0174	316.3
STA 301+87.90, STR 090-0172	364.0
TOTAL	680.3

REVETMENT MAT REMOVAL

LOCATION	SQ YD
STA 255+76, 71' RT	26
LITTLE LICK CREEK (FOR SS INSTALLATION)	
STA 275+87, 60' RT	50
STA 275+18 (AH), 64' LT	30
STA 275+62, 61' LT	36
TOTAL	142

STORM SEWER REMOVAL 18"

LOCATION	FOOT
IL 29 STA 280+02, 44.18' - 55.18' LT	11
TOTAL	11

STORM SEWER REMOVAL 36"

LOCATION	FOOT
STA 301+32.92, 75.76' LT - STA 301+66.88, 69.98' LT	40
TOTAL	40

FILL EXISTING STORM SEWERS

LOCATION	CU YD
STA 258+05, 1' TO 51' RT	2.3
STA 259+68, 1' LT - STA 279+74, 45' LT	2.9
STA 280+02, ℄ TO 44.18' RT	2.9
STA 309+05, 1' LT TO 53' RT	2.5
TOTAL	10.6

PILE REMOVAL

LOCATION	EACH
STA. 274+58, 55' RT	1
TOTAL	1

CONCRETE HEADWALL REMOVAL

LOCATION	EACH
STA 255+51.77, 47.19' LT	1
STA 255+70.54, 60.07' RT	1
STA 312+42.11, 50.12' LT	1
STA 321+89.48, 53.19' LT	1
TOTAL	4

BUILDING REMOVAL NO. 1

LOCATION	L SUM
STA. 303+50 RT. (HUBCAP HOUSE)	1
TOTAL	1

REMOVAL AND DISPOSAL OF NON-FRIABLE ASBESTOS, BUILD. NO. 1

LOCATION	L SUM
STA. 303+60, 80' RT. (HUBCAP HOUSE)	1
TOTAL	1

CONCRETE REMOVAL

LOCATION	CU YD
STA. 300+90, 35' RT	1.5
STA. 301+30, 35' RT	1.5
TOTAL	3

NOTE: ITEMS TO BE REMOVED ARE CONCRETE BLOCKS AT ENTRANCE TO IDNR PROPERTY.

POROUS GRANULAR EMBANKMENT, SPECIAL

LOCATION	CU YD
STRUCTURE	
STA 275+77.36, STR 090-0174	161.2
TOTAL	161.2

REMOVAL OF EXISTING STRUCTURES NO. 1

LOCATION	EACH
IL 29 STA. 322+16, 97' LT	1
TOTAL	1

REMOVAL OF EXISTING STRUCTURES NO. 2

LOCATION	EACH
IL 29 STA. 276+48 RT TO STA. 277+11 RT	1
TOTAL	1

REMOVAL OF EXISTING STRUCTURES NO. 3

LOCATION	EACH
IL 29 STA. 278+37 RT TO STA. 279+97 RT	1
TOTAL	1

REMOVAL OF EXISTING STRUCTURES NO. 4

LOCATION	EACH
IL 29 STA. 304+67 LT TO STA. 304+77 LT	1
TOTAL	1

REMOVAL OF EXISTING STRUCTURES NO. 5

LOCATION	EACH
IL 29 STA. 305+70 LT TO STA. 306+07 LT	1
TOTAL	1

REMOVAL OF EXISTING STRUCTURES NO. 6

LOCATION	EACH
IL 29 STA. 258+10, 58' RT	1
TOTAL	1

REMOVAL OF EXISTING STRUCTURES NO. 7

LOCATION	EACH
IL 29 STA. 258+26.5 RT	1
TOTAL	1

NOTE: QUANTITIES PROPOSED FOR FEDERAL SAFETY FUNDS ARE FROM STA 251+80 TO STA 282+00.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

PLOT DATE = 4/18/2006
FILE NAME = c:\pr\ujacob\29peksrt\phase.11\misc.dgn
PLOT SCALE = 50.0000 ' / IN.
REFERENCE = WEF