

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	11W-3,RS-8.*	TAZEWELL	442	51
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		
* 11BR-1, 11BR-2				

GUARDRAIL AND BARRIER WALL MARKER SCHEDULE

LOCATION	GUARDRAIL MARKERS, TYPE A EACH	BARRIER WALL MARKERS, TYPE B EACH	BARRIER WALL MARKERS, TYPE C EACH
SOUTHBOUND			
STA 259+98.48, 38.00' RT - STA 271+63.27, 38.00' RT NO REFLECTORS IN FIRST 50', SPACE 6 AT 80' ON CENTER (O-C) & 1 AT 400'	7		
STA 274+74.03, 45.60' RT - STA 275+59.38, 38.14' RT NO REFLECTORS IN FIRST 50', SPACE 2 AT 46.5' O-C	2		
STA 275+59.38, 38.14' RT - STA 276+39.11, 38.14' RT CONTINUE 46.5' O-C SPACING FROM GUARDRAIL MARKERS		2	2
STA 299+40.80, 42.00' RT - STA 300+30.59, 42.00' RT NO REFLECTORS IN FIRST 50', SPACE 4 AT 12.5' O-C	4		
STA 300+55.52, 45.14' RT - STA 301+29.06, 42.14' RT NO REFLECTORS IN FIRST 50', THEN PLACE 1 MARKER	1		
STA 301+29.06, 42.14' RT - STA 302+64.06, 42.14' RT PLACE 3 MARKERS AT 56' O-C FROM GUARDRAIL MARKER		3	3
STA 312+70.37, 42.00' RT - STA 333+73.55, 36.98' RT NO REFLECTORS IN FIRST 50', PLACE 6 AT 80' O-C & 4 AT 400' O-C	10		
NORTHBOUND			
STA 307+57.92, 42.00' LT - STA 314+77.74, 42.00' LT NO REFLECTORS IN FIRST 50', SPACE 6 AT 80' O-C	6		
STA 302+87.05, 69.11' LT - STA 302+46.74, 42.14' LT NO REFLECTORS IN FIRST 5' OF TY 2 TERMINAL, STARTING AT THE TY-2 TERMINAL, PLACE 2 AT 20' O-C & 1 AT 40' O-C	3		
STA 302+46.74, 42.14' LT - STA 301+11.74, 42.14' LT PLACE 1 MARKER AT 65' O-C FROM LAST GAURDRAIL MARKER, THEN 1 AT 80' O-C		2	2
STA 300+35.84, 42.00' LT - STA 305+00.63, 42.00' LT NO REFLECTORS IN FIRST 50', SPACE 4 AT 37.5' O-C	4		
STA 278+32.21, 38.00' LT - STA 277+67.42, 38.00' LT NO REFLECTORS IN FIRST 50', SPACE 4 AT 4' O-C	4		
STA 276+87.30, 107.30' LT - STA 275+95.34, 38.14' LT NO REFLECTORS IN FIRST 5' OF TY 2 TERMINAL, STARTING AT THE TY-2 TERMINAL, PLACE 5 AT 20' O-C & 1 AT 40' O-C	6		
STA 275+95.34, 38.14' LT - STA 275+13.01, 38.14' LT PLACE 1 MARKER AT 65' O-C FROM LAST GAURDRAIL MARKER		1	1
TOTAL	47	8	8

* ALL GURDRAIL MARKERS AND BARRIER WALL MARKERS ARE MONODIRECTIONAL SILVER.

NOTE: QUANTITIES PROPOSED FOR FEDERAL SAFETY FUNDS ARE FROM STA 251+80 TO STA 282+00.

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

DATE

PLOT DATE = 4/18/2006
 PLOT SCALE = 500000 / IN.
 PLOT SCALE = 500000 / IN.
 BBERRONSE = #4655A