

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	11W-3,RS-8,*	TAZEWELL	442	56
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
* 11BR-1, 11BR-2				

RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	
LOCATION	EACH
NORTHBOUND LANES	
STA 245+76.75 - STA 251+80 LT	4
STA 251+80 - STA 282+00 LT	38
STA 282+00 - STA 301+35 LT	24
(BRIDGE OMMISION - LICK CREEK)	
STA 302+80 - STA 334+41.46 LT	37
SOUTHBOUND LANES	
STA 245+76.75 - STA 251+80 RT	4
STA 251+80 - STA 282+00 RT	30
STA 282+00 - STA 301+35 RT	23
(BRIDGE OMMISION - LICK CREEK)	
STA 302+80 - STA 334+41.46 RT	37
MEDIAN	
STA 245+76.75 - STA 251+80 LT & RT	8
STA 251+80 - STA 256+00 LT & RT	30
TOTAL	235

WORK ZONE PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
STAGE 3	
STA. 269+50 - 271+50	
MEDIAN	133
DIAGONALS	25
STA. 282+00 - 296+00	
MEDIAN	467
STA. 308+00 - 312+00	
MEDIAN	267
DIAGONALS	77
STA. 312+00 - 319+00	
MEDIAN	233
DIAGONALS	178
SOUTH RIVER DR.	187
STAGE 4	
STA. 278+00 - 296+00	
MEDIAN	600
STA. 312+00 - 324+00	
MEDIAN	400
DIAGONALS	24
ELM ST. (TEMP. ACCESS DR.)	576
WEST LANE	200
AMVETS (TEMP. ACCESS DR.)	307
STAGE 5	
STA. 246+06 - 275+13.85(BK) / 274+91.42(AH) - 334+41	
ROADWAY	1181
SHOULDERS	236
TOTAL	5091

PAVEMENT MARKING REMOVAL	
LOCATION	SQ FT
STAGE III	
STA. 268+00 - 279+00	
SKIPS	92
SOLID	367
STA. 279+00 - 295+00	
SKIPS	133
STA. 295+00 - 308+00	
SKIPS	108
SOLID	433
STA. 308+00 - 320+00	
SKIPS	100
STAGE IV	
STA. 267+00 - 270+50	
SKIPS	29
STA. 270+50 - 280+00	
SKIPS	79
SOLID	317
STA. 280+00 - 295+50	
SKIPS	129
STA. 295+50 - 309+00	
SKIPS	113
SOLID	450
STA. 309+00 - 327+50	
SKIPS	154
AMVETS PARKING LOT	50
TOTAL	2554

REMOVE RIGHT-OF-WAY MARKERS	
LOCATION	EACH
STA. 312+01.47, 57.16' LT	1
STA. 313+01.60, 52.15' LT	1
STA. 314+50.83, 48.96' LT	1
STA. 317+02.83, 57.36' LT	1
STA. 321+66.13, 79.83' LT	1
TOTAL	5

BILLBOARD REMOVAL	
LOCATION	EACH
STA. 258+59.18, 57.05' RT	1
STA. 288+64.51, 54.05' RT	1
STA. 291+56.67, 50.00' RT	1
STA. 293+19.15, 52.72' RT	1
STA. 296+34.80, 54.22' RT	1
STA. 297+61.50, 55.35' RT	1
STA. 299+47.43, 52.19' RT	1
STA. 300+47.79, 46.65' RT	1
STA. 325+80.54, 65.89' LT	1
TOTAL	9

STEEL POST REMOVAL	
LOCATION	EACH
STA. 277+25.20, 110.9' LT	1
STA. 277+25.5, 106.5' LT	1
TOTAL	2

REMOVE SIGN COMPLETE	
LOCATION	SQ FT
STA. 301+31.10, 82.95' LT	
3 PANELS 12'x25' IN SIZE	900
TOTAL	900

TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
STAGE 3 LITTLE LICK CREEK BRIDGE	
STA. 273+66 - 279+25	590
LICK CREEK BRIDGE	
STA. 298+37.5 - 305+45.6	720
STAGE 4	
RT. STA. 303+04 - 303+84	80
TOTAL	1390

RELOCATE TEMPORARY CONCRETE BARRIER	
LOCATION	FOOT
LITTLE LICK CREEK BRIDGE	
STA. 273+53.4 - 279+24.9	610
LICK CREEK BRIDGE	
STA. 298+37.2 - 304+82	660
RT. STA. 302+64 - 303+04	40
TOTAL	1310

CONCRETE FILLED STEEL POST REMOVAL	
LOCATION	EACH
STA. 273+54.10, 58.7' RT	1
STA. 273+56.70, 58.6' RT	1
TOTAL	2

SIGN REMOVAL	
LOCATION	EACH
STA. 258+10, 58' RT	1
STA. 273+65.10, 60.98' RT	1
STA. 274+01.93, 58.51' RT	1
STA. 303+66.11, 46.42' RT	1
STA. 304+59.34, 29.68' RT	1
STA. 305+86.55, 75.46' LT	1
TOTAL	6

MISC. SCHEDULES		
LOCATION	UNIT	TOTAL
ENGINEER'S FIELD OFFICE, TY. A, (SPECIAL)	CAL MO	18
ENGINEER'S FIELD LABORATORY, (SPECIAL)	CAL MO	18
TRAINEES	HOURL	1500
MOBILIZATION	L SUM	1
CONSTRUCTION LAYOUT	L SUM	1
RAILROAD PROTECTIVE LIABILITY INSURANCE	L SUM	1

NOTE: QUANTITIES PROPOSED FOR FEDERAL SAFETY FUNDS ARE FROM STA 251+80 TO STA 282+00.

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION
NAME	DATE	
		<p>SCHEDULES OF QUANTITIES</p>