

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
669	11W-3,RS-8,•	TAZEWELL	442	59
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
• 11BR-1, 11BR-2				

TRENCH BACKFILL, SPECIAL	
LOCATION	CU YD
WATER MAIN	
STA. 302+50 - 303+75 LT	41.2
STA. 305+13 - 305+49 LT	11.9
STA. 307+25 - 312+20 LT	163
STA. 317+25 - 318+10 LT	28
STA. 334+11 LT	11.5
TOTAL	256

POROUS GRANULAR BACKFILL, SPECIAL	
LOCATION	CU YD
WATER MAIN	
STA. 282+50 - 301+00 LT	279.6
STA. 301+00 - 302+50 LT	24.2
STA. 302+50 - 307+00 LT	68.2
STA. 307+00 - 312+24 LT	80.4
STA. 312+24 - IL 29/IL 98	361.6
WEST LANE	15.1
IL 29/IL 98	4.5
TOTAL	833.6

FIRE HYDRANTS TO BE REMOVED	
LOCATION	EACH
WATER MAIN	
STA 303+46 LT	1
STA 306+81 RT	1
TOTAL	2

FIRE HYDRANTS	
LOCATION	EACH
WATER MAIN	
STA. 305+00 LT	1
STA. 323+00 LT	1
STA. 327+50 LT	1
STA. 332+00 LT	1
IL 29 / IL 98	1
WEST LANE	
TOTAL	6

STOPS & BOX SCHEDULE			
LOCATION	CURB BOX	CURB STOPS, 1"	CORP. STOPS, 1"
WATER MAIN			
STA. 304+00 LT (AMVETS)	1	1	1
STA. 305+00 LT (SANDROCK)	1	1	1
TOTAL	2	2	2

WATER MAIN CASING PIPE	
LOCATION	FOOT
WATER MAIN	
STA. 289+00 - 289+30 LT	30
STA. 301+74 - 302+01 LT	30
STA. 307+20 - 307+56 LT	40
STA. 307+88 - 308+13 LT	25
STA. 310+58 - 310+83 LT	25
STA. 312+00 - 312+25 LT	25
STA. 312+46 - 312+71 LT	25
STA. 313+56 - 313+81 LT	25
STA. 318+00 - 318+42 LT	45
IL 29 / IL 98	25
TOTAL	295

WATER MAIN SCHEDULE									
LOCATION	WATER MAIN, 10"	WATER MAIN, 6" PVC	WATER SERVICE LINE, 1"	REMOVE EXISTING WATER MAIN	ABANDON EXISTING WATER MAIN	WATER MAIN, 8" PVC	CONNECT TO EXISTING WATER MAIN, 4"	CONNECT TO EXISTING WATER MAIN, 6"	CONNECT TO EXISTING WATER MAIN, 8"
	FOOT	FOOT	FOOT	FOOT	EACH	FOOT	EACH	EACH	EACH
WATER MAIN									
STA. 282+50 LT									1
STA. 282+50 - 301+00 LT						1846			
STA. 302+50 - 307+00 LT						450			
STA. 312+24 - IL 29/IL 98						2387			
STA. 307+00 - 312+24 LT	531								
IL 29 / IL 98		30			1			1	
STA. 304+00 LT (AMVETS)			50						
STA. 305+00 LT (SANDROCK)			50						
WEST LANE STA. 80+56 - 81+44 LT				88		100	1		
TOTAL	531	30	100	88	1	4783	1	1	1

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SCHEDULES OF QUANTITIES

NOTE: QUANTITIES PROPOSED FOR FEDERAL SAFETY FUNDS ARE FROM STA 251+80 TO STA 282+00.

PLOT DATE = 4/18/2005  
 FILE NAME = c:\pcc\mca\29\pcc\mca\pcc\11\mca\pcc.dgn  
 PLOT SCALE = 50.0000 / IN.  
 REFERENCE = \*REF\*