

April 12, 2006
 C:\24\2006\240619A\Canton Ash St. & 11th Ave. (Phase 3) Final Eng. Sacs\040206\01-RSC\CONSTRUCTION\Plan\11-TABULATIONS.dwg

FAU. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
*	04-00093-00-RS	FULTON	11	5

CONTRACT NO. 80370

STATION TO STATION	SIDEWALK REMOVAL SQ. FT.	PORTLAND CEMENT CONCRETE SIDEWALK 4" SQ. FT.	DETECTABLE WARNINGS SQ. FT.	COMBINATION CURB AND GUTTER REMOVAL FOOT	COMBINATION CONCRETE CURB & GUTTER, TYPE B-6.18 FOOT	DRIVEWAY PAVEMENT REMOVAL & REPLACEMENT			PAVEMENT REMOVAL SQ. YD.	INCIDENTAL BITUMINOUS SURFACING TON	MANHOLES TO BE ADJUSTED EACH	VALVE BOXES TO BE ADJUSTED EACH
						CONCRETE	BITUMINOUS	GRAVEL				
						SQ. YD.	SQ. YD.	SQ. YD.				
ASH STREET - LT 21+76 - 22+57				40	40							
LT 22+57 - 25+80	108	96	12	298	298	15.3						
LT 25+80 - 28+72	117	93	24	285	285	8.4		4.0				
LT 28+72 - 32+04	104	92	12	301	301	8.6	2.7	2.0		1		
LT 32+04 - 35+07	1040	1028	12	248	248	24.6	5.8			1		3
LT 35+07 - 38+09	7	7		268	268			10.4				1
LT 38+09 - 40+31				182	182	5.3						
LT 40+31 - 44+54	203	203		408	408	17.3		5.1				
ASH STREET - RT 21+76 - 29+62	112	112		720	720	18.9	20					
RT 29+62 - 32+95	55	49	6	295	295	4.2			20.2	7		
RT 32+95 - 36+48	66	60	6	353	353	13.8			5.8	3		1
RT 36+48 - 38+09				161	161			3.1				
RT 38+09 - 44+54				600	600	18.5	9.5					
ASH STREET - 44+54 - 68+72				20	20							
11TH AVENUE - 0+00 - 12+82				50	50							
TOTAL	1812	1740	72	4229	4229	134.9	38.0	24.6	26.0	10	2	5

LOCATION	EACH
11TH AVENUE - STA. 0+00 TO STA. 12+82	6
ASH STREET - STA. 21+76 TO STA. 68+72	29
TOTAL	35

LOCATION	EACH
ASH STREET - STA. 21+76 TO STA. 68+72	4
TOTAL	4

LOCATION	EACH
ASH STREET - STA. 21+76 TO STA. 68+72	10
TOTAL	10

LOCATION	SQ. YDS.
11TH AVENUE - VARIOUS LOCATIONS	100
ASH STREET - VARIOUS LOCATIONS	94
TOTAL	194

LOCATION	TON
VARIOUS LOCATIONS	13
TOTAL	13

LOCATION	FOOT
ASH ST. AND 11TH AVE.	1372
TOTAL	1372

LOCATION	SQ. FT.
ASH ST. AND 11TH AVE.	175
TOTAL	175

LOCATION	FOOT
ASH ST. AND 11TH AVE	1440
TOTAL	1440

CROSSWALKS AT:	FEET
ASH STREET - AT 13TH AVE. - 2 @ 38'	76
- WEST SIDE OF 14TH AVE. - 2 @ 34' =	68
- WEST SIDE OF 15TH AVE. - 2 @ 38' =	76
- NORTH SIDE OF ASH ON 15TH AVE. - 2 @ 34' =	68
- AT ORCHID STREET - 2 @ 34' =	68
TOTAL	356

LOCATION	APPROX LENGTH (FEET)
11TH AND CHESTNUT - NORTH SIDE	14
11TH AND ASH - NORTH SIDE	14
- SOUTH SIDE	14
- EAST SIDE	17
- WEST SIDE	12
15TH AND ASH - NORTH SIDE	14
- SOUTH SIDE	14
- EAST SIDE	17
- WEST SIDE	17
TOTAL	133

LOCATION	TON
11TH AVENUE - STA. 0+00 TO STA. 12+82	4.5
ASH STREET - STA. 21+76 TO STA. 44+54	6
STA. 44+54 TO STA. 50+38	2
STA. 50+38 TO STA. 68+72	7
SIDE STREETS - VARIOUS LOCATIONS	1.5
TOTAL	21

LOCATION	GALS
11TH AVENUE - STA. 0+00 TO STA. 12+82	134
ASH STREET - STA. 21+76 TO STA. 44+54	175
STA. 44+54 TO STA. 50+38	62
STA. 50+38 TO STA. 68+72	202
SIDE STREETS - VARIOUS LOCATIONS	40
TOTAL	613

LOCATION	SQ. YD.
11TH AVENUE - STA. 0+00 TO STA. 12+82	3989
ASH STREET - STA. 21+76 TO STA. 44+54	5822
STA. 44+54 TO STA. 50+38	2077
STA. 50+38 TO STA. 68+72	6725
SIDE STREETS - VARIOUS LOCATIONS	1320
TOTAL	19933

LOCATION	TON
11TH AVENUE - STA. 0+00 TO STA. 12+82	359
ASH STREET - STA. 21+76 TO STA. 44+54	518
STA. 44+54 TO STA. 50+38	145
STA. 50+38 TO STA. 68+72	565
SIDE STREETS - VARIOUS LOCATIONS	111
TOTAL	1698

LOCATION	SQ. YDS.
11TH AVENUE - STA. 0+00 TO STA. 12+82	2049
ASH STREET - STA. 21+76 TO STA. 44+54	6581
STA. 44+54 TO STA. 50+38	779
STA. 50+38 TO STA. 68+72	2550
SIDE STREETS - VARIOUS LOCATIONS	1320
TOTAL	13279

LOCATION	L. SUM
11TH AVENUE - ASH STREET	
STANDARD 701501	1.0
11TH AVENUE - ASH STREET	
STANDARD 701801	1.0

LOCATION	L. SUM
PROJECT	1.0
TOTAL	1.0

LOCATION	SQ. FT.
11TH AVENUE	
AT CHESTNUT STREET	15.6
VARIOUS SIDE STREETS	62.2
ASH STREET	
AT 5TH AVENUE	12.8
VARIOUS SIDE STREETS	295.6
AT 15TH AVENUE	18.3
TOTAL	404.5

LOCATION	EACH
ASH ST. - STA. 21+76 - STA. 44+54	16
TOTAL	16



FOR: CITY OF CANTON, ILLINOIS			
REVISIONS	DATE	PROJECT NO.	
DESIGNED	04/14/06	234-06013A	
CHECKED		DRAWING NO.	
DRAWN	JAM	1	
FIELD BK.	CHECKED GBM	SHEET 1 OF 1	