

## SCHEDULES OF QUANTITIES

**PIPE UNDERDRAIN SCHEDULE ( CONTINUED )**

FROM STATION	SHOULDER CUT ( INCHES )	PAVEMENT ELEV. AT		CROSS-SLOPE [ % ]	TO STATION	SHOULDER CUT ( INCHES )	PAVEMENT ELEV. AT		CROSS-SLOPE [ % ]	PAVEM. T SLOPE [ % ]	DRAIN SLOPE [ % ]	PIPE UNDERDRAIN 4"	PIPE UNDERDRAIN 4" ( SPECIAL )	PIPE UNDERDRAIN 6"	PIPE UNDERDRAIN 6" ( SPECIAL )	CONCRETE HEADWALL FOR PIPE UNDERDRAIN	EROSION CONTROL BLANKET	
		DRAIN	PGL				60107600 ( FEET )	60108100 ( FEET )				60107700 ( FEET )	60108200 ( FEET )	60100060 ( EACH )	25100630 ( SQ. YD. )			
<b>CURTIS ROAD</b>																		
3+42.00	RT.	24.0	702.03	702.03	7+92.00	RT.	24.0	704.28	704.28		0.50	F E P P	450.0	46.0		1.0	4.0	
7+92.00	RT.	24.0	704.28	704.28	12+42.00	RT.	24.0	706.53	706.53		0.50	F E P P	450.0	46.0		1.0	4.0	
12+42.00	RT.	24.0	706.53	706.53	16+92.00	RT.	24.0	711.50	711.50		VAR	F E P P	450.0	46.0		1.0	4.0	
16+92.00	RT.	24.0	711.50	711.50	21+31.75	RT.	24.0	718.10	718.10		1.50	F E P P	439.8	46.0		1.0	4.0	
4+79.00	LT.	24.0	702.72	702.72	7+92.00	LT.	24.0	704.28	704.28		0.50	F E P P	313.0	46.0		1.0	4.0	
7+92.00	LT.	24.0	704.28	704.28	12+42.00	LT.	24.0	706.53	706.53		0.50	F E P P	450.0	46.0		1.0	4.0	
12+42.00	LT.	24.0	706.53	706.53	16+92.00	LT.	24.0	711.50	711.50		VAR	F E P P	450.0	46.0		1.0	4.0	
16+92.00	LT.	24.0	711.50	711.50	20+82.58	LT.	24.0	717.36	717.36		1.50	F E P P	390.6	46.0		1.0	4.0	
22+42.67	RT.	24.0	719.76	719.76	22+82.13	RT.	24.0	720.36	720.36		1.50	F E P P	39.5	51.0		1.0	4.0	
22+82.13	RT.	24.0	720.36	720.36	26+74.30	RT.	24.0	724.58	724.58		VAR	F E P P	392.2					
22+42.67	RT.	24.0	719.76	719.76	26+74.30	LT.	24.0	724.58	724.58		VAR	F E P P	431.6	57.0		1.0	4.0	
29+66.30	RT.	24.0	724.62	724.62	33+96.26	LT.	24.0	719.93	719.93		VAR	F E P P	430.0	57.0		1.0	4.0	
29+66.30	LT.	24.0	724.62	724.62	33+56.04	LT.	24.0	720.53	720.53		VAR	F E P P	389.7					
33+56.04	LT.	24.0	720.53	720.53	33+96.26	LT.	24.0	719.93	719.93		-1.50	F E P P	40.2	51.0		1.0	4.0	
35+53.06	RT.	24.0	717.58	717.58	39+19.00	RT.	24.0	713.04	713.04		VAR	F E P P	365.9					
39+19.00	RT.	24.0	713.04	713.04	39+82.27	RT.	26.0	712.92	712.92		VAR	0.45	63.3	46.0		1.0	4.0	
39+82.27	RT.	26.0	712.92	712.92	40+46.00	RT.	24.0	713.04	713.04		VAR	0.45	63.7	46.0		1.0	4.0	
40+46.00	RT.	24.0	713.04	713.04	44+73.00	RT.	24.0	720.04	720.04		VAR	F E P P	427.0					
44+73.00	RT.	24.0	720.04	720.04	48+37.00	RT.	24.0	728.42	728.42		2.30	F E P P	364.0	46.0		1.0	4.0	
35+01.26	LT.	24.0	718.36	718.36	39+19.00	LT.	24.0	713.04	713.04		VAR	F E P P	417.7					
39+19.00	LT.	24.0	713.04	713.04	39+82.27	LT.	26.0	712.92	712.92		VAR	0.45	63.3	46.0		1.0	4.0	
39+82.27	LT.	26.0	712.92	712.92	40+46.00	LT.	24.0	713.04	713.04		VAR	0.45	63.7	46.0		1.0	4.0	
40+46.00	LT.	24.0	713.04	713.04	44+73.00	LT.	24.0	720.04	720.04		VAR	F E P P	427.0					
44+73.00	LT.	24.0	720.04	720.04	49+73.00	LT.	24.0	731.16	731.16		VAR	F E P P	500.0	46.0		1.0	4.0	
<b>I-57 NORTHBOUND</b>																		
295+50.0	56' RT.	34.0	699.42	699.67	-1.56	300+00.00	RT.	24.0	700.44	700.69	-1.56	0.30	0.41		450.0	18.0	1.0	4.0
300+00.0	56' RT.	OUTLET EXISTING I-57 UNDERDRAIN																
309+58.0	56' RT.	OUTLET EXISTING I-57 UNDERDRAIN INTO INLET AT RAMP A STA. 25+00																
322+10.0	56' RT.	CONNECT EXISTING TO PROPOSED																
295+50.0	32' RT.	34.0	699.42	699.67	-1.56	300+00.00	LT.	24.0	700.44	700.69	-1.56	0.30	0.41		450.0	26.0	1.0	4.0
300+00.0	32' RT.	OUTLET EXISTING I-57 UNDERDRAIN																
<b>I-57 SOUTHBOUND</b>																		
295+50.0	56' LT.	35.0	699.54	699.79	-1.56	300+00.00	RT.	24.0	700.47	700.72	-1.56	0.21	0.41		450.0	18.0	1.0	4.0
300+00.0	56' LT.	OUTLET EXISTING I-57 UNDERDRAIN																
295+50.0	32' LT.	35.0	699.54	699.79	-1.56	300+00.00	LT.	24.0	700.47	700.72	-1.56	0.21	0.41		450.0	18.0	1.0	4.0
300+00.0	32' LT.	OUTLET EXISTING I-57 UNDERDRAIN																
318+25.0	56' LT.	OUTLET EXISTING I-57 UNDERDRAIN																
311+14.0	56' LT.	OUTLET EXISTING I-57 UNDERDRAIN																
<b>TOTALS</b>												<b>18,660.0</b>	<b>1,480.0</b>	<b>1,800.0</b>	<b>274.0</b>	<b>58.0</b>	<b>232.0</b>	
<b>UNIT</b>												<b>( FEET )</b>	<b>( FEET )</b>	<b>( FEET )</b>	<b>( FEET )</b>	<b>( EACH )</b>	<b>( SQ. YD. )</b>	
<b>PAY ITEM</b>												<b>60107600</b>	<b>60108100</b>	<b>60107700</b>	<b>60108200</b>	<b>60100060</b>	<b>25100630</b>	