

SUMMARY OF QUANTITIES

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
709	.	**	72	5

LOCATION OF WORK: FAP 709 (US 136)
SECTION 113(RS-5,BR)&114RS-2
CHAMPAIGN/VERMILION CO.
2 LANE RURAL

FAP 709 (US 136)
RURAL
STA. 423+35
TO
STA. 56+28
80% FED
20% STATE
1000

FAP 709 (US 136)
RURAL
STA. 56+28
TO
STA. 161+47.64
80% FED
20% STATE
1000

• 113(RS-5,BR) & 114RS-2
•• CHAMPAIGN AND VERMILION
CONTRACT NO. 90864

CONSTRUCTION TYPE CODE:

CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CHAMPAIGN CO.	VERMILION CO.
48100500	AGGREGATE SHOULDERS, TYPE A 6"	SO YD	441.0	441.0	0.0
48101200	AGGREGATE SHOULDERS, TYPE B	TON	3688.0	2676.0	1012.0
48202000	BITUMINOUS SHOULDERS SUPERPAVE	TON	188.0	0.0	188.0
50100300	REMOVAL OF EXISTING STRUCTURES NO. 1	EACH	1.0	1.0	0.0
50100400	REMOVAL OF EXISTING STRUCTURES NO. 2	EACH	1.0	1.0	0.0
51500100	NAME PLATES	EACH	1.0	1.0	0.0
54001000	BOX CULVERT END SECTIONS	EACH	2.0	2.0	0.0
54021204	PRECAST CONCRETE BOX CULVERT 12' X 4' (M273)	FOOT	56.0	56.0	0.0
54207162	PIPE CULVERTS, TYPE 1, REINFORCED CONCRETE - ELLIPTICAL, EQUIVALENT ROUND-SIZE 27"	FOOT	40.0	40.0	0.0
54214512	PRECAST REINFORCED CONCRETE FLARED END SECTIONS, EQUIVALENT ROUND-SIZE 27"	EACH	2.0	2.0	0.0
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	2.3	2.3	0.0
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	58.0	58.0	0.0
* 63000000	STEEL PLATE BEAM GUARD RAIL, TYPE A	FOOT	350.0	350.0	0.0
* 63000005	STEEL PLATE BEAM GUARD RAIL, TYPE B	FOOT	100.0	100.0	0.0
* 63000025	STEEL PLATE BEAM GUARD RAIL, ATTACHED TO STRUCTURES	FOOT	25.0	25.0	0.0
* 63100167	TRAFFIC BARRIER TERMINAL TYPE 1, SPECIAL (TANGENT)	EACH	11.0	11.0	0.0
63200310	GUARDRAIL REMOVAL	FOOT	800.0	800.0	0.0
66700110	PERMANENT SURVEY MARKERS TO BE ADJUSTED	EACH	7.0	4.0	3.0
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	5.0	3.0	2.0
67100100	MOBILIZATION	L SUM	1.0	0.7	0.3
70100450	TRAFFIC CONTROL AND PROTECTION, STANDARD 701201	L SUM	1.0	0.7	0.3
70100455	TRAFFIC CONTROL AND PROTECTION, STANDARD 701206	L SUM	1.0	1.0	0.0
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1.0	0.7	0.3
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	11234.0	7864.0	3370.0
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SO FT	1873.0	1311.0	562.0
* 78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SO FT	47.0	0.0	47.0
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	3020.0	0.0	3020.0
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	105.0	0.0	105.0
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	50.0	0.0	50.0
* 78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	87144.0	60477.0	26667.0
* 78001180	PAINT PAVEMENT MARKING - LINE 24"	FOOT	50.0	50.0	0.0
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	454.0	317.0	137.0
* 78201000	TERMINAL MARKER - DIRECT APPLIED	EACH	11.0	11.0	0.0

* SPECIALTY ITEM