

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
709	*	**	72	20

\* 113(RS-5,BR) & 114RS-2  
 \*\* CHAMPAIGN AND VERMILION  
 CONTRACT NO. 90864

## SCHEDULE OF QUANTITIES

### 44000025 BITUMINOUS SURFACE REMOVAL, SPECIAL

STATION	AREA SQ YD
<u>CHAMPAIGN COUNTY</u>	
LT 426+25.56	37.0
RT 475+67 (TR 2400 E)	44.0
RT 516+28 (TR 2500 E)	84.0
LT 516+28 (TR 2500 E)	85.0
LT 569+99 (TR 2600 E)	79.0
SUBTOTAL	329.0

### VERMILION COUNTY

LT 109+42 (TR 1700 E)	114.0
SUBTOTAL	114.0
<u>TOTAL QUANTITY</u>	<u>443.0</u>

### 44000500 COMBINATION CURB AND GUTTER REMOVAL

#### CHAMPAIGN COUNTY

STATION	TO	STATION	LIN. FT.
PENNFIELD RD	LT 803+35.89	LT 803+74.28	56.0
PENNFIELD RD	RT 804+25.51	RT 804+54.20	48.0
TOTAL			<u>104.0</u>

### 44002500 GUTTER OUTLET REMOVAL

#### CHAMPAIGN COUNTY

STATION	EACH	
PENNFIELD RD	LT 803+61.66	1.0
PENNFIELD RD	RT 804+41.06	1.0
TOTAL		<u>2.0</u>

### 48100500 AGGREGATE SHOULDERS, TYPE A 6"

#### CHAMPAIGN COUNTY

STATION	TO	STATION	SQ YD
LT 483+00		LT 483+94.18	47.1
RT 483+00		RT 483+94.18	47.1
LT 483+94.18		LT 485+94.18	133.4
RT 483+94.18		RT 485+94.18	133.4
LT 485+94.18		LT 486+74.18	40.0
RT 485+94.18		RT 486+74.18	40.0
TOTAL			<u>441.0</u>

### 60600095 CLASS SI CONCRETE OUTLET

#### CHAMPAIGN COUNTY

STATION	CU YD	
PENNFIELD RD	LT 803+34.89	0.56
PENNFIELD RD	LT 3+24.20	0.56
PENNFIELD RD	RT 2+07.77	0.56
PENNFIELD RD	RT 804+54.16	0.56

TOTAL	2.24
<u>USE</u>	<u>2.30</u>

### 60600500 COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24

#### CHAMPAIGN COUNTY

STATION	TO	STATION	LIN. FT.
PENNFIELD RD	LT 803+40.6	LT 803+55.19	16.3
PENNFIELD RD	LT 3+05.99	LT 3+19.52	16.7
PENNFIELD RD	RT 2+12.43	RT 2+29.95	21.0
PENNFIELD RD	RT 804+46.54	RT 804+49.55	3.5
TOTAL			57.5
<u>USE</u>			<u>58.0</u>

### 63000000 STEEL PLATE BEAM GUARDRAIL, TYPE A

#### CHAMPAIGN COUNTY

STATION	TO	STATION	FOOT
RT 483+18.19		RT 484+55.69	137.5
LT 484+32.66		LT 484+70.16	37.5
RT 485+18.19		RT 485+55.69	37.5
LT 485+32.66		LT 486+70.16	137.5
TOTAL			<u>350.0</u>

### 63000005 STEEL PLATE BEAM GUARDRAIL, TYPE B

#### CHAMPAIGN COUNTY

STATION	TO	STATION	FOOT
RT 484+55.69		RT 484+80.69	25.0
LT 484+70.16		LT 484+95.16	25.0
RT 485+18.19		RT 484+93.19	25.0
LT 485+32.66		LT 485+07.66	25.0
TOTAL			<u>100.0</u>

### 63000025 STEEL PLATE BEAM GUARDRAIL ATTACHED TO STRUCTURE

#### CHAMPAIGN COUNTY

STATION	TO	STATION	FOOT
RT 484+80.69		RT 484+93.19	12.5
LT 484+95.16		LT 485+07.66	12.5
TOTAL			<u>25.0</u>