

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7814	05-00186-01-PV	ADAMS	78	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

Y060

CODE NO.	ITEM	SP. PROV.	UNIT	TOTAL QUANTITIES	PARTICIPATING		NON-PART.		
					I000-2A	Y031-1F	100% CITY OF QUINCY WATER & SANITARY		
20100210	TREE REMOVAL (OVER 15 UNITS DIAMETER)		UNIT	139	139				
20200100	EARTH EXCAVATION	*	CU YD	9655	9655				
20800150	TRENCH BACKFILL	*	CU YD	1092	840		252		
21001000	GEOTECHNICAL FABRIC FOR GROUND STABILIZATION		SQ YD	3313	3313				
25000110	SEEDING, CLASS 1A		ACRE	3.2	3.2				
25000400	NITROGEN FERTILIZER NUTRIENT		POUND	284	284				
25000500	PHOSPHORUS FERTILIZER NUTRIENT		POUND	284	284				
25000600	POTASSIUM FERTILIZER NUTRIENT		POUND	284	284				
25100115	MULCH, METHOD 2		ACRE	3.2	3.2				
25100630	EROSION CONTROL BLANKET		SQ YD	66	66				
28000200	EARTH EXCAVATION FOR EROSION CONTROL		CU YD	45	45				
28000250	TEMPORARY EROSION CONTROL SEEDING		POUND	316	316				
28000300	TEMPORARY DITCH CHECKS		EACH	18	18				
28000400	PERIMETER EROSION BARRIER		FOOT	2138	2138				
28000500	INLET AND PIPE PROTECTION		EACH	5	5				
28100807	STONE DUMPED RIPRAP, CLASS A4		TON	189	189				
28200200	FILTER FABRIC		SQ YD	275	275				
31100100	SUB-BASE GRANULAR MATERIAL, TYPE A		TON	3538	3538				
35100100	AGGREGATE BASE COURSE, TYPE A		TON	8051	8051				
35650510	BASE COURSE WIDENING 11"		SQ YD	18	18				
40200100	AGGREGATE SURFACE COURSE, TYPE A		TON	40	40				
40600200	BITUMINOUS MATERIALS (PRIME COAT)		TON	17.1	17.1				
40600300	AGGREGATE (PRIME COAT)		TON	3.7	3.7				
40600895	CONSTRUCTING TEST STRIP		EACH	2	2				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT		SQ YD	54	54				
40600990	TEMPORARY RAMP		SQ YD	49	49				
42300200	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 6 INCH		SQ YD	152	152				
42300400	PORTLAND CEMENT CONCRETE DRIVEWAY PAVEMENT, 8 INCH		SQ YD	130	130				
42400100	PORTLAND CEMENT CONCRETE SIDEWALK 4 INCH		SQ FT	9763	9763				
42400800	DETECTABLE WARNINGS		SQ FT	174	174				
44000006	BITUMINOUS SURFACE REMOVAL 1 1/2"		SQ YD	1856	1856				
44000100	PAVEMENT REMOVAL	*	SQ YD	3896	3896				
44000200	DRIVEWAY PAVEMENT REMOVAL	*	SQ YD	82	82				
44000500	COMBINATION CURB AND GUTTER REMOVAL	*	FOOT	28	28				
44000600	SIDEWALK REMOVAL	*	SQ FT	25	25				
44004000	PAVED DITCH REMOVAL		FOOT	104	104				
44100100	PAVEMENT REPLACEMENT	*	SQ YD	3.3			3.3		
48101200	AGGREGATE SHOULDERS, TYPE B		TON	45	45				
50105220	PIPE CULVERT REMOVAL		FOOT	325	325				
50300225	CONCRETE STRUCTURES		CU YD	24.0	24.0				
50800105	REINFORCEMENT BARS		POUND	1820	1820				
50900805	PEDESTRIAN RAILING	*	FOOT	86	86				
54201297	PIPE CULVERTS, TYPE 2 RCCP 42"		FOOT	130	130				
54213657	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 12"		EACH	2	2				
54213663	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 18"		EACH	1	1				
54213669	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 24"		EACH	2	2				
54213675	PRECAST REINFORCED CONCRETE FLARED END SECTIONS 30"		EACH	1	1				
54216930	REINFORCED CONCRETE PIPE TEE, 18" PIPE WITH 18" RISER		EACH	1	1				
54217711	REINFORCED CONCRETE PIPE TEE, 42" PIPE WITH 24" RISER		EACH	1	1				
54248500	CONCRETE HEADWALLS	*	CU YD	8.8	8.8				
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"		FOOT	126	126				
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"		FOOT	558	558				
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"		FOOT	241	241				

REVISIONS	
NAME	DATE
TITLE BLOCK - SEB	9/26/05
PAY ITEM - SEB	9/26/05
PAY ITEM - SEB	1/10/06
ROW COM - SEB	3/6/06

SUMMARY OF QUANTITIES
 SHEET 1 OF 4
 FAU 7814 (HARRISON STREET)
 SECTION 05-00186-01-PV
 ADAMS COUNTY

SCALE: NONE
 DATE: 9/12/05

DRAWN BY: SEB
 CHECKED BY: SRW

3/6/2006 P:\0711\05\0834\Contract\03_04\034_01.dwg