

**PAVEMENT REMOVAL**

ROADWAY	STATION TO STATION		AREA (SQ YD)
EX HARRISON	100+14.4	101+50.0	435.9
	101+50.0	107+50.0	1385.8
	107+50.0	112+00.0	1004
	112+00.0	115+60.0	1056.7
IL 96	2262+73.5	2263+10.0	6.2
	2264+72.0	2265+15.0	7.1
<b>TOTALS:</b>			<b>3,896</b>

**DRIVEWAY PAVEMENT REMOVAL**

ROADWAY	STATION	OFFSET	AREA (SQ YD)
EX HARRISON	106+38	RT	82.4
<b>TOTALS:</b>			<b>82</b>

**COMBINATION CURB AND GUTTER REMOVAL**

LOCATION	LENGTH (FT)
SW QUADRANT - 36TH & HARRISON	12.0
NW QUADRANT - 36TH & HARRISON	16.3
<b>TOTALS:</b>	<b>28</b>

**PAVED DITCH REMOVAL**

ROADWAY	STATION TO STATION		LENGTH (FOOT)
EX HARRISON	106+85.0	107+89.0	104.0
<b>TOTALS:</b>			<b>104</b>

**PIPE CULVERT REMOVAL**

ROADWAY	STATION	OFFSET	DESCRIPTION	LENGTH (FOOT)
EX HARRISON	106+38	RT	24" CMP	26.5
	106+92	C	58" x 38" CMP	36.2
	108+51	RT	10" CMP	19.8
	113+34	LT	12" CMP	44.0
	114+84	LT	18" CMP	90.0
IL 96	2257+87	RT	18" CMP	60.4
	2263+65	RT	18" CMP	48.2
<b>TOTALS:</b>				<b>325</b>

**BITUMINOUS SURFACE REMOVAL SCHEDULE**

ROADWAY	STATION TO STATION		BITUMINOUS SURFACE REMOVAL - BUTT JOINT (SQ YD)	BITUMINOUS SURFACE REMOVAL 1/2" (SQ YD)	TEMPORARY RAMP (SQ YD)
HARRISON	115+60	115+85	54.2		
	2262+47	2263+74		543.3	25.7
	2263+74	2266+85		1312.9	23.7
<b>TOTALS:</b>			<b>54</b>	<b>1,856</b>	<b>49</b>

**PAVEMENT MARKING SCHEDULE**

LOCATION	THERMOPLASTIC PAVEMENT MARKING										PAINT		RAISED REFLECTIVE PAVEMENT MARKER		
	LETTERS & SYMBOLS	LINE 5"			LINE 6"		LINE 8"	LINE 12"		LINE 24"	LINE 4"	CHRYSTAL	AMBER		
		WHITE (SQ FT)	SOLID WHITE (FT)	SOLID YELLOW (FT)	SOLID WHITE (FT)	SKIP DASH WHITE (FT)	SKIP DASH WHITE (FT)	SOLID WHITE (FT)	SOLID YELLOW (FT)	SOLID WHITE (FT)	SKIP DASH YELLOW (FT)	SINGLE (EACH)	SINGLE (EACH)	DOUBLE (EACH)	
IL 96 & HARRISON	WEST LEG	63.5		134.0	176.7										
	SOUTH LEG	23.0	77.9	151.6	225.9				33.4		2		4		
	EAST LEG	23.0		657.0	275.9		208.1	95.0		40.6					
	NORTH LEG	23.0	268.0	762.0	479.9	10.0			22.0	24.0		10	8	6	
HARRISON STA 203+79.5 TO STA 115+60.0											340.0				
IL 96 STA 2257+30.0 TO STA 2258+60.0 RT			130.0												
<b>SUBTOTALS:</b>		132.5	475.9	1704.6	1158.4	10.0	208.1	95.0	22.0	98.0	340.0	12	8	10	
<b>TOTALS:</b>		<b>133</b>	<b>2,181</b>		<b>1,168</b>	<b>208</b>		<b>117</b>	<b>98</b>	<b>340</b>		<b>30</b>			

**WATER MAIN SCHEDULE**

PLAN LABEL	LOCATION			TRENCH BACKFILL (CU YD)	WATER MAIN 8" (FT)	CASING PIPE 16" (FT)	VALVE BOXES TO BE ADJUSTED (EACH)	FIRE HYDRANTS (SPECIAL) (EACH)	TAPPING VALVES AND SLEEVES 8" (EACH)	WATER MAIN FITTINGS 8"			PAVEMENT REPLACEMENT (SQ YD)
	ROADWAY	STATION	OFFSET							22.5° ELBOW (EACH)	45° ELBOW (EACH)	CAP AND BLOWOFF (EACH)	
W1	IL 96	2264+20.0	21.0' RT						1				3.3
W2				21.0	50	20							
W3	IL 96	2264+44.0	71.0' RT								1		
W4					16								
W5	HARRISON	200+82.0	35.0' LT										
W6					10								
W7	HARRISON	200+92.0	LT	6.0									
W8					10			1					
W9	HARRISON	201+02.0	35.0' LT								1		
W10	EX HARRISON	109+24.0	16.9' LT						1				
W11					20								
W12	EX HARRISON	109+24.0	36.9' LT							1			
W13				39.5	110								
W14	38TH STREET	50+36.6	26.2' RT	6.0									
W15					20								
W16	38TH STREET	50+56.5	22.0' RT								1		
W17	EX HARRISON	103+00.0	18.3' LT										
W18					10				1				
W19	EX HARRISON	103+00.0	28.3' LT								1		
	IL 96	2258+14.7	21.2' RT				1						
	IL 96	2263+96.9	21.0' RT				1						
	IL 96	2264+02.2	14.1' RT				1						
	HARRISON	213+55.7	C				1						
<b>TOTALS:</b>				<b>73</b>	<b>246</b>	<b>20</b>	<b>4</b>	<b>2</b>	<b>3</b>	<b>1</b>	<b>2</b>	<b>3</b>	<b>3.3</b>

**SANITARY SEWER SCHEDULE**

ROADWAY	STATION	OFFSET	TRENCH BACKFILL (CU YD)	MH SAN. 4" DIA. TY 1 FR CLSD LID (EACH)	SANITARY SEWER TYPE 3 8" (FOOT)	SANITARY SEWER TYPE 3 10" (FOOT)
HARRISON	200+65.0	35.0' LT		1		
			105.1		80.0	
EX HARRISON	200+70.0	45.0' RT		1		
	48+00.0	19.0' RT		1		70.0
	48+00.0	55.0' LT	73.9			
<b>TOTALS:</b>			<b>179</b>	<b>4</b>	<b>80</b>	<b>70</b>

**TURF REINFORCEMENT MAT**

LOCATION	SIZE	AREA (SQ YD)
38TH STREET STA 48+40 RT	25' X 18'	50.0
38TH STREET STA 48+65 RT to HARRISON STA 212+65 RT	230' X 12'	306.7
<b>TOTALS:</b>		<b>357</b>

**PERIMETER EROSION BARRIER**

LOCATION	LENGTH (FT)
IL 96 2263+00 RT to HARRISON 202+00 RT	164
IL 96 2264+65 RT to HARRISON 203+61 LT	373
HARRISON 203+90 LT to 206+75 LT	319
HARRISON 208+61 RT to 38TH ST. 48+66 LT	282
HARRISON 213+00 RT to 116+15 RT	520
EX HARRISON 101+26 LT to 105+83 LT	480
<b>TOTALS:</b>	<b>2,138</b>

**EROSION CONTROL BLANKET**

ROADWAY	STATION	OFFSET	AREA (SQ YD)
HARRISON	201+12	32' LT	5.3
	212+65	57' RT	9.4
	2262+75	42' RT	8.3
IL 96	2265+00	38' RT	8.3
	38TH STREET / EX HARRISON	101+24	C
EX HARRISON	106+10	26' LT	8.3
	48+40	32' RT	10.7
	48+40	36' RT	10.7
<b>TOTALS:</b>			<b>66</b>

**INLET AND PIPE PROTECTION**

ROADWAY	STATION	OFFSET	NUMBER (EACH)
HARRISON	201+12	32' LT	1
	115+68	25' LT	1
	115+79	27' RT	1
IL 96	2265+00	38' RT	1
EX HARRISON	105+06	21' RT	1
<b>TOTALS:</b>			<b>5</b>

**TREE REMOVAL SCHEDULE**

ROADWAY	STATION	OFFSET	SIZE (UNIT)
HARRISON	113+89	19' RT	36
	48+05	42' RT	42
	48+25	37' RT	24
	48+26	38' RT	17
	48+31	41' RT	20
<b>TOTALS:</b>			<b>139</b>

**TEMPORARY DITCH CHECKS**

ROADWAY	STATION TO STATION	OFFSET	NUMBER (EACH)	
HARRISON	211+26	212+65	RT	7
	2257+30	2258+60	RT	3
	2261+75	2266+85	RT	3
38TH STREET / EX HARRISON	100+30	101+20	C	2
	106+50	48+90	RT	3
<b>TOTALS:</b>			<b>18</b>	

**EARTH EXCAVATION FOR EROSION CONTROL**

ROADWAY	STATION	OFFSET	VOLUME (CU YD)
EX HARRISON	105+90	40' LT	45
<b>TOTALS:</b>			<b>45</b>

**SIDEWALK REMOVAL**

ROADWAY	STATION TO STATION	AREA (SQ FT)	
EX HARRISON RT	96+90.5	96+97.4	25.0
<b>TOTALS:</b>		<b>25</b>	

REVISIONS	
NAME	DATE
TITLE BLOCK - SEB	9/26/05
PAY ITEM - SEB	9/26/05
PAY ITEM - SEB	1/10/06
ROW COMM. - SEB	3/6/06

SCHEDULE OF QUANTITIES  
SHEET 2 OF 3  
FAU 7814 (HARRISON STREET)  
SECTION 05-00186-01-PV  
ADAMS COUNTY

SCALE: NONE DRAWN BY SEB  
DATE 9/12/05 CHECKED BY SRW

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7814	05-00186-01-PV	ADAMS	78	12

STA. TO STA.  
FED. ROAD DIST. NO. ILLINOIS FED. AID PROJECT

3/6/2006