F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7814	05-00186-01-PV	ADAMS	78	13
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

STORM SEWER SCHEDULE

PLAN LABEL	LOCATION ROADWAY	LOCATION STATION	LOCATION OFFSET	TRENCH BACKFILL (CU YD)	STORM SEWERS CLASS A TYPE 1 12" (FT)	CLASS A TYPE 1 24" (FT)	CLASS A TYPE 2 12" (FT)	CLASS A TYPE 2 18" (FT)	CLASS A TYPE 2 24" (FT)	CLASS A TYPE 2 30" (FT)	CLASS B TYPE 2 12" (FT)	WATER MAIN REQ. TYPE 1 D.I. 12" (FT)	WATER MAIN REQ. TYPE 2 18" (FT)	INLETS TYPE A TYPE 11 FR & GR (EACH)	INLETS TYPE B TYPE 11 FR & GR (EACH)	INLETS SPECIAL (EACH)	INLETS SPECIAL, TYPE E (EACH)	GRATES, SPECIAL (EACH)	PRECAST REINFORCED CONCRETE END SECTIONS 12" (EACH)	PRECAST REINFORCED CONCRETE END SECTIONS 18" (EACH)	PRECAST REINFORCED CONCRETE END SECTIONS 24" (EACH)	PRECAST REINFORCED CONCRETE END SECTIONS 30" (EACH)	PIPE CULV RCCP TYPE 2 42" (FT)	REINFORCED CONCRETE PIPE TEE 18" PIPE 18" RISER (EACH)	REINFORCED CONCRETE PIPE TEE 42" PIPE 24" RISER (EACH)	CONCRETE HEADWALLS (CU YD)	REINF. BARS (POUND)
1	IL 96	2262+75.0	41.6' RT																		1						
A				4.5		56																					
2	IL 96	2263+33.2	49.0' RT														1										
B				14.9		92																					
3	IL 96	2264+27.6	34.7' RT														1										
C				1.8		70																					
4	IL 96	2265+00.0	38.2' RT																		1						
D				12.5		61																					
5	HARRISON	201+12.0	25.2' RT														1										
E				9.6		203																					
6	HARRISON	203+25.0	22.6' RT														1										
F				26.0		76																					
7	37TH STREEET	10+47.0	15.2' LT														1										
G				4.8			32																				
8	37TH STREEET	10+47.0	15.2' RT														1										
D1				8.3	61																						
5A	HARRISON	201+12.0	22.6' LT														1										
D2				0.8	5																						
5B	HARRISON	201+12.0	32.1' LT																1								
9	HARRISON	208+40.0	22.6' LT														1										
H				107.9			131																				
10	HARRISON	209+80.0	22.6' LT														1										
I				76.4				78																			
11	38TH STREET	50+40.8	17.4' LT														1										
J				10.3			35																				
12	38TH STREET	50+45.0	16.0' RT														1										
K				167.2					157																		
13	38TH STREET	48+73.8	15.1' LT														1										
L				24.9					23																		
14	38TH STREET	48+40.0	℄	86.9																			66, 64		1	8.8	540
15	38TH STREET	48+37.4	15.1' RT														1										
16	EX HARRISON	105+06.0	14.5' LT											1													
M				5.8	30																						
17	EX HARRISON	105+06.0	15.1' RT														1										
N				34.2				100																			
18	EX HARRISON	106+10.0	15.1' RT														1										
O				11.9				31																			
19	EX HARRISON	106+10.0	15.1' LT														1										
P								7																			
20	EX HARRISON	106+10.0	26.9' LT																	1							
21	HARRISON	212+65.0	57.3' RT																			1					
Q				122.3						274																	
22	HARRISON	113+40.0	22.6' RT													1											
R				4.6								46															
23	HARRISON	113+40.0	22.6' LT														1										
S										201																	
24	HARRISON	115+45.0	22.6' RT													1											
T				55.8									46														
25	HARRISON	115+45.0	22.6' LT														1										
U				7.9				36																			
26	39TH STREET	10+37.0	23.5' RT												1												
V				34.0			43																				
27	39TH STREET	10+53.0	19.5' LT											1													
W								32																			
28	HARRISON	115+82.0	27.3' RT					3										1						1			
X				6.4							20																
29	EX HARRISON	101+55.9	℄											1													
Y				0.4	30																						
30	EX HARRISON	101+24.5	℄																1								
TOTALS:				840*	126	558	241	287	180	475	20	46	46	3	1	2	18	1	2	1	2	1	130	1	1	8.8	540**

* - SEE WATER MAIN AND SANITARY SEWER SCHEDULES FOR ADDITIONAL QUANTITIES

** - SEE RETAINING WALL BILL OF MATERIAL FOR ADDITIONAL QUANTITY (SHEET 41)

REVISIONS	
NAME	DATE
TITLE BLOCK - SEB	9/26/05
DRAINAGE SCH - SEB	1/10/06
ROW COMM. - SEB	3/6/06

SCHEDULE OF QUANTITIES
SHEET 3 OF 3
FAU 7814 (HARRISON STREET)
SECTION 05-00186-01-PV
ADAMS COUNTY

SCALE: NONE DRAWN BY SEB
DATE 9/12/05 CHECKED BY SRW

3/6/2006

P:\Proj\Jos\B48394\Contracts\11 B48394a_SCH001.dgn