F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
7814	05-00186-01-PV	ADAMS	78	73
STA. _____	TO STA. _____			
FED. ROAD DIST. NO. _	ILLINOIS	FED. AID PROJECT		

FINAL SURVEY	SURVEYED	DATE
NOTE BOOK	PLOTTED	
NO.	TEMP. ATE	8Y
	AREAS	
	AREAS CHECKED	

ORIGINAL SURVEY	SURVEYED	DATE
NOTE BOOK	PLOTTED	
NO.	TEMPLATE	8Y
	AREAS	
	AREAS CHECKED	

3/6/2006

P:\3Files\W40394\Contracts\63-#40394A.XSR007.dgn

REV 12/10/06

106+50

TCE | PR ROW | EX ROW | 1:2 | 1:2 | SD FL=658.50 | 664.73 | 2.0% | 665.00 | 2.0% | 664.73 | 1:4 | 1:4 | SD FL=663.50 | EX ROW | PR ROW | TCE

CUT = 13.6 SQ FT
FILL = 72.4 SQ FT

0.4"GAS | 12"W

106+38

TCE | PR ROW | EX ROW | 1:2 | 1:2 | SD FL=658.36 | 664.52 | 2.0% | 664.78 | 2.0% | 664.52 | STA 106+38.0 CONC PE | 33.2' | +1.8% | EX ROW | PR ROW | TCE

CUT = 13.4 SQ FT
FILL = 80.3 SQ FT

0.4"GAS | 12"W

106+00

TCE | PR ROW | EX ROW | 1:2 | 1:2 | SD FL=657.90 | 664.09 | 2.0% | 664.35 | 2.0% | 664.09 | +2.0% | EX ROW | PR ROW | TCE

18" Ø SS
FL = 659.46

CUT = 16.0 SQ FT
FILL = 66.1 SQ FT

12"W | 0.4"GAS

105+75

PR ROW | EX ROW | 1:3 | 664.00 | 2.0% | 664.26 | 2.0% | 664.00 | +2.0% | EX ROW | PR ROW

18" Ø SS
FL = 659.65

CUT = 10.4 SQ FT
FILL = 56.4 SQ FT

0.4"GAS | 12"W

665 / 660 | 80 75 70 65 60 55 50 45 40 35 30 25 20 15 10 5 0 5 10 15 20 25 30 35 40 45 50 55 60 65 70 75 80

EX HARRISON / 38TH STREET STA 105+75 TO STA 106+50