

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
853	(7,8)RS-3	HAMILTON	16	3
STA.		TO STA.		
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE		
CODE NO	ITEM	UNIT		1000 80% FED./ 20% STATE		
40200800	AGGREGATE SURFACE COURSE, TYPE B	TON	218	218		
40600100	BITUMINOUS MATERIALS (PRIME COAT)	GALLON	10624	10624		
40600300	AGGREGATE (PRIME COAT)	TON	213	213		
40600895	CONSTRUCTING TEST STRIP	EACH	1	1		
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	696	696		
40600990	TEMPORARY RAMP	SQ YD	143	143		
44000030	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SQ YD	106234	106234		
48101200	AGGREGATE SHOULDERS, TYPE B	TON	2012	2012		
67000500	ENGINEER'S FIELD OFFICE, TYPE B	CAL MO	3	3		
67100100	MOBILIZATION	L SUM	1	1		
70100460	TRAFFIC CONTROL AND PROTECTION, STANDARD 701306	L SUM	1	1		
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	7355	7355		
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	99308	99308		
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	1214	1214		
78001110	PAINT PAVEMENT MARKING - LINE 4"	FOOT	99308	99308		
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	460	460		
X4066418	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N90	TON	8924	8924		
XX005223	INCIDENTAL BITUMINOUS SURFACING, SUPERPAVE, N90	TON	95	95		

* * *

* SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE: VERT. HORIZ. DATE

DRAWN BY CHECKED BY

PLT DATE = 01/27/2008
 FILE NAME = c:\pcc\pcc\748733\02185p.dgn
 PLT SCALE = 1/8"=1'-0"
 USER NAME = hcasteryj