

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
853	(7,8)RS-3	HAMILTON	16	6
STA.	TO STA.			
FED. ROAD DIST. NO.	ILLINOIS FED. AID PROJECT			

PAVING SCHEDULE

STATION TO STATION	LENGTH	EXISTING PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "C", N90	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LINE 4"	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING - LINE 4"	RAISED REFLECTIVE PAVEMENT MARKER	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP
	LIN FT	FEET	SQ YD	GALLON	TON	TON	SQ YD	SQ YD	LIN FT	LIN FT	SQ FT	LIN FT	EACH	TON	SQ YD
STA. 301+50.00 TO 313+68.60	1218.6	26	3520.4	352	7.1	296	87	3521	244	4823	40	4823	15	68	14
STA. EQ. 313+68.60BK=313+70.40AH															
STA. 313+70.40 TO 327+82.40	1412	26	4079.1	408	8.2	343		4079	282	3914	47	3914	17	80	
STA. EQ. 327+82.40BK=327+84.30AH															
STA. 327+84.30 TO 333+40.00	555.7	26	1605.4	160	3.3	135	174	1606	111	2059	18	2059	7	32	19
STA. 333+40.00 TO 334+14.00	BRIDGE OMISSION														
STA. 334+14.00 TO 361+94.70	2780.7	26	8033.1	803	16.1	675		8033	556	7735	92	7735	35	148	19
STA. EQ. 361+94.70BK=361+95.30AH															
STA. 361+95.30 TO 379+62.50	1767.2	26	5105.2	511	10.3	429		5105	353	3976	58	3976	22	101	
STA. EQ. 379+62.50BK=379+63.20AH															
STA. 379+63.20 TO 399+35.00	1971.8	26	5696.3	570	11.4	478	174	5696	395	6071	65	6071	25	108	19
STA. 399+35.00 TO 400+11.00	BRIDGE OMISSION														
STA. 400+11.00 TO 408+24.80	813.8	26	2351.0	235	4.8	197		2351	163	2442	27	2442	10	44	19
STA. EQ. 408+24.80BK=408+25.20AH															
STA. 408+25.20 TO 578+85.40	17060.2	26	49285.0	4929	98.6	4140	261	49285	3412	44090	563	44090	214	946	
STA. EQ. 578+85.40BK=748+80.00AH															
STA. 748+80.00 TO 700+92.00	4788	26	13832.0	1383	27.7	1162		13832	958	10527	158	10527	60	253	20
STA. 700+92.00 TO 699+28.00	BRIDGE OMISSION														
STA. 699+28.00 TO 655+23.00	4405	26	12725.6	1273	25.5	1069		12726	881	13671	146	13671	55	232	33
TOTAL	37087			10624	213	8924	696	106234	7355	99308	1214	99308	460	2012	143

PLOT DATE = 9/27/2006
 FILE NAME = c:\pav\pav1\748955a\82105pav.dwg
 PLOT SCALE = 1/8"=1'-0" / IN.
 USER NAME = hesterj

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

PAVING SCHEDULE

SCALE: VERT. _____
 HORIZ. _____

DATE _____ DRAWN BY _____
 CHECKED BY _____