

F.A.P. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
853	9RS-4	HAMILTON	12	6
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		

PAVING SCHEDULE

STATION TO STATION	LENGTH	EXISTING PAVEMENT WIDTH	AREA	BITUMINOUS MATERIALS (PRIME COAT)	AGGREGATE (PRIME COAT)	LEVEL BINDER (MACHINE METHOD), SUPERPAVE N90	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE MIXTURE "C", N90	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	BITUMINOUS SURFACE REMOVAL (VARIABLE DEPTH)	BITUMINOUS SURFACE REMOVAL 2 1/4"	SHORT-TERM PAVEMENT MARKING	TEMPORARY PAVEMENT MARKING - LINE 4"	TEMPORARY PAVEMENT MARKING - LINE 24"	WORK ZONE PAVEMENT MARKING REMOVAL	PAINT PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	RAISED REFLECTIVE PAVEMENT MARKER	AGGREGATE SHOULDERS, TYPE B	TEMPORARY RAMP
STA 163+38 TO 164+20	82	30.5	277.9	28	0.6	12	23			278	25	20	16	3		20	16	1		47
STA 164+20 TO 166+98	278	27	834	83	1.7	35	70			834	83	70		9		70		4		
STA 166+98 TO 168+81	183	20.4	414.8	41	0.8	18	35			415	55	46		6		46		2		
STA 168+81 TO 169+71	90	18.8	188	19	0.4	16	16			188	27	23		3		23		1		
STA 169+71 TO 171+46	175	23.8	462.8	46	0.9	20	39			463	52	394		6		394		2		
STA 171+46 TO 171+75	29	23	74.1	7	0.2	3	6			74	9	65		1		65		0		
STA 171+75 TO 176+94	519	22	1268.7	127	2.5	53	107			1269	156	1168	24	17		1168	24	7		
STA 176+94 TO 180+15	321	30	1070	107	2.1	45	90			1070	96	722		11		722		4		
STA 180+15 TO 183+56	341	23.5	890.4	89	1.8	37	75			890	102	426		11		426		4		
STA 183+56 TO 184+01	45	25	125	13	0.3	5	10		125	13	101		2			101		1	1	
STA 184+01 TO 188+99.90	498.9	25	1385.8	139	2.8	58	116		1386	150	1079		17	486	593			6	20	
STA EQN 188+99.9BK = 189+00.1AH																				
STA 189+00.1 TO 196+50	749.9	25	2083.1	208	4.2	88	175		2053	30	225	1625		25	1625			9	33	
STA 196+50 TO 206+06.7	956.7	25	2657.5	266	5.3	112	223		2627	31	287	2152		32	2152			12	39	
STA EQN 206+06.7BK = 206+02.3AH																				
STA 206+02.3 TO 222+94.1	1691.8	25	4699.4	470	9.4	197	395		4699		508	5768		56	5768			21	57	
STA EQN 222+94.1BK = 223+80.9AH																				
STA 223+80.9 TO 256+11.2	3230.3	25	8973.1	897	18.0	377	754		8973		969	9876		108	9876			41	176	
STA EQN 256+11.2BK = 256+52.8AH																				
STA 256+52.8 TO 301+05	4452.2	25	12367	1237	24.7	519	1039		12367		1336	13376		148	13376			56	265	
STA 301+05 TO 301+50	45	25	125	13	0.3	5	11	125			14	180		2	180			1	3	35
TOTAL	13687.8			3790	76	1584	3184	125	32230	5542	4107	37091	40	457	33463	3628	40	172	594	82

REVISIONS		ILLINOIS DEPARTMENT OF TRANSPORTATION	
NAME	DATE	<h1>SCHEDULES</h1>	
SCALE:	VERT. DATE	HORIZ.	DRAWN BY
			CHECKED BY