


IMAGE FILES:

REVISIONS

NUMBER	BY	DATE



INDEX TO SHEETS

SHT. NO.	DESCRIPTION
1	COVER SHEET
2	INDEX TO SHEETS/SUMMARY OF QUANTITIES
3	SITE PLAN
4	CONSTRUCTION PHASING PLAN
5	EXISTING CONDITIONS
6	PROPOSED IMPROVEMENTS
7	APRON STAKING PLAN
8	TYPICAL SECTIONS
9	HAUL ROAD
10	DRAINAGE DETAILS
11	PAVEMENT MARKING
12	MISCELLANEOUS DETAILS
13	FENCING DETAILS 1
14	FENCING DETAILS 2
15	APRON CROSS SECTIONS 1 STA. 330+76.60 TO STA. 332+00
16	APRON CROSS SECTIONS 2 STA. 332+50 TO STA. 333+44.80

SUMMARY OF QUANTITIES

ITEM NO.	ITEM DESCRIPTION	UNIT	TOTAL QUANTITY	AS-BUILT QUANTITY
AR150510	ENGINEER'S FIELD OFFICE	L.S.	1	
AR150540	HAUL ROUTE	L.S.	1	
AR152410	UNCLASSIFIED EXCAVATION	C.Y.	300	
AR156510	SILT FENCE	L.F.	500	
AR156511	DITCH CHECK	EACH	4	
AR156540	RIPRAP	S.Y.	160	
AR161510	CLASS C FENCE	L.F.	450	
AR162504	CLASS E FENCE - 4'	L.F.	260	
AR201661	CLEAN & SEAL BITUMINOUS CRACKS	L.F.	2000	
AR201663	SAND MIX CRACK REPAIR	L.F.	1000	
AR201670	CRACK CONTROL FABRIC	S.Y.	11900	
AR401610	BITUMINOUS SURFACE COURSE	TON	1440	
AR401650	BITUMINOUS PAVEMENT MILLING	S.Y.	11900	
AR401665	BITUMINOUS PAVEMENT SAWING	L.F.	895	
AR603510	BITUMINOUS TACK COAT	GAL.	2500	
AR620520	PAVEMENT MARKING - WATERBORNE	S.F.	1000	
AR701512	12" RCP, CLASS IV	L.F.	48	
AR701536	36" RCP, CLASS IV	L.F.	24	
AR701900	REMOVE PIPE	L.F.	60	
AR752412	PRECAST REINFORCED CONC. FES 12"	EACH	4	
AR752436	PRECAST REINFORCED CONC. FES 36"	EACH	2	
AR752903	REMOVE HEADWALL	EACH	2	
AR901510	SEEDING	ACRE	0.2	
AR908510	MULCHING	ACRE	0.2	

CENTRALIA MUNICIPAL AIRPORT
 CENTRALIA, ILLINOIS
 REHABILITATE SOUTHWEST PORTION OF GA APRON
 INDEX TO SHEETS/
 SUMMARY OF QUANTITIES



DESIGN BY:	JEF
DRAWN BY:	CMT
CHECKED BY:	JEF
APPROVED BY:	JEF
DATE:	04/21/2006
JOB No:	05072-05
IL PROJ. NO. ENL-3556	
AIP PROJ. NO. 3-17-0015-B9	
SHEET 2 OF 16 SHEET	