


CODE NO.	ITEM	UNIT	TOTAL QUANTITY	CONSTR. CODE
				80% FEDERAL 20% STATE
				BOX CULVERT 0004 S.N. 049-0613
50200450	REMOVAL AND DISPOSAL OF UNSUITABLE MATERIAL FOR STRUCTURES	CU YD	20	20
50800205	REINFORCEMENT BARS, EPOXY COATED	POUND	12864	12864
51500100	NAME PLATES	EACH	1	1
54003000	CONCRETE BOX CULVERTS	CU YD	65	65
550A0160	STORM SEWERS, CLASS A, TYPE 1 36"	FOOT	8	8
550A4700	STORM SEWERS, CLASS A, TYPE 1 EQUIVALENT ROUND-SIZE 42"	FOOT	16	16
59100100	GEOCOMPOSITE WALL DRAIN	SO YD	13	13
60600095	CLASS SI CONCRETE (OUTLET)	CU YD	3	3
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	100	100
* 63000350	LONG-SPAN GUARDRAIL OVER CULVERT, 12 FT 6 IN SPAN	FOOT	37.5	37.5
* 63100045	TRAFFIC BARRIER TERMINAL, TYPE 2	EACH	1	1
* 63100167	TRAFFIC BARRIER TERMINAL, TYPE 1 (SPECIAL) TANGENT	EACH	1	1
* 66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	233	233
* 66900450	SPECIAL WASTE PLANS AND REPORTS	LSUM	1	1
* 66900530	SOIL DISPOSAL ANALYSIS	EACH	1	1

URBAN

TOTAL QUANTITY

BOX CULVERT
0004
S.N. 049-0613

* SPECIALTY ITEMS



USER NAME - unshanned	DESIGNED - AWM	REVISED -
DRAWN - TOM	REVISOR -	
CHECKED - JA	REVISOR -	
DATE - 04/03/2017	REVISOR -	

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

SUMMARY OF QUANTITIES

SCALE SHEET OF SHEETS STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
58E 172	2015-0048	LAKE	31	6
				CONTRACT NO. 62A58

ILLINOIS FED. AID PROJECT

REV 6-7-17

P:\62616605-03-PT177-004-W03-Hilwaukee_Culvert\CAD\DWG\Sheet6_62A58-int-500.dwg