URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80/20 (FED/STATE) ROADWAY 005
CODE NO	ITEM	UNIT		
~~20200100~~	~~EARTH EXCAVATION~~	~~CU YD~~	~~75~~	~~75~~
21101615	TOPSOIL FURNISH AND PLACE, 4"	SQ YD	80	80
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	2	2
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	2	2
25200110	SODDING, SALT TOLERANT	SQ YD	80	80
25200200	SUPPLEMENTAL WATERING	UNIT	0.8	0.8
40300200	BITUMINOUS MATERIALS (PRIME COAT)	TON	17	17
40600290	BITUMINOUS MATERIALS (TACK COAT)	POUND	28148	28148
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	63	63
40600827	POLYMERIZED LEVELING BINDER (MACHINE METHOD), IL-4.75, N50	TON	2295	2295
40600982	HOT-MIX ASPHALT SURFACE REMOVAL - BUTT JOINT	SQ YD	191	191
40601005	HOT-MIX ASPHALT REPLACEMENT OVER PATCHES	TON	218	218
40603565	POLYMERIZED HOT-MIX ASPHALT SURFACE COURSE, MIX "E", N70	TON	4671	4671

URBAN

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE 80/20 (FED/STATE) ROADWAY 005
CODE NO	ITEM	UNIT		
42001300	PROTECTIVE COAT	SQ YD	2035	2035
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	200	200
42400800	DETECTABLE WARNINGS	SQ FT	75	75
44000161	HOT-MIX ASPHALT SURFACE REMOVAL, 3"	SQ YD	41700	41700
44000600	SIDEWALK REMOVAL	SQ FT	200	200
44002212	HOT-MIX ASPHALT REMOVAL OVER PATCHES, 3"	SQ YD	1512	1512
44201753	CLASS D PATCHES, TYPE II, 9 INCH	SQ YD	630	630
44201757	CLASS D PATCHES, TYPE III, 9 INCH	SQ YD	380	380
44201759	CLASS D PATCHES, TYPE IV, 9 INCH	SQ YD	255	255
60201330	CATCH BASIN, TYPE A 4' DIA, TYPE 23 F&G	EACH	1	1
60252800	CATCH BASINS TO BE RECONSTRUCTED	EACH	1	1
60258100	MANHOLES TO BE CONSTRUCTED W/NEW TYPE 1 FRAME, OPEN LID	EACH	2	2
60262700	INLETS TO BE RECONSTRUCTED	EACH	1	1
60250200	CATCH BASIN TO BE ADJUSTED	EACH	3	3
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	4	4
60257900	MANHOLES TO BE RECONSTRUCTED	EACH	4	4
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	2	2
60253900	CATCH BASIN TO BE RECONSTRUCTED W/NEW TYPE 9 FRAME & GRATE	EACH	1	1
~~60602500~~	~~CONCRETE GUTTER, TYPE A~~	~~FOOT~~	~~175~~	~~175~~
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	3	3

FILE NAME =	USER NAME = solnwlich	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL-131 (S. GREEN BAY RD) FROM IL-120 (BELVIDERE) TO IL-132 SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
pw:\\IDOTAEBDINTEGJ11tnls.pw:PW(DOT\Documents\IDOT	Office\District Projects\D385\6\CADData\Design\D385\GBR-bwlich	DESIGN -	REVISED -			2711	UR-RS-1	LAKE	25	3
	PLOT SCALE = 100.000 ' / in.	CHECKED -	REVISED -					CONTRACT NO. 62C78		
	PLOT DATE = 3/28/2017	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. 20+00 TO STA. 94+00	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

REV 6-7-17

Rev

URBAN

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	80 (FED) 20 (STATE) ROADWAY 005					
X0320050	CONSTRUCTION LAYOUT (SPECIAL)	LSUM	1	1					
X5537800	STORM SEWERS TO BE CLEANED 12"	FOOT	200	200					
X6030310	FRAMES AND LIDS TO BE ADJUSTED	EACH	15	15					
	(SPECIAL)								
X7030005	TEMPORARY PAVEMENT MARKING REMOVAL	SQ FT	15000	15000					
Z0004562	COMBINATION CONCRETE CURB AND GUTTER	FOOT	475	475					
	REMOVAL AND REPLACEMENT								
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	20	20					
Z0030850	TEMPORARY INFORMATION SIGNING	SQ FT	103	103					

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	ROADWAY 005					

FILE NAME = pw:\\ILOB4EBI0INTEG.illinois.gov:PWIDOT\Documents\VDOT	USER NAME = sdfrivlich	DESIGNED -	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	IL-131 (S. GREEN BAY RD) FROM IL-120 (BELVIDERE) TO IL-132 SUMMARY OF QUANTITIES	F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
	Office\District hProjects\D1385\6\CADData\Design\D1385\GBR\Design	-	REVISED -			2711	UR-RS-1	LAKE	25	5
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -					CONTRACT NO. 62C78		
	PLOT DATE = 3/29/2017	DATE -	REVISED -		SCALE: SHEET NO. OF SHEETS STA. 20+00 TO STA. 94+00	FED. ROAD DIST. NO. 1	ILLINOIS	FED. AID PROJECT		

□ NON-PARTICIPATING

△ REV 6-7-17