URBAN

SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE						
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED 20% STATE						
42400800	DETECTABLE WARNINGS	SQ FT	34	34						
44000158	HOT-MIX ASPHALT SURFACE REMOVAL, 2	SQ YD	72855	72855						
	1/4"									
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	46	46						
44000600	SIDEWALK REMOVAL	SQ FT	600	600						
44201823	CLASS D PATCHES, TYPE I, 15 INCH	SQ YD	80	80						
44201827	CLASS D PATCHES, TYPE II, 15 INCH	SQ YD	3200	3200						
44201831	CLASS D PATCHES, TYPE III, 15 INCH	SQ YD	700	700						
44201833	CLASS D PATCHES, TYPE IV, 15 INCH	SQ YD	1180	1180						
48101498	AGGREGATE SHOULDERS, TYPE B 4"	SQ YD	304	304						
48102100	AGGREGATE WEDGE SHOULDER, TYPE B	TON	256	256						
50105220	PIPE CULVERT REMOVAL	FOOT	170	170						
54213657	PRECAST REINFORCED CONCRETE FLARED END	EACH	8	8						
	SECTIONS 12"									
542A0217	PIPE CULVERTS, CLASS A, TYPE 1 12"	FOOT	160	160						
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	1	1						

URBAN

	SUMMARY OF QUANTITIES				CONSTRUCTION TYPE CODE					
	CODE NO	ITEM	UNIT	TOTAL QUANTITIES	0005 80% FED 20% STATE					
*	63000003	STEEL PLATE BEAM GUARDRAIL, TYPE A, 9	FOOT	787.5	787.5					
		FOOT POSTS								
*	63000030	STRONG POST GUARDRAIL ATTACHED TO	FOOT	50	50					
		CULVERT								
*	63100167	TRAFFIC BARRIER TERMINAL, TYPE 1	EACH	11	11					
		(SPECIAL) TANGENT								
	63200310	GUARDRAIL REMOVAL	FOOT	1250	1250					
	64200108	SHOULDER RUMBLE STRIPS, 8 INCH	FOOT	2560	2560					
*	66900200	NON-SPECIAL WASTE DISPOSAL	CU YD	73	73					
*	66900450	SPECIAL WASTE PLANS AND REPORTS	LSUM	1	1					
*	66900530	SOIL DISPOSAL ANALYSIS	EACH	4	4	△1				
	67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	6	6					
	67100100	MOBILIZATION	LSUM	1	1					
	70102620	TRAFFIC CONTROL AND PROTECTION,	LSUM	1	1					
		STANDARD 701501								
	70102622	TRAFFIC CONTROL AND PROTECTION,	LSUM	1	1					
		STANDARD 701502								
	70102635	TRAFFIC CONTROL AND PROTECTION,	LSUM	1	1					
		STANDARD 701701								

* = SPECIALTY ITEMS

FILE NAME = pw:\\ILDB4EBIDINTEG.illinois.gov:PWIDOT\Documents\IDOT Offices\District 1\Projects\D1T516\CADData\Design\D1T516_sht_Rev.dgn	USER NAME = Vellichkovv	DESIGNED -	REVISED -
		-	REVISED -
	PLOT SCALE = 100.0000 ' / in.	CHECKED -	REVISED -
	PLOT DATE = 3/31/2017	DATE -	REVISED -

STATE OF ILLINOIS
DEPARTMENT OF TRANSPORTATION

IL 25 – JOHNOR AVE TO SOUTH OF BREWSTER CREEK BRIDGE
SUMMARY OF QUANTITIES

SCALE: | SHEET NO. OF SHEETS | STA. TO STA.

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
2503	(38, 43 & 49) RS-7	KANE	36	5
		CONTRACT NO. 62B90		

FED. ROAD DIST. NO. 1 | ILLINOIS | FED. AID PROJECT

△1 REV 6-7-17