

PAVEMENT REMOVAL FOR PATCHING								
MILE POINT	LANE	LENGTH (FT)	WIDTH (FT)	SQ YD	PARTIAL DEPTH REMOVAL, 3"			LONGITUDINAL PARTIAL DEPTH REMOVAL, 3"
MILE POINTS START AT ST. THOMAS ROAD (WEST TO EAST)					TYPE I	TYPE II	TYPE IV	
EASTBOUND								
0.99	2	3	12	4.00	4.00			
1.50	2	40	3	13.33		13.33		
1.94	1	3	12	4.00	4.00			
1.99	2	3	12	4.00	4.00			
2.24	1	3	12	4.00	4.00			
2.24	2	3	12	4.00	4.00			
2.35	1	3	12	4.00	4.00			
2.61	2	3	12	4.00	4.00			
2.73	3	40	3	13.33		13.33		
3.19	2	6	12	8.00		8.00		
3.19	3	6	12	8.00		8.00		
3.25	3	8	12	10.67		10.67		
3.26	3	6	12	8.00		8.00		
3.26	2	6	12	8.00		8.00		
3.28	3	4	12	5.33		5.33		
3.29	2	4	12	5.33		5.33		
3.29	3	4	12	5.33		5.33		
3.57	3	4	12	5.33		5.33		
4.35	2	4	12	5.33		5.33		
4.59	2	4	12	5.33		5.33		
4.84	1	4	12	5.33		5.33		
7.36	2	40	12	53.33			53.33	
8.14	2	10	6	6.67		6.67		
8.53	1	5	12	6.67		6.67		
8.63	1	4	12	5.33		5.33		
8.64	2	4	12	5.33		5.33		
		SUB-TOTAL			28.0	130.7	53.3	0.0
		ANTICIPATED FAILURES (10%)			2.8	13.1	5.3	0.0
		EB SUB-TOTAL			31	144 *	59*	0 *

NOT TOTAL QUANTITY.
SEE WESTBOUND SCHEDULE
FOR REMAINING QUANTITY

RAISED REFLECTIVE PAVEMENT MARKER	
MILE POINT	
EASTBOUND	EACH
0.99	0
1.50	2
1.94	0
1.99	0
2.24	0
2.24	0
2.35	0
2.61	0
2.73	2
3.19	0
3.19	0
3.25	0
3.26	0
3.26	0
3.28	0
3.29	0
3.29	0
3.57	0
4.35	0
4.59	0
4.84	0
7.36	2
8.14	0
8.53	0
8.63	0
8.64	0
EB RRPM TOTAL	6 *

*NOT TOTAL QUANTITY.
SEE WESTBOUND SCHEDULE
FOR REMAINING QUANTITY



REV. 6-6-2017