

PATCHING SCHEDULE FOR EASTBOUND LANE

LOCATION	PATCH LENGTH	CLASS B			DOWEL BARS 1 1/2"	SAW CUTS	WELDED WIRE REINF.	TIE BARS 3/4"
		TYPE II 14"	TYPE III 14"	TYPE IV 14"				
LOG MILE	(FT)	SO YD	SO YD	SO YD	EACH	FOOT	SO YD	EACH
0.00	INTERSECTION OF US 34 E11TH RD.							
1.20	12		16		20	60	16	
1.20	12		16		20	60	16	
1.20	6	8			20	48		
1.20	6	8			20	48		
1.20	6	8			20	48		
1.50	6	8			20	48		
1.50	6	8			20	48		
1.50	6	8			20	48		
1.50	6	8			20	48		
1.50	6	8			20	48		
1.50	6	8			20	48		
1.80	12		16		20	60	16	
1.90	6	8			20	48		
1.90	6	8			20	48		
1.90	6	8			20	48		
2.00	6	8			20	48		
2.00	10	13			20	56		
2.00	6	8			20	48		
2.10	6	8			20	48		
2.10	6	8			20	48		
2.30	6	8			20	48		
2.30	6	8			20	48		
2.30	6	8			20	48		
2.30	6	8			20	48		
2.40	12		16		20	60	16	
2.40	6	8			20	48		
2.40	6	8			20	48		
2.40	6	8			20	48		
2.40	6	8			20	48		
2.50	6	8			20	48		
2.50	12		16		20	60	16	
2.60	6	8			20	48		
2.60	6	8			20	48		
2.60	6	8			20	48		
2.60	6	8			20	48		
2.60	16		21		20	68	21	
2.60	6	8			20	48		
2.60	6	8			20	48		
2.60	6	8			20	48		
2.70	6	8			20	48		
2.70	6	8			20	48		
2.90	6	8			20	48		
2.90	6	8			20	48		
2.90	12		16		20	60	16	
3.10	6	8			20	48		
3.10	12		16		20	60	16	
SUBTOTALS	338	317	133		940	2368	133	

PATCHING SCHEDULE FOR EASTBOUND LANE

LOCATION	PATCH LENGTH	CLASS B			DOWEL BARS 1 1/2"	SAW CUTS	WELDED WIRE REINF.	TIE BARS 3/4"
		TYPE II 14"	TYPE III 14"	TYPE IV 14"				
LOG MILE	(FT)	SO YD	SO YD	SO YD	EACH	FOOT	SO YD	EACH
3.30	6	8			20	48		
3.30	6	8			20	48		
3.30	12		16		20	60	16	
3.40	6	8			20	48		
3.40	10	13			20	56		
3.50	6	8			20	48		
3.50	6	8			20	48		
3.50	16		21		20	68	21	
3.50	6	8			20	48		
3.70	6	8			20	48		
3.70	6	8			20	48		
3.70	16		21		20	68	21	
3.90	6	8			20	48		
3.90	6	8			20	48		
3.90	6	8			20	48		
3.90	16		21		20	68	21	
3.90	6	8			20	48		
3.90	6	8			20	48		
4.00	6	8			20	48		
4.00	6	8			20	48		
4.00	10	13			20	56		
4.20	6	8			20	48		
4.20	6	8			20	48		
4.20	6	8			20	48		
4.20	6	8			20	48		
4.30	12		16		20	60	16	
4.50	6	8			20	48		
4.60	6	8			20	48		
4.60	6	8			20	48		
4.60	6	8			20	48		
4.60	6	8			20	48		
4.80	10	13			20	56		
4.90	12		16		20	60	16	
5.00	16		21		20	68	21	
5.30	6	8			20	48		
5.30	6	8			20	48		
5.30	6	8			20	48		
5.30	16		21		20	68	21	
5.50	6	8			20	48		
5.50	6	8			20	48		
5.50	10	13			20	56		
5.50	6	8			20	48		
5.50	6	8			20	48		
5.60	6	8			20	48		
5.80	6	8			20	48		
5.80	6	8			20	48		
5.80	16		21		20	68	21	
6.00	10	13			20	56		
SUBTOTALS	386	339	174		960	2500	174	

FILE NAME: p:\11\LB04E01\INTEG.illinois.gov\1007\Do	USER NAME: woodhankr1	DESIGNED - RW	REVISED -	STATE OF ILLINOIS DEPARTMENT OF TRANSPORTATION	SCHEDULES - EASTBOUND	F.A.P. RTE. 587	SECTION (17,18)PP	COUNTY LASALLE	TOTAL SHEETS 10	SHEET NO. 6	
	Documents\1007\Offices\District 3\Projects\036	DRAWN Date\66H37RW	REVISED -			SCALE: 100.0000' / in.	CHECKED - EP	REVISED -		CONTRACT NO. 66H37	
Default	PLOT DATE: 6/1/2017	DATE: 2/24/2017	REVISED -			SCALE: SHEET 2 OF 2 SHEETS	STA. TO STA.			ILLINOIS FED. AID PROJECT	

1) SHEET SWAPPED 6-5-17