

LOCATION	20200100	FOR INFORMATION ONLY		
	EARTH EXCAVATION	EXCAVATION TO BE USED IN EMBANKMENT (ADJUSTED FOR SHRINKAGE) (EXC. x 0.75)	EMBANKMENT (FILL)	EARTHWORK BALANCE WASTE(+) AND SHORTAGE (-)
	CU. YD.	CU. YD.	CU. YD.	CU. YD.
STA. 9+52.00 TO STA. 9+59.11	4	3	3	0
STA. 9+59.11 TO STA. 10+32.89		0		0
STA. 10+32.89 TO STA. 10+40.00	4	3	3	0
TOTAL	8	6	6	0

EARTH EXCAVATION SHRINKAGE FACTOR = 25%

35101400 AGGREGATE BASE COURSE, TYPE B

TR 209A (WINDSOR RD.)	TON
CL 9+52.00 TO CL 9+59.79	9
CL 10+32.2 TO CL 10+40.00	9
TOTAL	18

60103700 PIPE DRAINS, CORRUGATED STEEL 18"

TR 209A (WINDSOR RD.)	FOOT
18' LT 9+70.00 TO LT 9+90.00	20
TOTAL	20

X7011800 TRAFFIC CONTROL AND PROTECTION, STANDARD BLR 21

TR 209A (WINDSOR RD.)	L SUM
TOTAL	1

67100100 MOBILIZATION

TR 209A (WINDSOR RD.)	L SUM
TOTAL	1

60100060 CONCRETE HEADWALLS FOR PIPE DRAINS

TR 209A (WINDSOR RD.)	EACH
18' LT 9+90.00	1
18' LT 10+10.00	1
TOTAL	2

X2501000 SEEDING, CLASS 2 (SPECIAL)

TR 209A (WINDSOR RD.)	ACRE
LT 9+52.00 TO LT 9+59.79	0.03
LT 10+32.2 TO LT 10+40.00	0.03
RT 9+52.00 TO RT 9+59.79	0.03
RT 10+32.2 TO RT 10+40.00	0.03
* TOTAL PER MIN. DEGREE OF ACCURACY	TOTAL 0.25

60103600 PIPE DRAINS, CORRUGATED STEEL 15"

TR 209A (WINDSOR RD.)	FOOT
18' LT 10+10.0 TO LT 10+30.00	20
TOTAL	20

X6110073 EXISTING FIELD TILE REMOVAL

TR 209A (WINDSOR RD.)	FOOT
18' LT 9+70.00 TO LT 9+90.00	20
18' LT 10+10.0 TO LT 10+30.00	20
TOTAL	40

MODEL Default: design firm no. 184001036 FILE NAME: C:\WHKS & CO\Jobs\Springs - Projects\Champaign County\9323 Champaign Co. TR209A over Kaskaskia Ditch\CADD\CAD Sheets\9323-24-18-schedule.dgn

design firm no. 184001036	USER NAME = bjohanson	DESIGNED - BJJ	REVISED - 06/02/2023
whks engineers + planners + land surveyors	DRAWN - GSJ/BJJ	CHECKED - CWC	REVISED -
	PLOT SCALE = 100:0.0000 " = 1"	DATE - 6/2/2023	REVISED -
	PLOT DATE = 6/2/2023		

CHAMPAIGN COUNTY HIGHWAY DEPARTMENT

SCHEDULE OF QUANTITIES			
TR 209A (WINDSOR RD.) OVER KASKASKIA DITCH			
SCALE: 1" = 50'	SHEET 1	OF 1 SHEETS	STA. TO STA.

T.R. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
209A	22-03122-00-BR	CHAMPAIGN	20	6
			CONTRACT NO. 91632	
			ILLINOIS FED. AID PROJECT	