

SUMMARY OF QUANTITIES

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
3545	54-WRS-7	DUPAGE	235	9
STA.		TO STA.		
FED. ROAD DIST. NO.		ILLINOIS FED. AID PROJECT		
CONTRACT NO. 62291				

CODE NO.	ITEM	UNIT	URBAN TOTAL QUANTITY	ROADWAY																				
				100% STATE 1000-2A	TRAFFIC SIGNALS RTE 56 @ SUMMIT/MIDWEST RD 90% STATE 10% DUPAGE CO. Y031-1F	SUMMIT/MIDWEST PRE-EMPTION EQUIPMENT 100% OAKBROOK TERRACE Y031-3D	TRAFFIC SIGNALS RTE 56 @ MYRTLE/MACARTHUR 90% STATE 10% OAKBROOK TERRACE Y031-1F	MYRTLE/MACARTHUR PRE-EMPTION EQUIPMENT 100% OAKBROOK TERRACE Y031-3D	TRAFFIC SIGNAL INTERCONNECT 100% STATE Y031-1F	SIDEWALK 50% STATE 50% OAKBROOK SFTY-1B	BIKE PATH 100% OAKBROOK TERRACE PARK DIST SFTY-1B	OAK BROOK WATER MAIN 100% OAKBROOK TERRACE Y060	OAKBROOK TERRACE WATER MAIN 100% OAKBROOK TERRACE Y060	OAK BROOK SEWER UPGRADE 75% STATE 25% OAK BROOK Y060	OAKBROOK TERRACE SEWER UPGRADE 60% STATE 40% OAKBROOK TERRACE Y060	HINSDALE SANITARY DISTRICT SEWER 100% SANITARY DISTRICT Y060								
72900200	METAL POST - TYPE B	FOOT	252	252																				
73400100	CONCRETE FOUNDATIONS	CU YD	95	95																				
73502000	RELOCATE GROUND-MOUNTED SIGN SUPPORT	EACH	1	1																				
73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	3	3																				
78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	1,274	1,274																				
78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	32,727	32,727																				
78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	3,726	3,726																				
78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	179	179																				
78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	1,228	1,228																				
78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	440	440																				
78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	950	950																				
78100200	TEMPORARY RAISED REFLECTIVE PAVEMENT MARKER	EACH	375	375																				
78300100	PAVEMENT MARKING REMOVAL	SQ FT	13,384	13,384																				
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	548	548																				
81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	5048		835		511		3,702															
81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	216		114		102																	
81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	28		18		10																	
81001100	CONDUIT IN TRENCH, 5" DIA., GALVANIZED STEEL	FOOT	10		10																			
81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	955		346		95		514															
81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	793		524		269																	
81400100	HANDHOLE	EACH	18		6		5		7															
81400200	HEAVY-DUTY HANDHOLE	EACH	6		4		2																	
81400300	DOUBLE HANDHOLE	EACH	3		2		1																	
81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	5209		950		557		3,702															
85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	1						1															
85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	2		1		1																	
86400100	TRANSCEIVER-FIBER OPTIC	EACH	2		1		1																	
87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	1791		1,532		259																	
87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	2173		1,450		723																	
87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	2098		1,152		946																	
87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	3541		2,107		1,434																	
87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	4345		2,964		1,381																	
87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	98		54		44																	

⊗ - DENOTES SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
F.A.U. ROUTE 3545
IL RTE 56 (BUTTERFIELD ROAD)

SUMMARY OF QUANTITIES

SCALE: NTS
DATE: 2/20/04
DRAWN BY: SMP
CHECKED BY: BDH