

CODE NUMBER	ITEM	UNIT	URBAN TOTAL	ROADWAY		SIDEWALK		TRAFFIC SIGNALS						LIGHTING	WATER MAIN			SANITARY SEWER
				100 % STATE	100 % STATE	50% STATE WESTMONT	50% STATE CLARENDON HILLS	FAIRVIEW 100% STATE	CASS 90% STATE WESTMONT	WOODSTOCK 90% STATE CLARENDON HILLS	MIDDAUGH 90% STATE CLARENDON HILLS	PROSPECT 93.3% STATE CLARENDON HILLS	INTERCONNECT CASS AVE 100% STATE	100 % WESTMONT	100% STATE	100% CLARENDON HILLS	63% STATE CLARENDON HILLS	100% DOWNERS SANITARY DISTRICT
				J000-2A	J000-1B	SPTV-1B	SPTV-1B	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y031-1F	Y030-1E	Y060-	Y060-	Y060-
42400200	PORTLAND CEMENT CONCRETE SIDEWALK 5 INCH	SQ FT	109,931	70,726		31,940	7,265											
42400610	TEMPORARY SIDEWALK	SQ FT	2,710	2,710														
44000006	BITUMINOUS SURFACE REMOVAL, 1 1/2"	SQ YD	1,040	1,040														
44000100	PAVEMENT REMOVAL	SQ YD	53,135	53,135														
44000200	DRIVEWAY PAVEMENT REMOVAL	SQ YD	7,662	7,662														
44000300	CURB REMOVAL	FOOT	435	435														
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	4,651	4,651														
44000600	SIDEWALK REMOVAL	SQ FT	63,502	63,502														
44004250	PAVED SHOULDER REMOVAL	SQ YD	408	408														
44300100	AREA REFLECTIVE CRACK CONTROL TREATMENT	SQ YD	800	800														
44300200	STRIP REFLECTIVE CRACK CONTROL TREATMENT	FOOT	600	600														
48200600	BITUMINOUS SHOULDERS 8"	SQ YD	133	133														
50102400	CONCRETE REMOVAL	CU YD	20	20														
50104400	CONCRETE HEADWALL REMOVAL	EACH	4	4														
X0323099	RETAINING WALL REMOVAL	CU YD	2	2														
50105220	PIPE CULVERT REMOVAL	FOOT	425	425														
50300225	CONCRETE STRUCTURES	CU YD	2.8	2.8														
54214743	PRECAST REINFORCED CONCRETE FLARED END SECTIONS - ELLIPTICAL, EQUIVALENT ROUND SIZE 48"	EACH	1	1														
54216231	REINFORCED CONCRETE PIPE TEE, 42" PIPE WITH 12" RISER	EACH	3	3														
54216242	REINFORCED CONCRETE PIPE TEE, 48" PIPE WITH 12" RISER	EACH	7	7														
54248180	GRATING FOR CONCRETE FLARED END SECTION EQUIVALENT ROUND-SIZE 48"	EACH	1	1														
55039700	STORM SEWERS TO BE CLEANED	FOOT	100	100														
550A0050	STORM SEWERS, CLASS A, TYPE 1 12"	FOOT	1,091	1,091														
550A0090	STORM SEWERS, CLASS A, TYPE 1 18"	FOOT	177	177														
550A0110	STORM SEWERS, CLASS A, TYPE 1 21"	FOOT	176	176														
550A0120	STORM SEWERS, CLASS A, TYPE 1 24"	FOOT	300	300														
550A0190	STORM SEWERS, CLASS A, TYPE 1 48"	FOOT	46	46														
550A0340	STORM SEWERS, CLASS A, TYPE 2 12"	FOOT	4,924	4,924														
550A0360	STORM SEWERS, CLASS A, TYPE 2 15"	FOOT	1,032	1,032														
550A0380	STORM SEWERS, CLASS A, TYPE 2 18"	FOOT	1,047	1,047														

• = SPECIALTY ITEM



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

**SUMMARY OF QUANTITIES**  
**MAPLE AVENUE / CHICAGO AVENUE**  
**SHEET 2 OF 10**

SCALE: NONE  
DATE: 27-APR-2005

DRAWN BY: E.D.  
CHECKED BY: G.T.