

CODE NUMBER	ITEM	UNIT	URBAN TOTAL	ROADWAY		SIDEWALK			TRAFFIC SIGNALS					LIGHTING	WATER MAIN			SANITARY SEWER
				100 % STATE	100 % STATE	50% STATE	50% STATE	FAIRVIEW	CASS	WOODSTOCK	MIDDAUGH	PROSPECT	INTERCONNECT	100 % WESTMONT	100% STATE	100% CLARENDON HILLS	83% STATE	100% DOWNERS SANITARY DISTRICT
				J000-2A	<del>1000-1A</del>	50% WESTMONT SFTY-1B	50% CLARENDON HILLS SFTY-1B	100% STATE	90% STATE	90% STATE	90% STATE	93.3% STATE	100% STATE	Y030-1E	<del>Y060-</del>	Y060-	<del>Y060-</del>	Y060-
X 78008270	POLYUREA PAVEMENT MARKING TYPE I - LINE 24"	FOOT	764	764														
X 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	729	729														
X 78100105	RAISED REFLECTIVE PAVEMENT MARKER (BRIDGE)	EACH	8	8														
78300100	PAVEMENT MARKING REMOVAL	SQ FT	510	510														
X 80700140	GROUND ROD, 5/8" DIA. X 10 FT.	EACH	7										7					
X 81000600	CONDUIT IN TRENCH, 2" DIA., GALVANIZED STEEL	FOOT	1742					324	435	480	439	64						
X 81000700	CONDUIT IN TRENCH, 2 1/2" DIA., GALVANIZED STEEL	FOOT	528					109	167	99	153							
<del>X 81000800</del>	<del>CONDUIT IN TRENCH, 3" DIA., GALVANIZED STEEL</del>	<del>FOOT</del>	<del>91</del>															
X 81001000	CONDUIT IN TRENCH, 4" DIA., GALVANIZED STEEL	FOOT	314					57	101	52	104							
X 81018500	CONDUIT PUSHED, 2" DIA., GALVANIZED STEEL	FOOT	1055					348	123	40	144							
X 81018900	CONDUIT PUSHED, 4" DIA., GALVANIZED STEEL	FOOT	754					310	196	146	102							
X 81400100	HANDHOLE	EACH	22					5	7	5	5							
X 81400200	HEAVY DUTY HANDHOLE	EACH	4					4										
X 81400300	DOUBLE HANDHOLE	EACH	6					2	2	1	1							
X 81500200	TRENCH AND BACKFILL FOR ELECTRICAL WORK	FOOT	3749					445	704	632	604	64	1,300					
X 81601020	UNIT DUCT, WITH 3-1/C NO. 4 AND 1/C NO. 6 GROUND, 600V (XLP-TYPE USE), 1 1/4" DIA., POLYETHYLENE	FOOT	1,500										1,500					
X 82102250	LUMINAIRE, SODIUM VAPOR, HORIZONTAL MOUNT, 250 WATT	EACH	6										6					
X 83007500	LIGHT POLE, ALUMINUM, 35 FT. M.H., 12 FT. MAST ARM	EACH	6										6					
X 83600200	LIGHT POLE FOUNDATION, 24" DIAMETER	FOOT	80										80					
X 84400105	RELOCATE EXISTING LIGHTING UNIT	EACH	2										2					
X 85000200	MAINTENANCE OF EXISTING TRAFFIC SIGNAL INSTALLATION	EACH	2					1					1					
X 85700200	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET	EACH	3						1	1	1							
X 85700205	FULL-ACTUATED CONTROLLER AND TYPE IV CABINET, SPECIAL	EACH	1					1										
X 86400100	TRANSCEIVER-FIBER OPTIC	EACH	1					1										
X 87301215	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 2C	FOOT	3110					1,177	915	706	312							
X 87301225	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 3C	FOOT	5170					1,522	1,828	1,327	493							
X 87301245	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 5C	FOOT	5771					709	2,342	1,670	1,050							
X 87301255	ELECTRIC CABLE IN CONDUIT, SIGNAL NO. 14 7C	FOOT	1579					1,395			184							
X 87301305	ELECTRIC CABLE IN CONDUIT, LEAD-IN, NO. 14 1 PAIR	FOOT	5074					1,967	1,079	904	1,124							
X 87301805	ELECTRIC CABLE IN CONDUIT, SERVICE, NO. 6 2C	FOOT	233					98	31	30	74							

\* = SPECIALTY ITEM  
 Y = Y080  
 Z = 100% Village of Westmont Y031-30



NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
**SUMMARY OF QUANTITIES**  
**MAPLE AVENUE / CHICAGO AVENUE**  
**SHEET 6 OF 10**  
 SCALE: NONE  
 DATE: 21-MAR-2005  
 DRAWN BY: E.D.  
 CHECKED BY: G.T.