

EARTHWORK SUMMARY

①		②		③		④		⑤		⑥	
STATION TO STATION	EARTH EXCAVATION CUBIC YARD	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL CUBIC YARD	EXCAVATION FOR EMBANKMENT (ADJUSTED FOR SHRINKAGE) CUBIC YARD	EMBANKMENT CUBIC YARD	FURNISHED EXCAVATION EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CUBIC YARD						
117+76.00 118+00.00	53.3	4.6	45.3	1.8	43.5						
118+00.00 118+50.00	71.3	12.5	60.6	3.5	57.1						
118+50.00 118+73.00	33.4	4.3	28.4	0.7	27.7						
118+73.00 119+00.00	35.5	5.2	30.2	2.1	28.0						
119+00.00 119+50.00	49.8	8.0	42.4	10.8	31.6						
119+50.00 119+58.00	7.6	0.7	6.5	2.2	4.2						
119+58.00 119+90.36	28.7	3.9	24.4	10.2	14.2						
119+90.36 120+00.00	7.0	1.2	5.9	4.6	1.3						
120+00.00 120+50.00	30.6	9.7	26.0	35.4	-9.3						
120+50.00 121+00.00	19.2	9.4	16.3	64.8	-48.5						
121+00.00 121+50.00	15.3	7.3	13.0	76.2	-63.2						
121+50.00 122+00.00	18.3	8.5	15.5	65.1	-49.5						
122+00.00 122+37.00	16.5	4.9	14.1	46.2	-32.1						
122+37.00 122+50.00	6.3	3.1	5.4	15.9	-10.5						
122+50.00 123+00.00	18.4	15.8	15.7	61.0	-45.3						
123+00.00 123+50.00	15.3	10.2	13.0	60.7	-47.7						
123+50.00 123+59.00	2.8	1.2	2.4	11.4	-8.9						
123+59.00 124+00.00	15.8	8.0	13.5	41.3	-27.9						
124+00.00 124+25.00	10.3	4.9	8.8	18.8	-10.0						
124+25.00 124+50.00	9.9	3.0	8.4	15.3	-6.9						
124+50.00 125+00.00	22.2	8.8	18.9	21.8	-2.9						
125+00.00 125+50.00	39.1	7.7	33.3	12.7	20.6						
125+50.00 125+59.00	9.8	0.6	8.3	1.0	7.3						
125+59.00 126+00.00	41.1	5.8	34.9	3.3	31.7						
126+00.00 126+50.00	59.7	8.9	50.8	1.9	48.9						
126+50.00 126+62.00	19.5	1.1	16.6	0.3	16.3						
126+62.00 126+87.00	43.8	1.4	37.2	0.7	36.5						
126+87.00 127+00.00	20.7	1.6	17.6	0.3	17.3						
127+00.00 127+50.00	86.8	7.9	73.8	0.3	73.5						
127+50.00 127+60.00	20.6	1.3	17.5	0.0	17.5						
127+60.00 128+00.00	71.0	7.7	60.3	0.2	60.1						
128+00.00 128+10.00	15.2	1.9	13.0	0.1	12.9						
128+10.00 128+50.00	54.3	6.0	46.2	0.1	46.1						
128+50.00 128+63.00	15.2	2.1	12.9	0.0	12.9						
128+63.00 129+00.00	34.7	7.7	29.5	0.5	29.0						
129+00.00 129+18.00	11.5	3.5	9.8	0.7	9.1						
129+18.00 129+50.00	31.8	4.1	27.0	1.2	25.9						
129+50.00 129+57.14	9.5	1.0	8.1	0.2	7.9						
129+57.14 130+00.00	49.2	7.8	41.8	1.5	40.3						
130+00.00 130+20.00	18.7	3.1	15.9	1.0	14.8						

①		②		③		④		⑤		⑥	
STATION TO STATION	EARTH EXCAVATION CUBIC YARD	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL CUBIC YARD	EXCAVATION FOR EMBANKMENT (ADJUSTED FOR SHRINKAGE) CUBIC YARD	EMBANKMENT CUBIC YARD	FURNISHED EXCAVATION EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CUBIC YARD						
130+20.00 130+50.00	30.1	4.5	25.6	1.1	24.5						
130+50.00 131+00.00	52.5	11.6	44.6	3.2	41.4						
131+00.00 131+50.00	46.6	11.4	39.6	3.9	35.7						
131+50.00 132+00.00	27.4	7.3	23.3	5.9	17.4						
132+00.00 132+50.00	29.7	7.5	25.2	7.6	17.6						
132+50.00 132+69.00	17.1	2.7	14.5	1.7	12.8						
132+69.00 133+00.00	22.6	4.3	19.2	4.7	14.4						
133+00.00 133+23.00	16.3	3.7	13.8	4.8	9.1						
133+23.00 133+50.00	20.5	4.3	17.4	5.9	11.5						
133+50.00 134+00.00	49.6	11.1	42.2	8.6	33.6						
134+00.00 134+21.00	27.9	3.6	23.7	1.5	22.2						
134+21.00 134+50.00	38.7	5.5	32.9	1.4	31.5						
134+50.00 135+00.00	66.3	13.2	56.3	4.6	51.7						
135+00.00 135+50.00	46.8	6.6	39.8	3.6	36.2						
135+50.00 135+63.00	26.2	2.0	22.3	0.1	22.2						
135+63.00 136+00.00	82.5	11.3	70.2	6.5	63.6						
136+00.00 136+50.00	42.9	10.8	36.5	20.4	16.1						
136+50.00 136+91.46	32.3	4.8	27.5	20.4	7.0						
136+91.46 137+00.00	6.8	0.9	5.8	4.3	1.5						
137+00.00 137+50.00	40.5	5.9	34.4	58.6	-24.1						
137+50.00 138+00.00	24.8	9.5	21.1	94.8	-73.7						
138+00.00 138+50.00	8.2	16.1	7.0	123.5	-116.5						
138+50.00 138+59.00	1.3	3.7	1.1	27.7	-26.5						
138+59.00 138+80.00	2.4	8.7	2.1	77.6	-75.5						
138+80.00 139+00.00	0.9	5.5	0.8	63.2	-62.4						
139+00.00 139+50.00	4.2	8.7	3.6	102.0	-98.4						
139+50.00 140+00.00	3.4	5.2	2.9	70.5	-67.6						
140+00.00 140+15.95	1.0	0.0	0.9	13.5	-12.6						
140+15.95 140+50.00	8.5	6.4	7.2	28.8	-21.6						
140+50.00 141+00.00	19.7	15.7	16.8	33.3	-16.5						
141+00.00 141+50.00	21.7	6.2	18.5	16.1	2.4						
141+50.00 142+00.00	26.3	3.7	22.4	3.5	18.9						
142+00.00 142+06.00	3.5	0.9	3.0	0.1	2.9						
142+06.00 142+50.00	18.4	4.1	15.6	3.3	12.3						
142+50.00 142+57.12	2.6	0.2	2.2	0.9	1.3						
142+57.12 142+73.00	6.7	1.0	5.7	2.0	3.8						
142+73.00 143+00.00	7.6	4.8	6.4	3.8	2.6						
143+00.00 143+16.00	3.4	2.9	2.9	2.2	0.6						
143+16.00 143+50.00	7.1	7.0	6.0	4.9	1.1						
143+50.00 143+84.00	6.7	7.0	5.7	4.9	0.8						

①		②		③		④		⑤		⑥	
STATION TO STATION	EARTH EXCAVATION CUBIC YARD	REMOVAL & DISPOSAL OF UNSUITABLE MATERIAL CUBIC YARD	EXCAVATION FOR EMBANKMENT (ADJUSTED FOR SHRINKAGE) CUBIC YARD	EMBANKMENT CUBIC YARD	FURNISHED EXCAVATION EARTHWORK BALANCE WASTE (+) OR SHORTAGE (-) CUBIC YARD						
143+84.00 144+00.00	4.4	3.1	3.8	2.1	1.6						
144+00.00 144+50.00	6.9	2.9	5.9	0.1	5.8						
CASS AVE											
12+00.00 12+50.00	5.7	0.0	4.8	5.7	-0.9						
12+50.00 13+00.00	5.4	0.0	4.6	5.4	-0.8						
13+00.00 13+50.00	5.4	0.0	4.6	4.6	-0.1						
13+50.00 13+57.61	0.9	0.0	0.7	0.6	0.1						
13+57.61 14+00.00	4.3	0.0	3.6	3.7	0.0						
14+00.00 14+50.00	4.4	0.0	3.7	4.3	-0.6						
14+50.00 15+00.00	4.3	0.0	3.6	4.3	-0.6						
15+00.00 15+50.00	4.6	0.0	4.0	4.6	-0.7						
15+50.00 16+00.00	4.7	0.0	4.0	4.7	-0.7						
16+00.00 16+41.42	4.1	0.0	3.5	3.5	0.0						
16+41.42 16+50.00	0.8	0.0	0.7	0.7	0.0						
16+50.00 17+00.00	4.3	0.0	3.7	4.3	-0.6						
17+00.00 17+50.00	4.5	0.0	3.8	4.5	-0.7						
17+50.00 17+59.66	2.0	0.0	1.7	0.7	1.0						
17+59.66 17+71.23	4.9	0.0	4.2	0.7	3.5						
17+71.23 17+90.35	10.8	0.0	9.2	1.3	7.9						
17+90.35 18+00.00	6.3	0.0	5.3	0.8	4.6						
18+00.00 18+25.52	19.1	0.0	16.2	1.8	14.4						
18+25.52 18+50.00	20.6	0.0	17.5	1.4	16.0						
18+50.00 19+00.00	52.8	0.0	44.9	2.5	42.4						
19+00.00 19+06.14	7.6	0.0	6.5	0.3	6.2						
19+06.14 19+16.83	13.7	0.0	11.7	0.5	11.2						
19+16.83 19+50.00	70.0	0.2	59.5	2.5	57.0						
NAPERVILLE ROAD INTERSECTION											
20+50.00 21+00.00	34.6	1.8	29.4	6.8	22.6						
21+00.00 21+50.00	40.0	0.0	34.0	0.1	33.9						
21+50.00 21+60.86	8.7	0.2	7.4	0.0	7.4						
21+60.86 22+00.00	31.2	1.8	26.6	0.0	26.5						
22+00.00 22+09.36	7.9	0.4	6.7	0.0	6.7						
22+09.36 22+17.86	7.1	0.2	6.0	0.0	6.0						
22+17.86 22+42.94	20.7	0.6	17.6	0.0	17.6						
22+42.94 22+50.00	5.7	0.3	4.9	0.0	4.9						
22+50.00 22+66.73	15.6	0.4	13.2	0.0	13.2						
22+66.73 23+00.00	36.7	0.8	31.2	0.0	31.2						
23+00.00 23+18.02	20.0	0.4	17.0	0.0	17.0						
23+18.02 23+22.05	4.2	0.0	3.6	0.0	3.6						
23+22.05 23+41.69	18.5	0.0	15.7	0.0	15.7						