

F.A.U. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
1487	66R	DUPAGE	412	77
STA. 23+00.00		TO STA. 144+00.00		
FED. ROAD DIST. NO.		ILLINOIS	FED. AID PROJECT	
CONTRACT NO. 62376				

PIPE TABLE									
PIPE NO.	STATION	-	STATION	CLASS / TYPE	DIAMETER (IN)	LENGTH (FT)	TBF (CU YD)	WMQP (FT)	RCP (FT)
349	115+75.0		115+75.0	CL A TY 1	12	10	1.32		10
351	117+00.0		114+80.0	CL A TY 2	12	216	37.37		216
352	116+75.0		116+75.0	CL A TY 1	12	10	1.32		10
353	117+25.6		117+00.0	CL A TY 2	12	40	8.34	25	15
354	118+00.0		118+00.0	CL A TY 2	12	10	2.35		10
355	118+00.0		118+00.0	CL A TY 2	12	21	5.41	16	5
356	119+50.0		117+00.0	CL A TY 2	12	246	68.39		246
358	119+50.0		119+50.0	CL A TY 2	12	8	2.39		8
362	123+00.0		123+00.0	CL A TY 2	12	17	5.26	17	
363	123+00.0		123+00.0	CL A TY 2	12	5	1.44		5
365	122+95.0		123+00.0	CL A TY 2	12	8	2.56	8	
366	123+00.0		125+70.0	CL A TY 2	12	266	215.02		266
367	125+70.0		125+70.0	CL A TY 2	12	15	4.33	15	
368	125+70.0		125+70.0	CL A TY 2	12	4	1.11		4
369	102+07.5		101+95.0	CL A TY 2	12	25	7.48		25
370	102+48.0		102+48.0	CL A TY 2	12	42	11.68	21	21
373	125+70.0		128+30.0	CL A TY 2	12	256	260.35		256
374	128+30.0		129+90.0	CL A TY 2	12	156	118.59		156
375	62+02.7		61+93.0	CL A TY 2	12	20	14.88	20	
376	58+09.4		57+93.1	CL A TY 2	12	15	4.96		15
377	57+76.4		58+09.0	CL A TY 2	12	33	8.12		33
378	58+09.0		57+91.0	CL A TY 2	12	32	10.24		32
379	57+91.0		57+91.0	CL A TY 2	12	5	1.92		5
380	105+39.0		105+39.0	CL A TY 1	12	5	0.66		5
381	131+01.7		131+01.7	CL A TY 1	12	17	2.24	10	7
382	128+30.0		128+30.0	CL A TY 2	12	5	1.44		5
383	128+30.0		128+30.0	CL A TY 2	12	15	4.49	10	5
384	130+50.0		130+65.0	CL A TY 2	12	16	4.78	16	
385	130+65.0		130+73.0	CL A TY 2	12	6	1.67		6
386	130+65.0		130+73.0	CL A TY 2	12	17	4.37	11	6
387	131+01.7		131+00.0	CL A TY 1	12	7	1.36	7	
388	143+40.0		143+29.0	CL A TY 2	12	14	4.48		14
390	138+25.0		138+25.0	CL A TY 2	12	26	17.27		26
391	72+74.0		72+74.0	CL A TY 1	12	40	5.28		40
392	132+25.0		132+25.0	CL A TY 2	12	5	0.66		5
393	133+85.0		130+73.0	CL A TY 2	12	307	72.15		307
394	133+10.0		133+10.0	CL A TY 2	12	20	2.58	6	14
395	133+85.0		133+85.0	CL A TY 2	12	9	1.43		9
396	133+85.0		133+85.0	CL A TY 2	12	24	3.25	12	12
397	134+45.0		133+85.0	CL A TY 1	12	57	7.52	57	
398	135+00.0		134+45.0	CL A TY 1	12	53	7.00	53	
405	136+35.0		136+85.0	CL A TY 1	12	47	6.20	47	
406	136+85.0		136+85.0	CL A TY 2	12	13	1.47	13	

PIPE TABLE									
PIPE NO.	STATION	-	STATION	CLASS / TYPE	DIAMETER (IN)	LENGTH (FT)	TBF (CU YD)	WMQP (FT)	RCP (FT)
407	137+40.0		137+40.0	CL A TY 2	12	12	1.88	12	
408	138+35.0		138+35.0	CL A TY 2	12	5	1.34	5	
409	136+85.0		139+75.0	CL A TY 2	12	286	185.33		286
410	131+40.0		131+00.0	CL A TY 1	12	38	5.02	38	
412	139+65.0		139+75.0	CL A TY 2	12	22	6.12		22
413	139+75.0		141+77.0	CL A TY 2	15	198	133.85	21	177
414	141+75.0		141+77.0	CL A TY 2	12	3	0.93		3
415	141+77.0		143+29.0	CL A TY 2	21	148	104.34		148
418	500+00.0		500+44.3	CL A TY 2	12	42	12.56		42
419	500+44.3		501+10.0	CL A TY 2	12	70	16.45		70
420	501+10.0		501+47.7	CL A TY 2	15	35	9.87	15	20
421	501+50.0		501+47.7	CL A TY 2	12	15	2.60	15	
422	501+47.7		139+75.0	CL A TY 2	15	33	13.13	21	12
423	140+45.0		140+45.0	CL A TY 2	12	18	5.00	18	
424	130+73.0		130+73.0	CL A TY 2	18	15	12.71		15
425	143+29.0		143+75.0	CL A TY 2	24	41	28.00		41
426	143+75.0		143+75.0	CL A TY 2	24	19	12.20	19	
427	143+75.0		144+86.0	CL A TY 1	24	108	44.50	108	
428	132+30.0		132+30.0	CL A TY 1	12	28	3.70	12	16
429	28+76.0		28+94.0	CL A TY 2	48	18	20.50		18



REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION

DRAINAGE STORM SEWER SCHEDULE
MAPLE AVENUE / CHICAGO AVENUE
SHEET 3 OF 3

SCALE: NONE
DATE: 27-APR-2005
DRAWN BY: E.D.
CHECKED BY: S.K.V.