

ROUTE	SECTION	COUNTY	TOTAL SHEETS	SHEET NUMBER
FAP 305	1518 PCC-PC-2	COOK	17	10

CONTRACT 62457

**WESTBOUND WILLOW ROAD.
W. OF PFINGSTEN RD. TO E. OF IL 43 (WAUKEGAN RD.)**

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2		
		SIZE (W X L)	AREA (SQ. YD.)	TYPE	SIZE (W X L)	AREA (SQ. YD.)	TYPE
160	144+65	12 x 6	8.0	II	12 x 6	8.0	II
161	145+70	12 x 6	8.0	II	12 x 6	8.0	II
162	147+10				12 x 6	8.0	II
163	148+10	12 x 6	8.0	II	12 x 6	8.0	II
164	149+33	12 x 6	8.0	II	12 x 6	8.0	II
165	151+21	12 x 6	8.0	II			
166	151+50				12 x 6	8.0	II
167	152+70	12 x 6	8.0	II	12 x 6	8.0	II
168	156+58	12 x 8	11.0	II	12 x 8	11.0	II
169	157+30	12 x 6	8.0	II	12 x 6	8.0	II
170	158+48	12 x 10	14.0	II	12 x 10	14.0	II
171	159+35	12 x 6	8.0	II	12 x 6	8.0	II
172	161+43	12 x 6	8.0	II	12 x 6	8.0	II
173	162+15	12 x 6	8.0	II	12 x 6	8.0	II
174	163+25	12 x 6	8.0	II	12 x 6	8.0	II
175	163+57	12 x 6	8.0	II	12 x 6	8.0	II
176	164+65	12 x 6	8.0	II	12 x 6	8.0	II
177	164+80				12 x 10	14.0	II
178	165+15	12 x 6	8.0	II	12 x 6	8.0	II
179	165+30	12 x 6	8.0	II	12 x 6	8.0	II
180	167+27	12 x 6	8.0	II	12 x 6	8.0	II
181	168+00				12 x 10	14.0	II
182	168+88	12 x 6	8.0	II	12 x 6	8.0	II
183	169+40	12 x 15	20.0	III			
184	169+65				12 x 6	8.0	II

NOTE: BRIDGE OMISSION - SN: 016-0534 FROM ± STA. 160+25 TO STA 161+20

PATCH LOCATION NUMBER	STATION	LANE 1			LANE 2		
		SIZE (W X L)	AREA (SQ. YD.)	TYPE	SIZE (W X L)	AREA (SQ. YD.)	TYPE
185	169+88				12 x 6	8.0	II
186	170+20	12 x 6	8.0	II	12 x 6	8.0	II
187	171+08	12 x 6	8.0	II	12 x 6	8.0	II
188	171+60				12 x 6	8.0	II
189	172+12	12 x 6	8.0	II	12 x 6	8.0	II
190	173+15	12 x 6	8.0	II	12 x 6	8.0	II
191	173+35	12 x 6	8.0	II	12 x 6	8.0	II
192	174+15	12 x 10	14.0	II	12 x 10	14.0	II
193	175+18	24 x 12	32.0	IV	24 x 12	32.0	IV
194	177+10	12 x 6	8.0	II	12 x 6	8.0	II
195	177+85	24 x 12	32.0	IV	24 x 12	32.0	IV
196	178+15	12 x 8	11.0	II			
197	178+63	12 x 6	8.0	II			
198	180+75	12 x 6	8.0	II			
199	181+30	12 x 6	8.0	II			
200	182+45	12 x 6	8.0	II			
201	183+15	12 x 6	8.0	II	12 x 6	8.0	II
202	183+75	12 x 6	8.0	II	12 x 6	8.0	II
203	184+60				12 x 13	18.0	III
204	185+07	12 x 13	18.0	III			
205	185+23	12 x 12	16.0	III			
206	185+65	24 x 12	32.0	IV			

ILLINOIS DEPARTMENT OF TRANSPORTATION

WILLOW RD.
PAVEMENT PATCHING SCHEDULE