

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000-2A				
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	11	11				
40600300	AGGREGATE (PRIME COAT)	TON	55	55				
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	3	3				
40600895	CONSTRUCTING TEST STRIP	EACH	1	1				
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	510	510				
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	260	260				
44000008	BITUMINOUS SURFACE REMOVAL 2 1/2"	SQ YD	27513	27513				
44000110	BITUMINOUS REMOVAL OVER PATCHES 2 1/2"	SQ YD	1800	1800				
44000500	COMBINATION CURB AND GUTTER REMOVAL	FOOT	80	80				
44004610	SIDEWALK REMOVAL AND REPLACEMENT (SPECIAL)	SQ FT	500	500				
44201765	CLASS D PATCHES, TYPE II, 10 INCH	SQ YD	240	240				
44201769	CLASS D PATCHES, TYPE III, 10 INCH	SQ YD	370	370				
44201771	CLASS D PATCHES, TYPE IV, 10 INCH	SQ YD	680	680				
50300300	PROTECTIVE COAT	SQ YD	123	123				
55039700	STORM SEWERS TO BE CLEANED	FOOT	1500	1500				
60300105	FRAMES AND GRATES TO BE ADJUSTED	EACH	5	5				
60404940	FRAMES AND GRATES, TYPE 23	EACH	3	3				
60404950	FRAMES AND GRATES, TYPE 24	EACH	5	5				
60603800	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.12	FOOT	30	30				
60605000	COMBINATION CONCRETE CURB AND GUTTER, TYPE B-6.24	FOOT	50	50				
67000200	ENGINEER'S FIELD OFFICE, TYPE A	EACH	2	2				
67100100	MOBILIZATION	L SUM	1	1				
70102630	TRAFFIC CONTROL AND PROTECTION, STANDARD 701601	L SUM	1	1				
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	1				
70102640	TRAFFIC CONTROL AND PROTECTION, STANDARD 701801	L SUM	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	4680	4680				
70300210	TEMPORARY PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	115	115				

SUMMARY OF QUANTITIES			CONSTRUCTION TYPE CODE					
CODE NO	ITEM	UNIT	TOTAL QUANTITIES	URBAN 1000-2A				
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	10770	10770				
70300240	TEMPORARY PAVEMENT MARKING - LINE 6"	FOOT	400	400				
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	500	500				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	86	86				
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	520	520				
*78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	115	115				
*78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	10770	10770				
*78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	400	400				
*78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	500	500				
*78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	86	86				
*78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	489	489				
*78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	100	100				
*88600500	DETECTOR LOOP REMOVAL	FOOT	426	426				
*88600600	DETECTOR LOOP REPLACEMENT	FOOT	426	426				
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	51.4	51.4				
X0656100	DRIVEWAY PAVEMENT REMOVAL AND REPLACEMENT	SQ YD	232	232				
X4066548	POLYMERIZED BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "F", N90	TON	2696	2696				
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	1156	1156				
XX003560	CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	500	500				
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	12	12				
Z0018600	DRAINAGE STRUCTURES TO BE RECONSTRUCTED	EACH	3	3				

\* SPECIALITY ITEM

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION  
SUMMARY OF QUANTITIES  
SOUTHWEST HIGHWAY