

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		LOC. 1 URBAN 100% STATE 1000	LOC. 2 URBAN 100% STATE 1000			
20201006	GRADING AND SHAPING SHOULDERS	UNIT	201	117	84			
25000400	NITROGEN FERTILIZER NUTRIENT	POUND	7	4	3			
25000500	PHOSPHORUS FERTILIZER NUTRIENT	POUND	7	4	3			
25000600	POTASSIUM FERTILIZER NUTRIENT	POUND	7	4	3			
25200110	SODDING, SALT TOLERANT	SQ YD	480	280	200			
25200200	SUPPLEMENTAL WATERING	UNIT	2	1	1			
40600200	BITUMINOUS MATERIALS (PRIME COAT)	TON	13	7	6			
40600300	AGGREGATE (PRIME COAT)	TON	63	33	30			
40600400	MIXTURE FOR CRACKS, JOINTS, AND FLANGEWAYS	TON	4	2	2			
40600895	CONSTRUCTING TEST STRIP	EACH	2	1	1			
40600980	BITUMINOUS SURFACE REMOVAL - BUTT JOINT	SQ YD	196	38	158			
40601000	BITUMINOUS REPLACEMENT OVER PATCHES	TON	1225	558	667			
44000124	BITUMINOUS REMOVAL OVER PATCHES 6"	SQ YD	1244	1244				
44000132	BITUMINOUS REMOVAL OVER PATCHES 8"	SQ YD	1489		1489			
44001700	COMBINATION CONCRETE CURB AND GUTTER REMOVAL AND REPLACEMENT	FOOT	2000	2000				
44201729	CLASS D PATCHES, TYPE II, 7 INCH	SQ YD	228	132	96			
44201733	CLASS D PATCHES, TYPE III, 7 INCH	SQ YD	290	118	172			
44201735	CLASS D PATCHES, TYPE IV, 7 INCH	SQ YD	2064	1269	795			
48101200	AGGREGATE SHOULDERS, TYPE B	TON	5381	3123	2258			
50300300	PROTECTIVE COAT	SQ YD	496	496				
55039700	STORM SEWERS TO BE CLEANED	FOOT	600	600				
60253000	CATCH BASINS TO BE RECONSTRUCTED WITH NEW TYPE 1 FRAME, OPEN LID	EACH	2	2				
60300305	FRAMES AND LIDS TO BE ADJUSTED	EACH	28	28				
67000400	ENGINEER'S FIELD OFFICE, TYPE A	CAL MO	4	2	2			
67100100	MOBILIZATION	L SUM	1	.5	.5			
70102620	TRAFFIC CONTROL AND PROTECTION, STANDARD 701501	L SUM	1	.5	.5			
70102625	TRAFFIC CONTROL AND PROTECTION, STANDARD 701606	L SUM	1	.5	.5			
70102635	TRAFFIC CONTROL AND PROTECTION, STANDARD 701701	L SUM	1	.5	.5			

SUMMARY OF QUANTITIES			TOTAL QUANTITIES	CONSTRUCTION TYPE CODE				
CODE NO	ITEM	UNIT		LOC. 1 URBAN 100% STATE 1000	LOC. 2 URBAN 100% STATE 1000			
70103815	TRAFFIC CONTROL SURVEILLANCE	CAL DA	1	1				
70300100	SHORT-TERM PAVEMENT MARKING	FOOT	8412	3474	4938			
70300220	TEMPORARY PAVEMENT MARKING - LINE 4"	FOOT	38412	20316	18096			
70300260	TEMPORARY PAVEMENT MARKING - LINE 12"	FOOT	78	78				
70300280	TEMPORARY PAVEMENT MARKING - LINE 24"	FOOT	278	10	268			
70301000	WORK ZONE PAVEMENT MARKING REMOVAL	SQ FT	935	386	549			
* 78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	38412	20316	18096			
* 78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	78	78				
* 78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	278	10	268			
* 78100100	RAISED REFLECTIVE PAVEMENT MARKER	EACH	431	275	156			
78300200	RAISED REFLECTIVE PAVEMENT MARKER REMOVAL	EACH	355	275	80			
* 88600600	DETECTOR LOOP REPLACEMENT	FOOT	259		259			
X0322256	TEMPORARY INFORMATION SIGNING	SQ FT	102.8	51.4	51.4			
X4066424	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N50	TON	1383	1383				
X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	1266		1266			
X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	1324	691	633			
X4409410	BITUMINOUS SURFACE REMOVAL 2 1/4"	SQ YD	31132	16459	14673			
Z0018500	DRAINAGE STRUCTURES TO BE CLEANED	EACH	28	28				

*SPECIALTY ITEMS

REVISIONS	
NAME	DATE

ILLINOIS DEPARTMENT OF TRANSPORTATION
SUMMARY OF QUANTITIES

PLOT DATE: 3/30/2005

3/30/2005