F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	*	COOK	860	15
STA. 2200+00.00		TO STA. 2362+00.00		
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

* (1516.1, 1717 & 1818) R-8

62694

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE					
					DAN RYAN J000-2A	FRONTAGE RD I000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	I.T.S. Y032-1F	STRUCTURAL Y007
*	X0322859	WEED CONTROL, PRE-EMERGENT GRANULAR HERBICIDE	POUND	22	22					
	X0323426	SEDIMENT CONTROL, DRAINAGE STRUCTURE INLET FILTER CLEANING	EACH	180	118	62				
*	X0323574	MAINTENANCE OF LIGHTING SYSTEM	CAL MO	18			18			
*	X0323907	COMMUNICATIONS VAULT	EACH	6					6	
	X0324112	BARRIER BASE	FOOT	2003	2003					
*	X0324209	CONDUIT ENCASED, REINFORCED CONCRETE, 3 - 4" DIA., CNC 2 WIDE X 2 HIGH	FOOT	86			86			
*	X0324210	CONDUIT ENCASED, REINFORCED CONCRETE, 4 - 4" DIA., CNC 2 WIDE X 2 HIGH	FOOT	86			86	△1		
*	X0324211	CONDUIT ENCASED, REINFORCED CONCRETE, 5 - 4" DIA., CNC 2 WIDE X 3 HIGH	FOOT	38			38			
*	X0324212	CONDUIT ENCASED, REINFORCED CONCRETE, 6 - 4" DIA., CNC 2 WIDE X 3 HIGH	FOOT	90			90	△1		
*	X0324219	CONDUIT ENCASED, REINFORCED CONCRETE, 2 - 4" DIA., CNC 2 WIDE X 1 HIGH	FOOT	306			306			
	X0324433	LIGHT TOWER SERVICE PAD, 6"	SQ FT	137	137					
*	X0324455	DRILLING AND SETTING SOLDIER PILES (IN SOIL)	CU FT	210013						210013
*	X0324456	DRILLING AND SETTING SOLDIER PILES (IN ROCK)	CU FT	116						116
	X0324697	SOIL STABILIZERS	POUND	29000	29000					
	X0324698	APPLYING DUST SUPPRESSION AGENT	UNIT	11	11					
*	X0324863	COMBINED SEWERS, ESVCP, TYPE 2, 8"	FOOT	7		7				
	X0324864	DRAIN CONNECTIONS	FOOT	83		83				
	X0712400	TEMPORARY PAVEMENT	SQ YD	12721	12721					
	X4021000	TEMPORARY ACCESS (PRIVATE ENTRANCE)	EACH	5		5				
	X4022000	TEMPORARY ACCESS (COMMERCIAL ENTRANCE)	EACH	5		5				
	X4023000	TEMPORARY ACCESS (ROAD)	EACH	5		5				
	X4066426	BITUMINOUS CONCRETE SURFACE COURSE, SUPERPAVE, MIX "D", N70	TON	823		823				
	X4067100	POLYMERIZED LEVELING BINDER (MACHINE METHOD), SUPERPAVE, IL-4.75, N50	TON	427		427				
	X6061001	COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.48	FOOT	5933.5	5933.5					
	X6063401	COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.12	FOOT	6379.5	6379.5					
	X6063600	COMBINATION CONCRETE CURB & GUTTER, TYPE M-4.24	FOOT	5745.5	4625.5	1120.0				
	X6065740	CONCRETE MEDIAN SURFACE, 5" (MODIFIED)	SQ FT	9060		9060				
	X6370920	CONCRETE BARRIER, SINGLE FACE, 42 INCH HEIGHT	FOOT	1199	1199					
	X6370930	CONCRETE BARRIER, DOUBLE FACE, 32 INCH HEIGHT	FOOT	491	491					
	X6640210	TEMPORARY CHAIN LINK FENCE (PORTABLE)	FOOT	11279		11279				
	X6700410	ENGINEER'S FIELD OFFICE, TYPE A (SPECIAL)	CAL MO	15	15					
	X7011015	TRAFFIC CONTROL AND PROTECTION (EXPRESSWAYS)	L SUM	1	1					

* - SPECIALTY ITEM

□ - IDOT PAY CODE SFTY-3N

△ - IDOT PAY CODE Y080

⊙ - NON-PARTICIPATING

△1 Rev. 6-1-05

TY·LIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 9 OF 10

SCALE: NONE | DRAWN BY: MPG

DATE: MARCH 18, 2005 | CHECKED BY: JPA

P:\0231\3\road\cir\a\sqt\task093a.dgn 05/09/2005 03:33:11 PM