F.A.I. RTE.	SECTION	COUNTY	TOTAL SHEETS	SHEET NO.
94	•	COOK	860	12
STA. 2200+00.00	TO STA. 2362+00.00			
FED. ROAD DIST. NO.	ILLINOIS	FED. AID PROJECT		

• (1516.1, 1717 & 1818) R-8

62694

SUMMARY OF QUANTITIES

	CODE NUMBER	ITEM DESCRIPTION	UNIT	TOTAL	URBAN - 90% FEDERAL, 10% STATE					
					DAN RYAN J000-2A	FRONTAGE RD I000-2A	LIGHTING Y030-1E	SIGNING Y002-1C	I.T.S. Y032-1F	STRUCTURAL Y007
*	72400330	REMOVE SIGN PANEL - TYPE 3	SQ FT	108				108		
*	72400720	RELOCATE SIGN PANEL - TYPE 2	SQ FT	20				20		
⊙⊙ *	72700100	STRUCTURAL STEEL SIGN SUPPORT - BREAKAWAY	POUND	3224				3224		
*	72800100	TELESCOPING STEEL SIGN SUPPORT	FOOT	18				18		
*	72900100	METAL POST - TYPE A	FOOT	84				84		
*	72900200	METAL POST - TYPE B	FOOT	264				264		
*	73000100	WOOD SIGN SUPPORT	FOOT	458				458		
*	73000105	WOOD SIGN SUPPORT, SPECIAL	FOOT	102					102	
*	73100100	BASE FOR TELESCOPING STEEL SIGN SUPPORT	EACH	2				2		
*	73300100	OVERHEAD SIGN STRUCTURE - SPAN, TYPE I-A (4'-0" x 4'-6")	FOOT	188				188		
*	73300200	OVERHEAD SIGN STRUCTURE - SPAN, TYPE II-A (4'-6" x 5'-3")	FOOT	552				552		
*	73300300	OVERHEAD SIGN STRUCTURE - SPAN, TYPE III-A (5'-0" x 7'-0")	FOOT	112				112		
*	73302190	OVERHEAD SIGN STRUCTURE - CANTILEVER, TYPE III-C-A (24" x 7'-0")	FOOT	40				40		
*	73304000	OVERHEAD SIGN STRUCTURE - BRIDGE MOUNTED	FOOT	121				121		
*	73305000	OVERHEAD SIGN STRUCTURE WALKWAY	FOOT	584				584		
*	73400100	CONCRETE FOUNDATIONS	CU YD	7				7		
*	73400200	DRILLED SHAFT CONCRETE FOUNDATIONS	CU YD	180				180		
*	73600100	REMOVE OVERHEAD SIGN STRUCTURE - SPAN	EACH	8				8		
*	73600200	REMOVE OVERHEAD SIGN STRUCTURE - CANTILEVER	EACH	3				3		
*	73700100	REMOVE GROUND-MOUNTED SIGN SUPPORT	EACH	3				3		
*	73700200	REMOVE CONCRETE FOUNDATION - GROUND MOUNT	EACH	3				3		
*	73700300	REMOVE CONCRETE FOUNDATION - OVERHEAD	EACH	13				13		
*	78000100	THERMOPLASTIC PAVEMENT MARKING - LETTERS AND SYMBOLS	SQ FT	463		463				
*	78000200	THERMOPLASTIC PAVEMENT MARKING - LINE 4"	FOOT	5016		5016				
*	78000400	THERMOPLASTIC PAVEMENT MARKING - LINE 6"	FOOT	1676		1676				
*	78000500	THERMOPLASTIC PAVEMENT MARKING - LINE 8"	FOOT	1859		1859				
*	78000600	THERMOPLASTIC PAVEMENT MARKING - LINE 12"	FOOT	3123		3123				
*	78000650	THERMOPLASTIC PAVEMENT MARKING - LINE 24"	FOOT	344		344				
*	78005110	EPOXY PAVEMENT MARKING - LINE 4"	FOOT	40849	40849					
*	78005120	EPOXY PAVEMENT MARKING - LINE 5"	FOOT	10202	10202					
*	78005140	EPOXY PAVEMENT MARKING - LINE 8"	FOOT	18370	18370					
*	78005150	EPOXY PAVEMENT MARKING - LINE 12"	FOOT	3845	3845					

⊙⊙ SFTY-3C

* - SPECIALTY ITEM

□ - IDOT PAY CODE SFTY-3N

△ - IDOT PAY CODE Y080

⊙ - NON-PARTICIPATING

TY·LIN INTERNATIONAL

REVISIONS	
NAME	DATE
REVISED	05/06/05
REVISED	04/15/05

ILLINOIS DEPARTMENT OF TRANSPORTATION

F.A.I. 94 (DAN RYAN EXPRESSWAY)

SUMMARY OF QUANTITIES
SHEET 6 OF 10

SCALE: NONE | DRAWN BY: MPG

DATE: MARCH 18, 2005 | CHECKED BY: JPA

P:\0237 3\cad\cl\ts\ts106-3.dgn
05/09/2005 03:33:09 PM